


March 1996

Vol. 20 No. 3

NASA Tech Briefs


The Design/Engineering Technology Digest

CAD INNOVATIONS



**“NASA
News
Briefs”
Debuts**

Compatibility from the



Virtual Instrumentation with Windows 95 and Windows NT

Designed for 32-Bit Windows

Now, more than ever, you can take advantage of Virtual Instrumentation with the latest 32-bit technologies in Windows 95 and Windows NT. Since 1992, we've designed our virtual instrumentation products, such as LabVIEW® and LabWindows®/CVI, specifically for 32-bit operating systems.

Designed for Plug and Play

As you know, Virtual Instrumentation is more than just software. Our DAQ, GPIB, VXI, and serial interface hardware take advantage of our 32-bit device drivers to give you much higher performance. And, with our Windows 95 Plug and Play hardware, system configuration is automatic – gone are the days of wasting time configuring your PC plug-in boards.

Designed for Productivity

The real benefit of Virtual Instrumentation is productivity. That's why you should START today. Our 32-bit software and Plug and Play hardware are available now.

There's no need to slow down your 32-bit operating system with old 16-bit applications.

Designed for You

Choose from our wide variety of software and hardware solutions designed for your individual needs. Whether you prefer LabVIEW graphical programming, LabWindows/CVI for C, or Visual Basic development with ComponentWorks™, we've got a solution for you. We even have menu-driven solutions in VirtualBench™ and Measure™ for Microsoft Excel.

To learn more about Virtual Instrumentation from the company who invented it, give us a call – we'll show you how to START using Virtual Instrumentation today.



Free Information Pack
on migrating to Windows 95
and Windows NT.
Call (800) 433-3488



U.S. Corporate Headquarters • Tel: (512) 794-0100 • Fax: (512) 794-8411 • E-mail: info@natinst.com • WWW: <http://www.natinst.com>



Free Seminar. Call to register for our seminar,
Virtual Instrumentation with Windows 95 and Windows NT.

© Copyright 1996 National Instruments Corporation. All rights reserved. Product and company names listed are trademarks or trade names of their respective companies.

Come to NI Week, the worldwide conference
on Virtual Instrumentation, August 3-8

For More Information Write In No. 550

Location: <http://www.omega.com>

ISO 9001
CERTIFIED
CORPORATE QUALITY

**High Speed
Temperature &
Process Signal
Measurement
System**



Model
OMB-TEMPSCAN-1000A

\$1995

Circle No. 625
or Request Document #6255,
OMEGAfax™ Service

**Microprocessor-Based
Portable Datalogger**

NEW



OM-2000 Series

\$1999

Circle No. 626 or
Request Document #6364,
OMEGAfax™ Service

See us
at the
**Industrial
Expo**
Booth #3000
And Enter Our Daily Drawing!



**Temperature & Temperature/
Humidity Dataloggers**

OM-NOMAD Series
Datalogger

\$135

Circle No. 627
or Request
Document #6358
OMEGAfax™
Service



OMEGA Universal Guide to Data Acquisition and
Computer Interfaces™

**NEW
FREE!**



**Portable Handheld
Datalogger**



**MADE IN
USA**

Model AD128
Datalogger

\$799

Circle No. 628
or Request Document
#6365 OMEGAfax™
Service

To Request The Encyclopedia OMEGA®

Circle No. 629 Or Request
Document #9988, OMEGAfax™ Service,
Dial 1-800-848-4271

OMEGAfax™
OMEGA's 24-Hour-a-Day, On-Demand Publishing Service
DIAL 1-800-848-4271
OMEGAnet™ ON-LINE SERVICE
See OMEGA on the World Wide Web! <http://www.omega.com>
For Sales and Service:
1-800-82-66342™
1-800-TC-OMEGA

Ω OMEGA®



<http://www.omega.com>

e-mail: info@omega.com

© COPYRIGHT 1996 OMEGA ENGINEERING, INC. ALL RIGHTS RESERVED.

OMEGA ENGINEERING, INC. ONE OMEGA DRIVE, P.O. BOX 4047, STAMFORD, CT. 06907-0047

NEW
VISUAL
CADD
2.0




**If Henry Ford Had Used
The Power Of Visual CADD,TM
Things Might Look Different.**

SUPER PRODUCTIVE DRAFTING FOR WINDOWS[®] 95

NUMERA VISUAL CADD 2.0 ESTABLISHES A NEW LEVEL OF CAD PERFORMANCE FOR UNDER \$600. THIS POWERFUL CAD PROGRAM DELIVERS PROFESSIONAL DRAFTING FEATURES, OPEN ARCHITECTURE AND FULL COMPATIBILITY WITH OTHER CAD PACKAGES. IT'S NATIVE FOR 32-BIT WINDOWS[®] 95 AND COMES LOADED WITH NEW FEATURES LIKE MULTIPLE VIEWS, DIRECT PLOT AND WIZARDS. ENJOY ADVANCED, YET SIMPLE EDITING TECHNIQUES THAT LET YOU ADD, SUBTRACT AND INTERSECT TWO OR MORE CROSSING SHAPES. PLUS, IT NOW OFFSETS MULTIPLE ENTITIES.

VISUAL CADD IS MICROSOFT[®] OFFICE COMPATIBLE AND DELIVERS SEAMLESS INTEGRATION WITH CUSTOMIZED COMMANDS ON MENUS, TOOL PALETTES AND KEYBOARD SHORTCUTS. GET FULL READ-WRITE CAPABILITIES FOR AUTOCAD[®]. DWG, DXF FILES AND GENERIC CADD[®]. GCD FILES. THIS IS THE FIRST

OF A NEW GENERATION OF WINDOWS 95 CAD. AS HENRY MIGHT SAY, "THERE'S A VISUAL CADD IN YOUR FUTURE" AND IT'S ONLY \$595!



**VISUAL
CADD**


FOR MORE INFORMATION AND A FREE DEMO, CALL:
1-800-956-2233 EXT. 102
VISIT THE NUMERA HOME PAGE: <http://www.numera.com>
e-mail: info@numera.com

For More Information Write In No. 660

numera
Software

IN-STOCK!

Where Superior Service Begins



***Rated #1 for
Availability of Product!***


Call, write, fax or visit our
web site for your FREE CATALOG today!

Digi-Key®
1-800-344-4539

Digi-Key Corporation, 701 Brooks Ave. South, Thief River Falls, MN 56701 • Fax: 218-681-3380 • <http://www.digikey.com>

For More Information Write In No. 604

To design this kind of performance into a data acquisition board, you'd have to do what our competitors do.



Advanced LabVIEW VIs

Free Windows Data Acquisition Program

Compatible with 5B Series signal conditioners (up to 1024 channels)

On-board ADI DSP

Sustained 1MHz A/D throughput

External Expansion to 4096 channels

Come to us.

For years companies who make data acquisition boards have depended on ADCs, DACs and other components from Analog Devices. Now the best combination of ultra-high performance and low price is available from the acknowledged leader in the field.

Our RTI-2100 Series boards provide solutions for the most exacting test and measurement, process monitoring and control, pilot plant, laboratory and R&D

applications. And when combined with our industry standard line of signal conditioning products, we're the single source you've been looking for in data acquisition.

Take a look at the specs. You'll see what the industry has known for a long time. Our data acquisition boards have quality written all over them.

ANALOG DEVICES

Analog. Digital. Solutions.

RTI-2100 Series Hardware

- 1MHz, 12-bit, 16 Channel A/D (16 channels at 62.5kHz/Channel)
- 4 D/A Channels (2 12-bit, 2 16-bit)
- Dual channel DMA or 16/32-bit Rep String operation with 2k FIFO
- On-board DSP (ADI DSP-2101)
- Samples directly to Windows memory at full A/D speed
- Programmable gain and simultaneous sampling available
- Prices starting at \$1260 (software included!)

RTI-2100 Software Includes

- Windows 3.1 (including Visual BASIC), Windows 95 and DOS drivers
- Complete source code for entire driver system available
- Status for DOS and Status for Windows data acquisition system

Third Party Software Support

- Drivers for LabVIEW, LabWindows/CVI, Labtech Notebook, SnapMaster, TestPoint, DasyLab

One Technology Way, P.O. Box 9106, Norwood, MA 02062-9106
617-255-8100 / 800-426-2564 / ios.sales @ analog.com / AnalogFax™ 1-800-446-6212 document 7081 / www.analog.com

Product and company names listed are trademarks or trade names of their respective companies.

Make quick cash from surplus test equipment.



FREE TEST EQUIPMENT CATALOG

RF & microwave equipment,
spectrum analyzers,
synthesizers, oscilloscopes,
environmental chambers,
power supplies and more!

Calibrated & NIST Traceable Used Equipment,
Factory Authorized New Equipment

RAG Buys Test Equipment

To sell test equipment
you're no longer using,
call RAG
and ask for purchasing.

RAG Electronics, Inc.

1-800-590-3457

To order a FREE catalog call...

2450 Turquoise Circle, Newbury Park, California, U.S.A. 91320-1200 • FAX 805-498-3733 • Tel: 805-498-9933

For More Information Write In No. 508

Contents

NASATechBriefs

Official Publication of the National
Aeronautics and Space Administration

FEATURES

18 NASA NewsBriefs

20 Resource Report: National Technology Transfer Center

TECHNICAL SECTION

22 Special Focus: Computer-Aided Design and Engineering



- 22 Using Aerospace Technology
To Design Orthopedic Implants
- 24 Multidisciplinary Design of Hot
Composite Structures
- 26 Computer-Aided Process Model
for Carbon/Phenolic Materials
- 28 Program for Evaluation of Reliability
of Ceramic Parts
- 33 TSS - Thermal Synthesizer System
- 35 Program Calculates Current Densities
of Electronic Designs
- 35 Computing Operating Characteristics
of Bearing/Shaft Systems

37 Electronic Components and Circuits



- 37 Antennas for Receiving Signals
Broadcast via Satellites
- 38 Split-Waveguide Mounts for Submillimeter-
Wave Multipliers and Harmonic Mixers
- 40 Algorithm for Detecting dc Series Arcs
- 42 Focal-Plane Analysis for Calculating
Antenna Gain

44 Electronic Systems



- 44 Automated Monitoring of Dielectric
Properties of Tree Trunks
- 46 Modular, Hierarchical Learning by
Artificial Neural Networks
- 48 Ground-Based Calibration of a
Microwave Landing System
- 48 Coherent-Phase Monitoring of Cavitation
in Turbomachines

52 Physical Sciences



- 52 Integrated Oxygen-Recovery System
- 54 Selective Oxidizer for Removal of
Carbon Monoxide
- 55 Silicon Carbide Transistor for Detecting
Hydrocarbon Gases
- 56 Swivel Total-Temperature Probe
- 59 Testing Thermophotovoltaic Cells
With Black-Body Radiation

60 Materials




- 60 Skutterudite Compounds for Power
Semiconductor Devices
- 62 Modified Process for Formation of
Silicon Carbide Matrix Composites
- 63 Epitaxial Silicon Doped With Antimony

70 Computer Programs



- 70 Computing Displacements and Strains
From Video Images
- 70 Program Models a Laser Beam Focused
in an Aerosol Spray

(continued on page 8)



Dr. Daniel Carter (right) and Dr. Joseph Ho of NASA's Marshall Space Flight Center examine a three-dimensional mockup and computer simulation of the atomic structure of an important enzyme from a parasite known to cause schistosomiasis, the second leading cause of death worldwide. The discovery may lead to combining drug treatment and preventive vaccines to stop transmission of the disease. For more information on this breakthrough and other NASA developments, see "NASA NewsBriefs," which premieres this month on page 18.

Photo by Emmett L. Given, courtesy of Marshall Space Flight Center.

Make Short Work Of Backup With 200 MB Per Minute Speed.



The CY-8505 is the latest in a long line of 8mm tape drives that have provided reliable, unattended backup to businesses worldwide. Backwards compatible with all earlier models and scalable to a 2.8 TB library, the CY-8505 gives you something that's nice to find in the computer industry: *investment protection*.

The CY-8505 can store 7 GB on a single tape — up to 35 GB with hardware data compression. Two or more drives can work together with our Advanced SCSI Processor to give you *striping, mirroring, off-line copy/verify, cascade, and independent* modes of operation — and speeds of up to 200 MB per minute. Or, choose a tape library for unattended backup of *terabytes* of data.

Plug compatible with virtually every computer system, our 8mm tape drives offer more than performance in a custom configuration.



Our CY-8505 can store up to 7 GB native, up to 35 GB with data compression.

Need to access files quickly?
We offer Accelerated File Access.

**Need hands-free control
of a tape library?**
We've got the Robotic Control Software
to do it.

Need to protect sensitive data?
It's as simple as adding
Data Encryption.

With a MTBF of 160,000 hours and a bit error rate of less than 1 in 10^{17} , our subsystems give you unbeatable reliability and data integrity.

Easy to cost-justify and backed by a two year warranty that includes unlimited in-house technical support from our



Our CY-CHS10A features one or two tape drives and can store up to 385 GB on eleven tapes—without tape handling

engineering group, there's no smarter way to store data — today and tomorrow — than the family of CY-8505 tape subsystems.

Call today
for a custom
configuration and quote at...
(804) 833-9000.

True Compatibility With:

Alliant	Parallel Port
Alpha Micro	PC 386/ix
Altos	PC MS-DOS
Apollo	PC Xenix/Unix
Arix	Pertec
AT&T	PICK
Basic-4	Plexus
Concurrent	Prime
Convergent	Pyramid
Data General	Sequent
DEC	Silicon Graphics
Gould/Encore	STC
HP	Stratus
IBM	Sun
ICL	Texas Instruments
Intergraph	Unisys
Macintosh	Ultimate
McDonnell Douglas	Wang
Motorola	Windows NT
NCR	- and more
NeXT	
Novell	
OS/2	
PS/2	

CYBERNETICS

Tera One • Yorktown, Virginia 23693
Fax: (804) 833-9300

Contents *(continued)*

74 Mechanics



- 74 Refinement of Hexahedral Cells
in Euler Flow Computations
- 76 Sensing Position With Approximately
Constant Contact Force
- 78 Multigrid, Fractional-Step Computation
of Flow
- 80 Bearings Incorporating Deadband Rollers

81 Machinery/Automation



- 81 Helium-Recycling Plant
- 84 Noncavitating Pump for Liquid Helium
- 84 Magnetostrictive Actuators for
Cryogenic Applications

88 Manufacturing/Fabrication



- 88 Manufacturing Superconducting Cables
- 90 Compressor Case Made With Filaments
Wound With V-CAP Resin
- 91 Brazing Dissimilar Metals
- 92 Mathematical Model of Variable-Polarity
Plasma Arc Welding
- 93 Electrical-Discharge Machining
of Perpendicular Passages
- 94 Verifying Removal of Red Penetrant
Dye From Inspected Welds

96 Mathematics and Information



Sciences

- 96 Modified Mean-Pyramid Coding Scheme
- 98 Algorithm for a Self-Growing
Neural Network
- 99 Software for Multivariate Bayesian
Classification
- 100 Fast Parallel Computation of
Multibody Dynamics

DEPARTMENTS

NASA Commercial Technology Team	14
New Product Ideas	16
New Literature	105
New on the Market	106
New on Disk	108
Advertisers Index	111

102 Books and Reports



- 102 Thermal Conductance of Gold Contacts
at Liquid-Helium Temperatures
- 102 Basis and Application of the CARES/LIFE
Computer Program
- 103 Non-Newtonian Effects in Viscous Flows
- 103 Theory of Controlling Spacecraft Motion
With Pulsed Thrusters
- 103 Experimental Study of Rotating
Unbalanced-Mass Actuators

1a-21a Federal Laboratory Electronics Tech Briefs

Follows page 64 in selected editions only.

1b-16b Industry Focus: Motion Control/ Positioning Equipment

Follows page 80 in selected editions only.

On the cover:

Colors represent velocity in this transient simulation of an input valve performed by Ford Motor Company using STAR-CD. EnSight, a postprocessor from Computational Engineering International of Research Triangle Park, NC, was used to visualize and animate the results. For more information on advances in computer-aided design and engineering, see the Special Focus beginning on page 22.

Photo courtesy of Computational Engineering International

This document was prepared under the sponsorship of the National Aeronautics and Space Administration. Neither Associated Business Publications Co., Ltd. nor the United States Government nor any person acting on behalf of the United States Government assumes any liability resulting from the use of the information contained in this document, or warrants that such use will be free from privately owned rights. The U.S. Government does not endorse any commercial product, process, or activity identified in this publication.

Permissions: Authorization to photocopy items for internal or personal use, or the internal or personal use of specific clients, is granted by Associated Business Publications, provided that the flat fee of \$3.00 per copy be paid directly to the Copyright Clearance Center (222 Rosewood Drive, Danvers, MA 01923). For those organizations that have been granted a photocopy license by CCC, a separate system of payment has been arranged. The fee code for users of the Transactional Reporting Service is: ISSN 0145-319X/96 \$3.00+.00.

NASA Tech Briefs, ISSN 0145-319X, USPS 750-070, copyright © 1996 by Associated Business Publications Co., Ltd. Copyright is not claimed for the individual "tech briefs" contained in this publication. The U.S. Government has a paid-up license to exercise all rights under the copyright claimed herein for governmental purposes. NASA Tech Briefs is published monthly by Associated Business Publications Co., Ltd., 317 Madison Ave., Ste. 921, New York, NY 10017-5391. Editorial, sales, production, and circulation offices at 317 Madison Ave., New York, NY 10017-5391. Subscription for non-qualified subscribers in the U.S., Panama Canal Zone, and Puerto Rico, \$75.00 for 1 year; \$125 for 2 years; \$200.00 for 3 years. Single copies \$10.00. Foreign subscriptions one-year U.S. Funds \$195.00. Remit by check, draft, postal, express orders or VISA, MasterCard, and American Express. Other remittances at sender's risk. Address all communications for subscriptions or circulation to NASA Tech Briefs, 317 Madison Ave., New York, NY 10017-5391. Second-class postage paid at New York, NY and additional mailing offices.

POSTMASTER: Please send address changes to NASA Tech Briefs, P.O. Box 10523, Riverton, NJ 08076-0523

For Information on Finite Element Design and Analysis



Stop by Our Place

WWW.ALGOR.COM

Algor's Internet Home is the fastest way to find out about:



Houdini: CAD/FEA Integration with 8-node "Bricks"



Finite Element Design and Analysis Software



Plant and Piping System Design and Analysis Software



Multimedia Products for Engineers (books, videos, etc.)



Speed-Mesh: CAD to 8-node "Brick" Modeling Service



Algor Education Seminars

When you visit you can...

- Learn more about FEA, whether you're a novice, or a "guru"
- Download free software - real software, not just demos
- Find the information you need fast with Algor's Magellan Search Commander
- Compare notes with other engineers through Algor's application illustrations
- Try your hand at a variety of verification problems
- Get the latest update and new product information for Algor customers
- Communicate directly with Algor sales, engineering and development people
- Do something new every time you return

E-mail: info@algor.com

Phone: +1 (412) 967-2700

Fax: +1 (412) 967-2781

For More Information Write In No. 525

Introducing a new way for workstations to think.



PENTIUM[®] PRO
PROCESSOR

It's the Intel Pentium[®] Pro processor. And it's the brains behind some of the most powerful new workstations available.

Whether you're creating 3-D graphics for a hot new Web site or authoring a multimedia title, designing with CAD applications or developing new software,



PENTIUM® PRO
PROCESSOR


Intel's Pentium Pro processor delivers the
The Intel Pentium Pro processor. It's the
stations in a long time. For more information
<http://www.intel.com/>

performance you need.
brightest idea to hit work-
visit our Web site at

intel®
The Computer Inside.™

CONVERT COMPUTER GRAPHICS TO VIDEO

RECORDING, TRANSMISSION,
PROJECTION AND
TELECONFERENCING



RGB/Videolink®

VIDEO SCAN CONVERTERS

- Autosync
- Simple external connections
- Flicker filter
- Optional graphics/video overlay
- Up to 1280 x 1024 pixel input
- Models from \$7,995.00
- Pan & zoom



SPECTRUM®

950 Marina Village Parkway Alameda, CA 94501
Tel: (510) 814-7000 Fax: (510) 814-7026

Published by Associated Business Publications
President/Chief Executive Officer Bill Schnirring
Publisher Joseph T. Pramberger
Chief Editor Linda L. Bell
Editor, Federal Lab Tech Briefs Robert Clark
Production Manager Donna Pituras
Advertising Coordinator Margery Koen
Art Director Lois Erlacher
Production Artist Brian Edgar
Circulation Director Martin J. Horan
Assistant Circulation Director Lori Coppin
Telemarketing Specialist Evelyn Mars
Assistant to Reader Service Manager Damiana Garcia
Sales Support Joanna Lipton

BRIEFS & SUPPORTING LITERATURE: Written and produced for NASA by
Advanced Testing Technologies, Inc., Commack, NY 11725

Technical/Managing Editor Ted Selinsky
Sr. Technical Analyst Dr. Larry Grunberger
Art Manager Eric Starstrom
Administrator/Chief Copy Editor Greg Galitzine
Staff Writers/Editors Dr. Theron Cole, George Watson,
Howard Falk, Gail Pyke
Graphics Robert Simons
Editorial & Production Joan Schmiemann, Caroline Weaver
Becky D. Bentley

NASA:

NASA Tech Briefs are provided by the National Aeronautics and Space
Administration, Technology Transfer Division, Washington, DC:

Administrator Daniel S. Goldin
Director, Commercial Technology Robert Norwood
Deputy Director Carl Ray
Manager, Technology Transfer Office, NASA Center
For AeroSpace Information Walter M. Heiland

ASSOCIATED BUSINESS PUBLICATIONS

317 Madison Avenue, Suite 921, New York, NY 10017-5391
(212) 490-3999 FAX (212) 986-7864

President/Chief Executive Officer Bill Schnirring
Executive Vice President/Chief Operating Officer Domenic A. Mucchetti
Treasurer Joseph T. Pramberger
Credit/Collection Felecia Lahey
Staff Accountant Larry Duze
Trade Show Director Wendy S. Corvi
Exhibition Sales Wayne Pierce
Trade Show Coordinator Tracy A. Wenz
Human Resources Manager Lourdes Del Valle
MIS Manager Ted Morawski
Assistant MIS Manager Pak Tong
MIS Data Entry Roxanne Portella
Office Manager Sylvia Valentin
Mailroom Operations Alfredo Vasquez, Thomas C. Snyder, Rose D'Addozio
Administrative Assistant Christine Saluzzi

NASA TECH BRIEFS ADVERTISING ACCOUNT EXECUTIVES

Headquarters (212) 490-3999
NY, NJ (Area Code 201), Eastern Canada John Waddell
at (212) 490-3999
PA, DE, NJ (Area Code 908, 609), VA, DC, MD, WV Tara Morie
at (610) 640-3118
Eastern MA, NH, ME, RI Paul Gillespie at (508) 429-8907
Bill Doucette at (508) 429-9861
Western MA, CT, VT George Watts
at (802) 875-3310
Southeast, South Central Robert Hubbard
at (910) 299-7754
OH, MI, IN, KY, Western NY Louise Clemens
at (216) 397-7477
IL, WI, MO, IA, MN, ND, SD, NE, KS, Central Canada Melinda Mead
at (312) 296-2040
N. Calif., CO Bill Hague
at (415) 974-1211
WA, OR, ID, MT, WY, Western Canada Bill Madden; Bill Hague
at (206) 858-7575
S. Calif., (Area Codes 909, 818, 805, 213, 310), NV, UT Tom Stillman
at (310) 372-2744
S. Calif., (Area Codes 619, 714), AZ, NM Richard Ayer; Jane Hayward
at (714) 366-9089
Japan Akio Saijo
at 03 (5691) 3335

How To Reach Us On Line

Letters to the editor: ntb_edit@interramp.com

To find out about advertising opportunities:

ntb_advertise@interramp.com

NASA Tech Briefs home page: <http://www.keds.com/ntb>

The Answers to Your Questions...



IDL

Immediately gain insight from your data with IDL, the pioneering software for interactive analysis and application development. If you analyze data from tests, experiments, simulations, or images — or write applications for others to use — IDL will give you clear results faster.

Dramatically improve your productivity using IDL for visual data analysis, rapid prototyping, or application development. Nothing else provides the speed, flexibility, and breadth of built-in functions for access, manipulation, and display of scientific and engineering data.

See results "on the fly" with integrated

graphics, image processing, mathematics, and statistics. Quickly turn your ideas into powerful applications using IDL's high-level, array-oriented programming language and cross-platform GUI tools.

A few lines of IDL code can do the job of hundreds of lines of C or Fortran, without sacrificing flexibility or performance. Plus, you can call functions in other languages or link IDL to your C or Fortran applications.

IDL programs are portable. You can deliver complete solutions on UNIX[®], VMS[™], Windows, Windows NT[™], Macintosh[®], and Power Macintosh, while writing programs only once.


So why waste time starting from scratch? Exploit IDL and find the answers — in less time, with less programming, and less hassle.

SEE THE ANSWERS FOR YOURSELF

For a free evaluation copy, call

303-786-9900

Email: info@rsinc.com/Fax: 303-786-9909

Software  Vision.



Research Systems, Inc.

2995 Wilderness Place
Boulder CO 80301

Research Systems, Inc. is represented by the following distributors: **GERMANY** CREASO, GmbH 49 8105 25055 • **FRANCE** Fast Parallel Solutions 33 1 46 87 25 22 • **UK** Floating Point Systems UK Ltd. 44 734 776333 • **ITALY** Alliant Computer Systems SRL 39 39 6091766 • **JAPAN** Adam Net Ltd. 81 35802 2251 • **BRAZIL** SulSoft 55 51 488 22 57 • **KOREA** InterSys 82 42 869 4746

For More Information Write In No. 577

NASA's R&D efforts produce a robust supply of promising technologies with applications in many industries. A key mechanism in identifying commercial applications for this technology is NASA's national network of commercial technology organizations. The network includes ten NASA field centers, six Regional Technology Transfer Centers (RTTCs), the National Technology Transfer Center (NTTC), business support organizations, and a full tie-in with the Federal Laboratory Consortium (FLC). We encourage all businesses with technical needs to contact the appropriate organizations for more information. For those who have access to the Internet, general information can be accessed with Mosaic software on the NASA Commercial Technology Home Page at URL: <http://nctn.oact.hq.nasa.gov>. Instructions regarding how to acquire the free Mosaic software can be obtained by sending an e-mail request to: innovation@oact.hq.nasa.gov.

NASA's Technology Sources

If you need further information about new technologies presented in *NASA Tech Briefs*, request the Technical Support Package (TSP) indicated at the end of the brief. If a TSP is not available, the Commercial Technology Office at the NASA field center that sponsored the research can provide you with additional information and, if applicable, refer you to the innovator(s). These centers are the source of all NASA-developed technology.

Ames Research Center

Selected technological strengths: Fluid Dynamics; Life Sciences; Earth and Atmospheric Sciences; Information, Communications, and Intelligent Systems; Human Factors.
Syed Shariq
(415) 604-0753
syed_shariq@qm.gate.arc.nasa.gov

Dryden Flight Research Center

Selected technological strengths: Aerodynamics; Aeronautics; Flight Testing; Aeropropulsion; Flight Systems; Thermal Testing; Integrated Systems Test and Validation.
Lee Duke
(805) 258-3119
duke@louie.drrf.nasa.gov

Goddard Space Flight Center

Selected technological strengths: Earth and Planetary Science; Missions; LIDAR; Cryogenic Systems; Tracking; Telemetry; Command.
George Alcorn
(301) 286-5810
galcorn@gscf-mail.nasa.gov

Jet Propulsion Laboratory

Selected technological strengths: Near/Deep-Space Mission Engineering; Microspacecraft; Space Communications; Information Systems; Remote Sensing; Robotics.
Wayne Schober
(818) 354-2240
wayne.r.schober@jpl.nasa.gov

Johnson Space Center

Selected technological strengths: Artificial Intelligence and Human Computer Interface; Life Sciences; Human Space Flight Operations; Avionics; Sensors; Communications.
Hank Davis
(713) 483-0474
hdavis@gp101.jsc.nasa.gov

Kennedy Space Center

Selected technological strengths: Emissions and Contamination Monitoring; Sensors; Corrosion Protection; Bio-Sciences.
Bill Sheehan
(407) 867-2544
billsheehan@ksc.nasa.gov

Langley Research Center

Selected technological strengths: Aerodynamics; Flight Systems; Materials; Structures; Sensors; Measurements; Information Sciences.
Charlie Blankenship
(804) 864-6005
c.p.blankenship@larc.nasa.gov

Lewis Research Center

Selected technological strengths: Aeropropulsion; Energy Technology; High Temperature Materials Research.
Ann Heyward
(216) 433-3484
ann.o.heyward@lerc.nasa.gov

Marshall Space Flight Center

Selected technological strengths: Materials; Manufacturing; Nondestructive Evaluation; Biotechnology; Space Propulsion; Controls and Dynamics; Structures; Microgravity Processing.
Harry Craft
(800) USA-NASA
susan.van.ark@msfc.nasa.gov

Stennis Space Center

Selected technological strengths: Propulsion Systems; Test/Monitoring; Remote Sensing; Nonintrusive Instrumentation.
Anne Johnson
(601) 688-3757
ajohnson@ssc.nasa.gov

NASA Program Offices

At NASA Headquarters there are seven major program offices that develop and oversee technology projects of potential interest to industry. The street address for these strategic business units is: NASA Headquarters, 300 E St. SW, Washington, DC 20546.

Gene Pawlik
Small Business Innovation Research Program (SBIR)
(202) 358-4661
gpawlik@oact.hq.nasa.gov

Robert Norwood
Office of Space Access and Technology (Code X)
(202) 358-2320
rnorwood@oact.hq.nasa.gov

Philip Hodge
Office of Space Flight (Code M)
(202) 358-1417
phodge@osfms1.hq.nasa.gov

Gerald Johnson
Office of Aeronautics (Code R)
(202) 358-4711
g.johnson@aeromail.hq.nasa.gov

Bill Smith
Office of Space Sciences (Code S)
(202) 358-2473
wsmith@sm.ms.ossa.hq.nasa.gov

Bert Hansen
Office of Microgravity Science Applications (Code U)
(202) 358-1958
bhansen@gm.olmsa.hq.nasa.gov

Granville Paules
Office of Mission to Planet Earth (Code Y)
(202) 358-0706
gpaules@mtpe.hq.nasa.gov

NASA-Sponsored Commercial Technology Organizations

These organizations were established to provide rapid access to NASA and other federal R&D and foster collaboration between public and private sector organizations. They also can direct you to the appropriate point of contact within the Federal Laboratory Consortium.

Lee Rivers
National Technology Transfer Center
(800) 678-6882

Dr. William Gasko
Center for Technology Commercialization
(800) 472-6785 or
(508) 870-0042

Gary Sera
Mid-Continent Technology Transfer Center
Texas A&M University
(800) 472-6785 or
(409) 845-8762

Chris Coburn
Great Lakes Industrial Technology Center
Battelle Memorial Institute
(800) 472-6785 or
(216) 734-0094

Robert Stark
Far-West Technology Transfer Center
University of Southern California
(800) 642-2872 or
(213) 743-2353

J. Ronald Thornton
Southern Technology Applications Center
University of Florida
(800) 472-6785 or
(904) 462-3913

Lani S. Hummel
Mid-Atlantic Technology Applications Center
University of Pittsburgh
(800) 472-6785 or
(412) 648-7000

NASA's Business Facilitators

NASA has established several organizations whose objectives are to establish joint sponsored research agreements and incubate small start-up companies with significant business promise.

Dr. Stephen Gomes
American Technology Initiative
Menlo Park, CA
(415) 325-5353

John Gee
Ames Technology Commercialization Center
Sunnyvale, CA
(408) 734-4700


Jill Fabricant
Johnson Technology Commercialization Center
Houston, TX
(713) 335-1200

Dan Morrison
Mississippi Enterprise for Technology
Stennis Space Center, MS
(800) 746-4699

Easy Access To The FLC: Call (206) 683-1005 for the name of the Federal Laboratory Consortium Regional Coordinator in your area. The Regional Coordinator, working with the FLC Locator, can help you locate a specific laboratory to respond to your needs.

If you are interested in information, applications, and services relating to satellite and aerial data for Earth resources, contact: Dr. Stan Morain, **Earth Analysis Center**, (505) 277-3622. For software developed with NASA funding, contact **NASA's Computer Software Management and Information Center (COSMIC)** at phone: (706) 542-3265; Fax: (706) 542-4807; E-mail: <http://www.cosmic.uga.edu> or service@cosmic.uga.edu. If you have questions...NASA's Center for AeroSpace Information can answer questions about NASA's Commercial Technology Network and its services and documents. Use the Feedback Card in this issue or call (410) 859-5300, ext. 245.

PCI-EZ™ is the standard—others will follow.



Packed with performance, it's the first PCI data acquisition board for your Pentium™

The rest must follow the leader.

PCI-EZ is a cutting-edge series of low-cost, multi-function, data acquisition boards for the PCI Bus within your PC. You'll clearly see the difference in performance.

Filled with benefits.

One of the greatest advantages to the PCI Bus is that it operates at a higher priority than other peripheral buses, giving PCI-compatible boards first shot at system resources like RAM, the hard disk, and the CPU. Also,

PCI's higher bandwidth allows all subsystems on a board to operate simultaneously, resulting in speeds up to 15 times that of the ISA Bus. In addition, PCI devices can access memory without involving the CPU, letting you run other applications or perform data processing concurrent with PCI data acquisition. All of these benefits, combined with PCI's support of true Plug 'N Play, gives you a leading advantage to develop first-rate test and measurement applications.

Standards following standards:
PCI-EZ supports DT-Open Layers.

DT-Open Layers is a set of open standards for developing integrated, modular software under Microsoft Windows. Not only does it allow access to our hardware at the touch of a button, but it ensures support of all hardware upgrades and new functions for the future—including those on standard PC busses like PCI, ISA and PCMCIA. That's why we call DT-Open Layers the insurance policy that comes with every Data Translation purchase.

Model	Channels	Analog Inputs		Analog Outputs		Digital I/O Lines
		Resolution (bits)	Gain	Throughput (kHz)	Channels	
DT3001	16SE/8DI	12	1, 2, 4, 8	330	2 DACs	8
DT3002	32SE/16DI	12	1, 2, 4, 8	330	—	8
DT3003	64SE/32DI	12	1, 2, 4, 8	330	2 DACs	8
New	16SE/8DI	16	1, 2, 4, 8	100	2 DACs	8

So call us today, and discover for yourself why the competition follows our standards.

1-800-525-8528

INTERNET: <http://www.datx.com>



World Headquarters: (508) 481-3700, UK Headquarters: (01734) 793838, Germany Headquarters: (07142) 95 31-0, Italy Headquarters: (030) 2425696.

Sales Offices: Argentina 322-3791; Australia (02) 9979 5643; Austria 13697660; Belgium 02-5 69 56 47; Brazil (011) 564-6024; Canada (508) 481-3700, (416) 625-1907; Chile 638 7806; China 8428276, 10 833 1145; Denmark 48 14 14 88; Finland (90) 351 1800; France (1) 69 07 92 12; Greece (301) 3846200; Hong Kong 2515-0018; India (22) 2831040; Israel 9-581860; Japan (03) 5489-3871; Korea (02) 718-9521; Malaysia (03) 261 6786; Mexico (5) 575-6091; The Netherlands 010-47 95 700; New Zealand 94158362; Norway 2243 4150; Portugal 01/793 48 34; Singapore 773 4300; South Africa 12803 7680; Spain 91-555.8112; Sweden 08-765 02 80; Switzerland 01/908 13 13; Taiwan (02) 561-2211; Thailand (02) 668-5080; Turkey (21) 288 6213 10/10/95

For More Information Write In No. 530



New Product Ideas

New Product Ideas are just a few of the many innovations described in this issue of *NASA Tech Briefs* and having promising commercial applications. Each is discussed further on the referenced page

in the appropriate section in this issue. If you are interested in developing a product from these or other NASA innovations, you can receive further technical information by requesting

the TSP referenced at the end of the full-length article or by writing the Commercial Technology Office of the sponsoring NASA center (see page 14).

Integrated Oxygen-Recovery System

A developmental system revitalizes breathing air in an enclosed environment by converting carbon dioxide and water to oxygen and methane. Such a system

is smaller, weighs less, and consumes less power than conventional systems using an electrolyzer and Sabatier reactor as distinct components. (See page 52.)

Selective Oxidizer for Removal of Carbon Monoxide

Multiple catalytic stages at progressively lower temperatures operate without becoming poisoned. Here most of the carbon monoxide is oxidized in a stream of reformed fuel gas that is fed to a low-temperature fuel cell. (See page 54.)

Silicon Carbide Transistor for Detecting Hydrocarbon Gases

A proposed transistor would be specifically designed for measuring concentrations of hydrocarbon gases. Such devices have numerous potential applications in automotive, industrial, aeronautic, and environmental monitoring applications. (See page 55.)

Sensing Position With Approximately Constant Contact Force

A computer-controlled system uses a number of linear variable-differential transformers to measure axial positions of selected points on the surface of a lens, mirror, or other precise optical component with a high finish. The pneumatic pressure can extend the probes in 0.006-in. (0.15-mm) increments. (See page 76.)

Helium-Recycling Plant

A proposed system would recover and store helium gas for reuse. Helium would be conserved with little contamination or back pressure on the source. Conservation of helium is becoming an important issue that could affect the development of new technologies and scientific discoveries in the 21st century. (See page 81.)

FieldWorks Field WorkStations™ have been put to the challenge by the World's most grueling and demanding work environments; from ice core testing in the sub-zero climates of Antarctica to testing nuclear reactor power plants world-wide to aiding corporate America's large field sales and field service fleets. Our attention to detail, MIL-SPEC rugged design and usability makes the FieldWorks computer line the logical choice in mission critical applications as well as your own specialized application. FieldWorks has met the challenge of today's most severe working environments.

133 MHz Pentium...
ISA/PCI Slots...
CD-ROM...PCMCIA...
Call today for an
information kit
on the complete
FieldWorks
Rugged product line.

**Rugged
Field
Computing
Starts
Here!**



Sales: 1-800-588-9144

9961 Valley View Road
Eden Prairie, MN, USA 55344
Phone: (612) 947-0856
Fax: (612) 947-0859

fieldworks
inc.

SIMULINK[®]


The express connection between concept and code.

Announcing a software innovation for developers of DSP-based systems: SIMULINK now bridges the gap between DSP research and product design.


Built on the powerful MATLAB Technical Computing Environment, SIMULINK integrates algorithm development, simulation, and code generation to speed up DSP product development on your UNIX workstation, PC, or Macintosh.

Interactive DSP simulation

SIMULINK's new DSP Blockset gives you over 100 signal processing and vector math functions within an interactive block-diagram environment.



This MATLAB spectrogram shows the output of an adaptive filtering simulation. The filter improves the signal-to-noise ratio by 21dB within 200 msec and by 40dB when fully adapted.



Visual programming with SIMULINK's drag-and-drop user interface makes it easy to create hierarchical simulations of DSP systems such as this adaptive FIR noise canceling filter.

Just drag and drop icons into block diagrams to rapidly create and simulate sophisticated DSP designs.

With SIMULINK, you can take advantage of a wide range of built-in DSP techniques, or add your own custom algorithms without low-level programming.

Integrated software for faster design

SIMULINK's DSP design capability extends the unrivaled power of MATLAB to model, analyze, and visualize signal data and DSP algorithms. Together, they create the express connection that puts your ideas on the fast track to implementation.

NEW!
DSP Blockset

SIMULINK DSP Highlights

- Intuitive block-diagram DSP simulation
 - Spectral analysis
 - Filter design and implementation
 - Multi-rate signal processing
 - Vector and complex math
- Portable C code generation with Real-Time Workshop[™]
- Integration with MATLAB's high-level algorithm development tools
- Runs on workstation, PC, and Macintosh

Real-time code generation

SIMULINK's Real-Time Workshop generates portable C code from block diagrams. With the click of your mouse, you can streamline prototyping and simplify implementation on your programmable DSP hardware.



Generated C code can run on a variety of DSP hardware.

Call today for a free technical brief that will show you how SIMULINK speeds up DSP design.

508-647-7000

The
**MATH
WORKS**
Inc.

24 Prime Park Way/Natick, MA 01760
Phone: (508) 647-7000 Fax: (508) 647-7101
E-mail: info@mathworks.com
Web: <http://www.mathworks.com>

The MathWorks is represented in the following countries:
Australia: +61-2-9224311 • France: +33-1-4534-2391 • Germany: +49-89-470750
India: +91-80-2260260 • Israel: +972-3-5415151 • Italy: +39-11-2485-332
Japan: +81-3-5978-5410 • Korea: +82-2-517-1257 • Poland: +48-13-36-32-18
Portugal: +34-3-415-4904 • Scandinavia: +46-8-15-30-22 • Singapore: +65-7477-234
Spain: +34-3-415-4904 • Switzerland: +41-31-998-44-1 • Taiwan: +886-2-501-8787
For Belgium, Luxembourg, The Netherlands, United Kingdom and Republic of Ireland call Cambridge Control, Ltd. +44-1223-425-200 or Rapid Data, Ltd. +44-1903-821-266

MATLAB and SIMULINK are registered trademarks, and Real-Time Workshop is a trademark of The MathWorks, Inc.

NASA NEWS BRIEFS

Lewis Research Center has signed a Space Act Agreement with the Cleveland Clinic, establishing a three-year relationship for cooperative research. This marks the first agreement between NASA and an academic medical center.

Under the agreement, Lewis and the Cleveland Clinic Foundation's Department of Biomedical Engineering will engage in mutually beneficial research to develop products and technologies, and to solve technological problems related to orthopedic and cardiovascular devices, medical imaging, and microelectrical mechanical systems. The two are currently collaborating on the development of an artificial heart pump and computer-assisted minimally invasive surgery.

In another Space Act Agreement, Kirby Co. of Cleveland, OH, is working with Lewis to apply NASA technology to the company's line of vacuum cleaners. Using Lewis facilities and expertise, Kirby is researching advanced operational concepts such as particle flow behavior and vibration, which are critical to improving vacuum cleaner performance. Nozzle tests using a Lewis-developed technique called Stereo Imaging Velocity will enable Kirby researchers to accurately characterize fluid and air experiments. Kirby also is using Lewis' holography equipment to study vibration modes of jet engine fans.

For more information, contact the Lewis Office of Community and Media Relations at 216-433-2888.

The new \$250-million Mission Control Center (right) is operating at NASA's Johnson Space Center in Houston. Designed, implemented, and integrated by Loral Space Information Systems of Houston, the center handles command and control of all NASA manned space vehicles. Loral architecture and infrastructure software provides all basic telemetry, trajectory, and command capabilities for planning and real-time control of space shuttle and international space station operations. The center uses approximately 90% commercial off-the-shelf (COTS) hardware and 30% COTS software, which are expected to lower NASA's operating costs by \$20 million per year.

Spacecraft flight controllers use new consoles that provide integrated voice, video, and data via one of the world's

largest Fiber Distributed Data Interface local area networks. The combined development and operational environments can store 3 terabytes of data, the equivalent of the information contained in a stack of paper 36.4 miles high. Combined shuttle and space station operations in the new center require only 197 workstations, compared with the 204 required previously. By 1999, the facility is expected to operate using only 700 equipment racks, compared to the 1400 used now for shuttle support alone.

For more information, contact Lisa Koppel at Loral Corp.; 703-416-5542.

Marshall Space Flight Center scientists have determined the three-dimensional atomic structure of an important enzyme from a species of parasite known to cause schistosomiasis, a disease that affects 200 to 300 million people worldwide for which there is no vaccine. The disease is second only to malaria in causing death. Victims become infected by any of four parasitic flatworms or flukes when wading or swimming in contaminated fresh water.

Dr. Daniel Carter, research director and chief of Marshall's Biophysics and Advanced Materials Branch of the Space Sciences Laboratory, said that this step "seems to offer the most potential for developing vaccines that protect people against the entire species of schistosomiasis parasites, not just one species." The determination of the enzyme structure offers the possibility of combining such

techniques as the use of disease-fighting drugs with preventive vaccines to form a barrier against the transmission of the disease.

For more information, contact Dr. Daniel Carter at 205-544-5492.

Marshall scientists have determined that a NASA lightning detector may be used to identify the formation of tornadoes and severe storms from space. Using data from the Optical Transient Detector (OTD), Marshall researchers are building a global picture of the role lightning plays in the atmosphere, including lightning produced by large storms. The OTD, which was launched last year, has been observing lightning flashes as it passes over severe storms. The "flashrate" of lightning may provide, in conjunction with other detection systems, an indication of the formation of tornadoes.

For more information, contact the Marshall Public Affairs office at 205-544-0031.

NASA's Jet Propulsion Laboratory has developed a new infrared detector array that uses highly sensitive quantum-well IR photodetectors (QWIPs) to cover longer wavelengths than those possible with conventional mercury cadmium telluride and indium antimonide arrays. With the new technology, doctors may detect tumors using thermographic analysis and pilots may be able to make better landings



with improved night vision equipment. Other possible uses are pollution and weather pattern monitoring, drug and law enforcement applications, search and rescue, and industrial process control.

JPL has demonstrated two IR cameras using QWIP arrays for ground-based and space-based imaging. The lab currently is working with Amber, a Raytheon company in Goleta, GA, to develop QWIPs for new portable IR cameras.

For more information, contact Tom Hamilton of JPL at 818-354-7344.

SY Technology of Huntsville, AL, in partnership with MicroBioMed, the University of Kansas Medical Center, and the optics division of the Coherent Auburn group, was awarded a \$600,000 Phase II Small Business Innovation Research (SBIR) grant from NASA to develop two diffractive optics-based systems for NASA and the medical community.

The first of the systems will be used by NASA to fabricate complex optical components which previously were not possible. The new components will be used in space telescopes and for making test optics to verify the performance of NASA-developed optical systems. The second system will demonstrate advanced surgi-

cal techniques which may eliminate the need for sutures in corneal transplants.

For more information, contact Greg Sharp of SY Technology at 205-722-9095.

NASA's Mid-Continent Technology Transfer Center (MCTTC) is attempting to locate capital sourcing for the Attitude Adjuster, an automatic adjustable weight system for scuba divers developed by Joe Nicklo of Think Tank Technologies in Houston, TX. The company already has received requests for prototypes from the U.S. Navy. The device consists of two tubes that fasten lengthwise to the diver's air tank. They are partially filled with lead shot that adjusts automatically with the diver's position, or attitude. The MCTTC has secured testing of the device at Marshall Space Flight Center's Weightlessness Environmental Training Facility.

For more information, contact Joe Nicklo of Think Tank Technologies at 713-933-9875.

The Air & Space Network, a premium television network devoted entirely to aviation and space programming, is scheduled to debut in May. The network will offer avia-


tion news broadcasts and talk shows, including a daily aviation weather program; an aviation call-in program; coverage of military air shows; college aviation courses; a shopping program; educational, safety, aircraft, equipment, NTSB accident analysis, and legislative programming; and live coverage of NASA's manned and unmanned space flight, including space shuttle and other space exploration missions.

Entertainment services will include historic documentaries, biographies, feature films, air shows, special events, and aerospace news. Much of the programming will come from archives of federal and state governments, private foundations, aviation associations, and independent producers. The network will debut as a premium/mini-pay service offered on Direct Broadcast Satellite (DBS) and analog C-band satellite TV. Cable, wireless, and traditional broadcast channels will be added as capacity becomes available.

Computer-interactive services via telephone will be offered, including games, downloadable weather fax service, an air and space calendar of events, downloadable software, chat lines and bulletin boards, merchandise catalogs, and guides to services and products.

For more information, contact Matthew Simek of The Air & Space Network at 503-224-9821.

HIGH TEMPERATURE FURNACE INSULATION



Call, Fax or Write For More Information

PREMIUM GRADE ALUMINA INSULATION


**SUPERIOR HOT STRENGTH
USES TO 1820C (3308F)
LOW K FACTOR
LIGHTWEIGHT
EASILY MACHINED**

**STANDARD BOARDS &
CYLINDERS
CUSTOM SHAPES &
INSULATION PACKAGES**

**Zircar**
FIBROUS CERAMICS

ZIRCAR Products, Inc.

110 North Main St., P.O. Box 458
Florida, NY 10921-0458
Phone 914-651-4481
Fax 914-651-3192



The National Technology Transfer Center opened its new headquarters building on the campus of Wheeling Jesuit College in May 1995.

NATIONAL TECHNOLOGY TRANSFER CENTER: *Serving the Nation's Industrial Competitiveness*

It might seem a long leap from the federal laboratory network to the local dry-cleaning establishment, but bringing the two together is just one of the more unusual successes of the National Technology Transfer Center (NTTC). Since its establishment in 1990, the center has acted on more than 10,000 technical requests and recorded more than 100,000 log-ons to its electronic information system.

Funded by NASA, and with additional support from the Ballistic Missile Defense Organization, the U.S. Navy, and other federal agencies, the NTTC has its headquarters on the campus of Wheeling Jesuit College in Wheeling, WV. From there it extends its reach throughout the country, drawing on the expertise of more than 700 laboratories and thousands of scientists, engineers, and managers who make up the Federal Laboratory Consortium. NTTC also teams with NASA's Regional Technology Transfer Centers (RTTCs)—six offices nationwide that assist local industry in technology evaluation and commercialization, as well as market assessment and other areas of business expertise.

NTTC's programs run the gamut of technology transfer initiatives. A key service is called the National Gateway, pro-

viding callers from business and industry free access to technology and expertise from the NASA labs and other federally funded research facilities. This is done through NTTC technology access agents, who, once apprised of a technical challenge or area of interest, search the proper databases, contact the labs, and often put the inquirer in touch with the individual experts who are the best resources.

But if the inquirer simply wants to browse through the ideas and technical information available from federal sources, there is Business Gold, a free service available via the Internet or direct modem connect. Operating 24 hours a day, NTTC's electronic bulletin board provides information that can be downloaded onto the user's computer free of all charges except for the phone lines. Included are descriptions of new technologies available for licensing and commercialization; NASA RTTC contacts; current SBIR, Technology Reinvestment Program, and similar solicitations; technology transfer conference calendars; information from government software centers; and more.

Forging Partnerships

NTTC acts either directly or through the regional network to facilitate technology transfer. When Hi-Shear Technology Corp. of Torrance, CA, was looking for a new design for the power unit for Lifeshear, a cutting tool for extracting auto accident victims from wreckage, NTTC provided the immediate link to NASA's Jet Propulsion Laboratory. An advanced technology for powering an initiator for multi-stage rockets and explosive bolts was co-developed for dual use under a JPL-managed Technology Reinvestment Project award to Hi-Shear. Federal Emergency Management Agency rescue workers later used Lifeshear at the Oklahoma City bombing site. (See "Mission Accomplished," *NASA Tech Briefs*, August 1995, Vol. 19, No. 8, page 20.)

Using the regional connection, NTTC referred Jay Carter Jr., president of CarterCopters Inc. of Wichita Falls, TX, and designer of a unique gyroplane, to the Mid-Continent Technology Transfer Center (MCTTC) in Texas. After MCTTC's evaluation, Carter was directed to NASA Ames Research Center officials, who helped him draw up a Small Business Innovation Research proposal that won a \$70,000 award from NASA last fall. He hopes the CarterCopter will fly as early as the end of the year.

The Office of Law Enforcement Technology Commercialization (OLETC) is another recent example of NTTC's successful partnerships. The center hosts OLETC, a joint undertaking with NASA

and the Justice Department's National Institute of Justice. Through it, NTTC funnels state-of-the-art law-enforcement product ideas to the manufacturing community, and arranges for rapid prototyping at test facilities. The center also provides timely funding information to law-enforcement and criminal justice organizations throughout the country to help them acquire advanced technology.

OLETC is pursuing several innovative projects, including a remote-controlled retractable roadway barrier strip that deflates tires, thus eliminating the hazards of high-speed auto chases; a "smart" gun that can be fired only by its owner; a pepper spray launcher-dispenser intended for use in efforts to free hostages; a disabling net and launcher system that deploys a lightweight net to trap escaping suspects; and concealed-weapons detection systems.

Last year the partners in OLETC presented Law Enforcement Technology Innovation Awards to Idaho National Engineering Laboratory (INEL) and 3M Law Enforcement Products. INEL designed a rear-seat air bag for patrol vehicles that restrains a violent apprehended suspect, preventing him from injuring himself or others or damaging the vehicle. 3M's fingerprint visualization system (FVIS) is a small kit that detects prints left on nonporous surfaces at a crime scene by dispensing heated cyanoacrylate vapor over an area via a self-igniting wand.

Another critical function of OLETC is helping law-enforcement agencies find ways to pay for innovative equipment. The office has compiled a guide to federal law-enforcement technology funding sources that provides eligibility requirements, criteria for selecting proposals, and examples of funded projects.

Training for the Future

Education and training are significant aspects of NTTC's activities. Idea Contact™, a new program directed at federal lab and agency personnel, teaches scientists, engineers, and managers how to evaluate a technical innovation for its manufacturability, marketability, and usefulness to the commercial world. For small and medium-sized manufacturers, NTTC provides technology-driven industrial extension programs, concentrating on the use of federal technologies as a catalyst for economic revitalization. As part of the Technology Reinvestment Program, NTTC received a grant to work with the Pennsylvania Technical Assistance Program, Rensselaer Polytechnic Institute, and other manufacturing assistance groups to create a national curriculum for training industrial extension agents. Finally, in cooperation with Wheeling Jesuit College, NTTC has developed courses of study for bachelor

and master of science degrees in technology management, innovation, commercialization, and technology transfer.

As for the dry-cleaning innovation, David Porter, president of Garment Care Inc. in Kansas City, came to NTTC with an idea that would eliminate the environmentally troublesome dry-cleaning chemical perchloroethylene. His rack-conveyer system would carry soiled clothes through a water-based ultrasound bath, eliminating the need for the traditional chemical. An NTTC agent searched the center's technology database and came up with a potential research partner: the Kansas City Department of Agriculture facility operated by AlliedSignal. Researchers there responded with 40 hours of free discussion and preliminary tests on swatches of material. The ultimate result was a two-year Department of Energy "mini-CRADA" award of \$50,000 for full-fledged research and development.

The dry-cleaning industry "wants innovation that not only takes care of our environment, but also our wallets," Porter says. "That's why we're excited about the technology transfer possibilities now before us. NTTC has, in my opinion, great networking potential for small business."



At the Technology 2005 conference and exhibition in Chicago late last year, NASA Administrator Daniel Goldin (right) spoke to Jay Carter Jr. about the CarterCopter gyroplane, a model of which is seen behind them. NTTC's referral of Carter to NASA sources resulted in a Small Business Innovation Research grant. (Photo: Bill Ingalls/NASA)

To access the National Gateway, phone 1-800-678-6882; to reach Business Gold, use Internet: URL <http://www.nttc.edu>. For more information on the NTTC, phone Jim Reed, Deputy Director of Marketing,

at (304) 243-4400. OLETC is searching for 1996 Technology Innovation Award candidates: call NTTC at 800-678-6882 for more information.

Pittman offers big performance in a compact package. Choose from four series of DC motors, 1.18" to 2.13" diameter. Continuous-duty torques from 1.2 to 50 oz.-in. Options include spur or planetary gearheads, optical encoders, EMI filters, and other value-added assemblies.

Call 215-256-6601

Fax 215-256-1338



PITTMAN®
HARLEYSVILLE, PA 19438-0003 USA
A DIVISION OF PENN ENGINEERING & MANUFACTURING CORP.

© Pittman, 1995 G10



Special Focus: Computer-Aided Design and Engineering

Using Aerospace Technology To Design Orthopedic Implants

Methods for optimizing designs of turboprop blades have been applied to prosthetic knee joints.

Lewis Research Center, Cleveland, Ohio

Technology originally developed to optimize the designs of composite-material aerospace structural components has found a new use in efforts to develop a method for optimizing the designs of orthopedic implants. Thus far, the development effort has focused on designing knee implants, but the long-term goal of this effort is to develop a method for optimizing the designs of orthopedic implants in general.


The prototype method provides for tailoring the shapes of the tibial components of a total-knee-replacement implant for optimal interaction within the environment of the tibia. The shapes of the components of the implant are opti-

mized such that the stresses in the bone are distributed more favorably than they otherwise would be, thereby minimizing the degradation of bone, improving the mechanical integrity of the bone/implant system, and preventing failures of the components of the implant.

The computer code used in the prototype method is an adapted version of the Structural Tailoring of Advanced Turboprops (STAT) computer code. Despite the obvious differences between laminated composite turboprop blades on the one hand and bone/implant systems on the other hand, the essential features of STAT are applicable to both; these features include composite-

mechanics, finite-element-analysis, and structural-optimization capabilities. An essential part of the optimization procedure is mathematical modeling of the quasi-static mechanical response of the laminated tissue structure of the upper end of the tibia. This modeling involves utilization of the finite-element-modeling capability of STAT and, in particular, laminated-plate models (see figure) as a compromise between overly simplistic two-dimensional models and fully complex three-dimensional models.

The analysis of stresses and strains takes place in three stages. In the first stage, stiffness matrices that represent the characteristics of the discrete bone



Laminated-Plate Models are used in the initial finite-element analysis of the bone/implant system.



Introducing Sun Ultra 1. A box so revolutionary, it allows you to think outside of it.

Forget incremental
advancements. Forget
compromises. In short,
forget everyone else.

UltraComputing™ is here, and
the only way you can get it is
the Sun™ Ultra™ 1. The new workstation
that converges all the best computing
technology. A powerful 64-bit processor, real-time
video and audio, imaging, 2D and 3D graphics, and the
ability to run over 10,000 existing applications. It even offers
networking that's 10 times faster than today's standards.
And with supercomputing power on your desktop, you can
collaborate in ways once thought impossible. Sun Ultra 1. You'll
never look at computing the same way again. To learn more,
call 1-800-786-0785, Ext. 360. Or see us at <http://www.sun.com>



layers are synthesized. Integration through the sagittal plane (thickness) provides the equivalent local through-the-thickness extensional and flexural stiffness matrices of the laminate, relating the generalized (average) laminate stresses to the generalized (average) laminate strains. In the second stage, the global static response is obtained via finite-element analysis with discretized nodal displacements in the frontal plane. The third and final stage involves the back-calculation of stresses within the bone and the implant components from the calculated global structural response. The generalized strains in the frontal plane are calculated, then the strain in each discretized layer is calculated. The stresses in the discretized material layers are then calculated from the layer strains.

The design parameters subject to optimization include those that specify the

shape of a post and the thickness of a metal backing tray that are parts of the implant. The basic criterion for optimization of these parameters is assumed to be an acceptable state of stress in the bone/implant composite structure. For the tibial component, the most likely mode of failure is aseptic loosening, which involves the resorption of the bone adjacent to the implant. This is attributed in many cases to the stress-induced adaptation of the bone after the implantation surgery in response to the altered stress field induced exclusively by the presence of the implant. Thus, the optimal-design goal becomes the minimization of undesirable atrophy of the adjacent bone, or, in a positive sense, the creation of a favorable stress field in the bone.

Accordingly, the optimization-and-design procedure is an iterative one in which the shape of the post and the

thickness of the metal backing tray are made to evolve in small increments, after each of which a finite-element analysis is performed to determine the new stress field. That information obtained at each such step of the design can then be used to direct the next design move in an effort to reach the optimum design by minimizing an objective function. The objective function chosen initially was the maximum specific distortion energy near the bone/implant interface.

This work was done by D. A. Saravanos, P. J. Mraz, and D. T. Davy of Case Western Reserve University for Lewis Research Center. For further information, write in 65 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Lewis Research Center; (216) 433-2320. Refer to LEW-16093.



Multidisciplinary Design of Hot Composite Structures

A computer code incorporates modules for simulation and analysis by traditionally separate disciplines.

Lewis Research Center, Cleveland, Ohio

A unified computer code has been developed to implement a multidisciplinary approach to the design and analysis of composite-material structures that must withstand high temperatures. The code is modular: it includes an executive module that communicates with and coordinates other modules that perform calculations pertaining to traditionally separate disciplines like those of acoustics, structural vibrations, structural loads, and thermal effects (see Figure 1).

An essential feature of the multidisciplinary approach is finite-element numerical simulation of the relevant physical phenomena according to the applicable disciplines. The same finite-element mesh is used in the thermal, vibrational, and structural analyses; this minimizes data-preparation time and eliminates the errors incurred in transforming temperatures from one finite-element mesh to another.

The integrated multidisciplinary simulation procedure is founded, in part, on recognition of the essential complexity and nonlinearity of the coupled heat-transfer, geometrical, material-property, structural, acoustic and nonacoustic vibrational, and environmental effects. For example, the thermal, mechanical, and acoustic properties of a composite material are nonlinear functions of tem-

perature and other environmental parameters. Accordingly, the unified program includes a module that contains the Integrated Composite Analyzer (ICAN) computer program, which implements micromechanics- and laminate-oriented mathematical models of composite

materials to compute both the macroscale and the local microscale hygro/thermo/mechanical responses of composite materials, including effects of deterioration of properties with time.

Figure 2 illustrates the multidisciplinary design-tailoring and analysis proce-





Figure 1. A **Unified Computer Code** includes modules for simulation and analysis by traditionally separate disciplines.

Go ahead.

Think the impossible.



To us, it is, at 6,500 metric tons, the largest, the most powerful, the most advanced aluminum extrusion press in the world.

To you, it is the world's most sophisticated idea machine. It opens new possibilities. It shortens the distance from concept to reality. It sharpens your competitive edge.

And, along with complete painting facilities and an anodizing system that goes state-of-the-art one better, it's just one of eight presses available to meet your most demanding specifications.

Until today, there were things you just couldn't do with aluminum extrusions. Welcome to the future.

A Aluminum Shapes Inc.
THE FUTURE TAKING FORM

9000 RIVER ROAD, DELAIR, NJ 08110 609.662.5500 fax 609.662.5605

dures. The first step in the design-tailoring procedure is the specification of the tailoring input, which consists of an objective function, design variables, constraints, and convergence tolerances. The next step is to establish the current design via an initial multidisciplinary analysis based on values of the current design variables. The mathematical representation of the discipline-specific loads (e.g., thermal and mechanical loads) activates the corresponding multidisciplinary analysis modules.

The rest of the tailoring procedure is iterative. The gradients of the objective function and constraints are computed with respect to the design variables. A search vector is defined. A new set of design variables is chosen along the direction of the search vector. Again using the multidisciplinary analysis module, a proposed design based on the new design variables is then formulated and the physical behavior of the structure with the proposed design is simulated numerically. Then the objective function, the

design variables, and the constraints are checked, on the basis of specified tolerances, to determine whether the proposed design is optimum. The procedure is repeated until an optimum design that satisfies all the constraints is achieved.

This work was done by Christos C. Chamis of Lewis Research Center and Surendra N. Singhal of NYMA. For further information, write in 64 on the TSP Request Card. LEW-15977




Figure 2. Multidisciplinary Design and Analysis Procedures that are implemented in the computer code reflect the nonlinearity and complexity of the relevant physical phenomena and of the design process.

Computer-Aided Process Model for Carbon/Phenolic Materials

The model can be used to optimize curing processes and predict the properties of the materials.

Marshall Space Flight Center, Alabama

A computer program implements a thermochemical model of the processing of carbon-fiber/phenolic-matrix composite materials into molded parts

of various sizes and shapes. The program and model are subjects of a continuing development effort. Although this effort is directed toward improving the

fabrication of rocket-engine-nozzle parts made of carbon/phenolic materials, the model can also be used to optimize the fabrication of other structural compo-

DO GOOD WORK. FAST!

Integrated's line of **electromagnetic** software, using the boundary element method (BEM) performs effortlessly...so you can analyze, customize and finalize, quickly and easily. You save time and money through:

- immediate productivity
- accurate, efficient solutions
- reduced prototyping costs
- expert technical support.

"Integrated's BEM software provides accurate results and improves motor design cycle time without a complex FEM mesh."

Mark R. Thomas, R&D Engineering Manager,
Prestolite Electric Inc.

We're on the cutting edge of CAE design and analysis, bringing you the **most advanced electromagnetic software available anywhere**. Our high powered, user-friendly software enables you to optimize your designs with incredible efficiency.

We provide you with sample problems plus a database of solved industry-specific designs. Also, IGES or DXF geometry translators and **parametric** definitions accelerate the synthesis of your own solutions.

"Integrated's software optimizes our high voltage accessory and insulator designs...reducing material cost and enhancing performance."

Tom Bialek, Senior Product Development Engineer,
Raychem Corporation

Count on full technical support, via phone, fax or e-mail, plus you receive **regular software enhancements** each year.

Installation time and the "software learning curve" barely form a speed bump on the road to **doing good work, fast** with Integrated's software. **Call today for a 30-day trial.**

Electromagnetic Applications:

- AC/DC motors
- switches & sensors
- low/high voltage systems
- magnetic systems
- actuators
- cables
- other systems

Solution Capabilities:

- electromagnetic fields
- torque & force
- eddy currents & ohmic losses
- skin & proximity effects
- R, L, C, G & Zo
- temperature & heat flow
- trajectories



INTEGRATED
ENGINEERING SOFTWARE

Phone: (204) 632-5636 Fax: (204) 633-7780
e-mail: info@integrated.mb.ca

For More Information Write In No. 607


nents, and its material-property parameters can be changed to apply to other materials. The model helps to reduce costs by reducing the amount of laboratory trial and error needed to optimize curing processes and to predict the properties of the cured parts.

The program and model are based on the SINDA heat-transfer program and model. The program incorporates sophisticated computer-graphical capabilities; it can provide a three-dimensional view of a part being analyzed, the position of the part in the nozzle or other overall structure, and cross-sectional views of changes in temperature, degree of cure, moisture, and viscosity during the curing process. The model includes submodels of the transfer of heat, thermochemical reactions, generation and diffusion of moisture, viscosity, and the degree of cure. These submodels have been verified in laboratory tests.

A submodel of the flow of resin under pressure (see figure) is planned. This submodel will be based on data from flow tests in a laboratory. The model has been verified by correlation with data on a commercial carbon-cloth/phenolic composite. With suitable adjustments of kinetics parameters, the predictions of the model also seem to be well correlated with data on some other composite materials.

Several enhancements of the program and model are planned. The first would be modification of the program to make it easier to use; anyone who has minimal knowledge of SINDA but at least some knowledge of computers would be able to use the model. The second enhancement would be completion and verification of the resin-flow submodel. The third enhancement would be the addition of a submodel and code for the calculation of residual stresses and of compaction during cure.

This work was done by Mischell A. Letson and Robert C. Bunker of Thiokol Corp. for **Marshall Space Flight Center**. For further information, **write in 26** on the TSP Request Card. MFS-28969



Some of the Matrix Resin Flows out from between plies when a fiber/matrix composite laminate is squeezed during the curing process.

Program for Evaluation of Reliability of Ceramic Parts

This program predicts the probability of failure as a function of time in service.

Lewis Research Center, Cleveland, Ohio

Successful application of advanced ceramics depends on proper characterization of material properties and the use of probabilistic methodology for designing parts made of brittle materials. CARES/LIFE is a computer program for predicting the probability of failure of a monolithic ceramic component as a function of its time in service.

Probabilistic component design involves predicting the probability of failure of a thermomechanically loaded component from specimen rupture data. Typically, experiments to acquire these data are performed by use of many simple-geometry flexural or tensile test specimens. A static, dynamic, or cyclic load is applied to each specimen until fracture. Statistical strength fatigue parameters are then determined from these data.

Using these parameters and the results obtained from a finite-element analysis, the time-dependent reliability for a complex component geometry and loading is then predicted. Appropriate design changes are made until an acceptable probability of failure has been reached. This design methodology combines the statistical na-

ture of strength-controlling flaws with the mechanics of crack growth to allow for multiaxial stress states, concurrent (simultaneously occurring) flaw populations, and subcritical crack growth (SCG).

CARES/LIFE predicts the probability of failure of a monolithic ceramic component as a function of service time. It assesses the risk that the component will fracture prematurely as a result of SCG. The effect of proof testing of components prior to service is also considered. CARES/LIFE is coupled to such commercially available finite-element programs such as ANSYS, ABAQUS, MARC, MSC/NASTRAN, and COSMOS/M. It also retains all of the capabilities of the previous CARES code, which include estimation of fast-fracture component reliability and Weibull parameters from inert strength (without SCG contributing to failure) specimen data. CARES/LIFE can estimate parameters that characterize SCG from specimen data as well.

Finite-element heat transfer and linear-elastic stress analyses are used to determine the distributions of temperature and stress in a component. The reli-


ability at each element is calculated under the assumption that randomly distributed volume flaws and/or surface flaws control the failure response. The overall component reliability is the product of all the element-survival probabilities. CARES/LIFE generates a data file containing element risk-of-rupture intensities (a local measure of reliability) for graphical rendering of the critical regions of a structure.

CARES/LIFE describes the probabilistic nature of the strength of a material, using the Weibull cumulative distribution function. The Weibull equation is based on the weakest-link theory (WLT), in which it is assumed that the structure is analogous to a chain with many links. Each link may have a different limiting strength. When a load is applied to the structure such that the weakest link fails, then the structure fails.

The effect of multiaxial stresses on reliability is predicted by using the principle of independent action (PIA), the Weibull normal-stress-averaging method (NSA), or the Batdorf theory. For the PIA model, the reliability of a compo-

(continued on page 33)

FROM SUPERCOMPUTER TO PC



Take the power of CFD into your own hands, the way you work, where you work — at your own desk!

Adaptive's newest version of CFD2000 can meet you on almost any platform: your PC, your workstation, or your supercomputer.

Now, computer simulations of physical processes involving fluid dynamics coupled with heat transfer can be performed on your desktop. With CFD2000™, full 3D viscous Navier-Stokes flow — once achievable only via the supercomputer — is at your fingertips.

As a leader in computational fluid dynamics for over 20 years, Adaptive delivers software with advanced simulation capabilities,

CFD SOLUTIONS *FLOW.*



accomplished through continuous development and application. The results: CFD2000™.

Today's advances in computer memory and computer speed, in conjunction with CFD2000's™ revolutionary advances in numerical methods and user interface graphics tools, provide an enabling technology for designers and analysts who are addressing real problems in engineering mechanics.




Equip yourself with the tools that make engineering solutions flow. Call your Adaptive Technical Sales Engineer today to

find out how to solve your design challenges using computational fluid dynamics.



"Adapt or Die."

To anyone
who is choosing
between designing
in 2D or 3D,
we offer the
following advice.



For the name of the nearest Autodesk Systems Center or Autodesk Training Center, call 1-800-964-6432. Outside the U.S. and Canada, fax us at 1-415-507-6142. ©1996 Autodesk, Inc. Autodesk, the Autodesk logo and AutoCAD are registered trademarks and the Autodesk Mechanical Desktop is a trademark of Autodesk, Inc. in the U.S. and other countries.

Don't.

Introducing Autodesk Mechanical Desktop.[™] Uniting 2D and 3D.

That's right. From now on you and your entire design team can end the debate and really get the job done. The reason is the new Autodesk Mechanical Desktop. And if you read on, you'll see that everything we're talking about here is designed around your needs as a mechanical designer. Take 2D drafting. For some projects it's the best way to go and it just may be the way that you're most comfortable working. Since Mechanical Desktop is built on AutoCAD[®] software, the unsurpassed 2D drafting standard, you know the capabilities are there. Other projects are more effectively done in 3D or a mixture of 2D and 3D. Our

enhanced feature-based solid modeler speeds design and makes change effortless. And users totally new to 3D will easily get up to speed because of their familiarity with AutoCAD. So you see, with Mechanical Desktop you'll have a powerful mechanical design tool that's flexible enough for anyone in your design team whether they need 2D or 3D, for straightforward components or complex assemblies. There you have it. You'll be able to use one tool for a variety of projects. You'll have a network of training and support centers worldwide. And yes, it's affordable. Sound too good to be true? Call us on it.

Feature-based, parametric solid modeling

You model with familiar features like tapped holes and chamfers. Mix surfaces and solids to build complex shapes.

Comprehensive assembly modeling


Assemblies are associative. Make a change and see the entire design update.

2D design and drafting

.DWG format ensures compatibility with your existing data, vendors and clients.

Associative drafting

Automatically generate detailed drawings. Full bi-directional associativity updates models and drawings.




Analysis by ANSYS, Inc.

With Mechanical Desktop as a foundation, you can take your projects from design to manufacture. Thanks to the Mechanical Applications Initiative (MAI), you can choose from the best-of-class design through manufacturing applications and know that they'll be fully integrated.



Machined by NC Microproducts.

CALL 1-800-964-6432 AND ASK FOR DEMOPAK S605.

 **Autodesk.**

Of course, when it comes to service, training and support, you're going to have a lot of choices.

As you can see from the list, you'll have a lot of resellers from which to choose. But we're not just talking about variety here. You see, we've implemented a new program that certifies our resellers specifically in the mechanical market. Which means that when you visit an Autodesk Systems Center (ASC) in the U.S., or an Autodesk Industry Specialist (AIS) in Canada, you'll find people who understand your market and who speak your language. You'll also find certified engineers who not only know the ins and outs of every Autodesk mechanical product, but all the MAI applications as well. So, you'll be able to choose from the best-of-class design through manufacturing applications and have the assurance that they'll be fully integrated. These resellers will give you the in-depth knowledge, training and support to really speed your learning. Along with a wealth of Autodesk-published training materials that you can use to train your entire company. So, if you're looking for increased productivity, minimized downtime and advice and support that you can really count on, go ahead, take your pick.

MECHANICAL AUTODESK SYSTEMS CENTERS:

Central Region

Cadalog Resources/CAD Express
Des Moines, IA

NECAD
W. Des Moines, IA
Omaha, NE

CADD/CAM Tools
Arlington Heights, IL

Ad-Tech/Safari Systems
Park Ridge, IL

Hagerman & Company
Mt. Zion, IL
Schaumburg, IL

CIM-TECH
W. Chicago, IL

Pinnacle Computer Services
Evansville, IN

CAD ONE, Inc.
Farmington Hills, MI
Dayton, OH

Devtron, Russell, Inc.
Gladwin, MI

Integrated Systems Technology
Grand Rapids, MI
Madison Heights, MI

CAD/CAM Engineering Systems
Bloomington, MN

Quannon CAD Systems
Minnetonka, MN

CADWARE
St. Paul, MN

Technical Software, Inc.
Cleveland, OH

Sarcom, Inc.
Miamishburg, OH

MasterGraphics
Appleton, WI
Madison, WI
Waukesha, WI

Western Region

microCAD Technologies/
CAD Solutions
Santa Ana, CA

U.S. CAD
Irvine, CA

CAD/CAM Consulting Services
Newbury Park, CA

Lackner Computer Systems
Placentia, CA

Digital Dimensions
San Diego, CA

CAD Solutions/
microCAD Technologies
San Jose, CA

Design Technologies
Northglenn, CO

KETIV Technologies, Inc.
Portland, OR

Advantage Computing
Salt Lake City, UT

Eastern Region

Datamat Programming Systems
Norwalk, CT

Advanced Solutions
Louisville, KY

Premier Design Systems
Owings Mills, MD

DTI Technologies, Inc.
Bedford, NH

C.D.M. Technologies
Wayne, NJ

Cratin Computing Company
Plymouth Meeting, PA

Synergis Technologies, Inc.
Quakertown, PA

Greenwich Business Systems
Warwick, RI

South Central Region

Mid-West CAD
Lee's Summit, MO

Hagerman & Company
St. Louis, MO

CPI
Oklahoma City, OK
Tulsa, OK
Dallas, TX

CADworks, Inc.
Irving, TX

South Eastern Region

CADD Development
Orlando, FL

Applied Software Technology
Atlanta, GA

Comtrex Corporation
Charlotte, NC

The Print Machine
Greenville, SC

Canadian Autodesk Industry Specialists

Automated Design Systems
Winnipeg, Manitoba

CADCORP Inc.
London, ON
Markham, ON

Cad Resource Center
Scarborough, ON

Lamb Computers
Stoney Creek, ON


Vision Technologies
Toronto, Ontario

Naoki Systems Inc.
St-Basile Le Grand, PQ

Applicad Inc.
Montreal, Quebec

Les Graphiques Buscom
Montreal, Quebec

CALL 1-800-964-6432 AND ASK FOR DEMOPAK S605.



nent under multiaxial stresses is the product of the reliability of the individual principal stresses acting independently. The NSA method involves the integration and averaging of tensile normal stress components evaluated about all possible orientations and locations. This approach is a special case of the more general Batdorf theory and involves the assumption that the material is insensitive to shear.

The Batdorf theory combines the WLT and linear elastic fracture mechanics (LEFM). A flaw geometry selected by the user and a mixed-mode fracture criterion are required to model volume- or surface-strength-limiting defects. "Mixed-mode fracture" refers to the ability of a crack to grow under the combined actions of a normal load (opening mode) and shear load (sliding and tearing modes) on the crack face.

In CARES/LIFE, the relations that describe subcritical crack growth are directly incorporated into the PIA, NSA, and Batdorf theories. Subcritical crack growth is modeled with the power law, the Paris law, and the Walker law for static and constant-amplitude cyclic loading.

These laws use experimentally determined parameters that are material- and environment-sensitive.

Predicted lifetime reliability of structural ceramic components depends on Weibull and fatigue parameters estimated from widely used tests that involve flexural or tensile specimens. CARES/LIFE estimates fatigue parameters from naturally flawed specimens ruptured under static, cyclic, or dynamic (constant stress rate) loading. Fatigue and Weibull parameters are calculated from rupture data on three-point and four-point flexure bars as well as tensile specimens. For other specimen geometries, finite-element models of the specimens are also required when estimating these parameters.

CARES/LIFE is written in ANSI FORTRAN 77 to be machine-independent. Therefore, the program will run on any computer in which sufficient addressable memory (at least 8MB) and a FORTRAN 77 compiler are available. The CARES/LIFE software package has been successfully implemented on DEC VAX computers running VMS, Sun4-series computers running SunOS 4.1.3, Silicon

Graphics computers running IRIX 5.2, and DECstation-series computers running DEC RISC ULTRIX. Sample output files from the ANSYS (Swanson Analysis Systems, Inc.), MSC/NASTRAN (MacNeal-Schwendler Corp.), and ABAQUS (Hibbitt, Karlsson, and Sorenson, Inc.) commercially available finite-element-analysis software packages are included with the distribution. For an IBM-compatible personal computer with a minimum 640K memory, a limited program is available (CARES/PC, COSMIC number LEW-15248). The standard distribution medium for CARES/LIFE is a 0.25-in. (6.35-mm) streaming-magnetic-tape cartridge (Sun QIC-24) in UNIX tar format. Alternate distribution media and formats are available upon request. CARES/LIFE was released in 1994.

This program was written by N. Nemeth, L. A. Janosik, and J. P. Gyekenyesi of Lewis Research Center and Lynn M. Powers of Cleveland State University. For further information, write in 96 on the TSP Request Card. LEW-16018

TSS — Thermal Synthesizer System

This software can greatly expedite the thermal-engineering process.

Lyndon B. Johnson Space Center, Houston, Texas

The Thermal Synthesizer System (TSS) is an integrated set of thermal-analysis application programs that is designed to solve problems encountered by thermal engineers. TSS combines the functionality of Systems Improved Numerical Differencing Analyzer/Fluid Integrator (SINDA/FLUINT) and radiation analysis with a friendly and easily understood user-interface environment coupled with powerful interactive color graphics and geometric modeling capability. The effort expended on developing this means of interaction has resulted in a system that is easy and straightforward to use. This system will enable thermal engineers to spend more of their time solving engineering problems instead of laboriously constructing and verifying math models.

TSS functionality is logically grouped into a number of application programs. The Executive application program serves as the starting point for all other TSS application programs. This application program also encapsulates UNIX functionality into a user-friendly

interface. The Geometry application program facilitates construction, verification, and display of thermal-radiation mathematical models as well as solid and shell models for subsequent processing by the Radiation Conductance (RADK), Heatrate, Conductance-Capacitance, and Image application programs.

The RADK application program allows calculation of thermal-radiation form factors, interchange factors, and radiation conductances through use of Monte Carlo ray-tracing techniques. RADK output is compatible with SINDA/FLUINT, also included in TSS. The Orbit application program provides a means of creating and visualizing orbits for subsequent use by the Animation and Heatrate application programs. The Orbit application program operates in six different modes: basic, Keplerian, Sun-referenced, date-dependent, heliocentric, and planetary surface. The Animation application program facilitates the articulation of model geometries (in either an orbiting or a geometry-only mode) for subsequent

processing by the RADK and Heatrate application programs. Each object within a geometric model can be articulated in one of four animation modes: velocity plus rotation rate, positional interpolation, inertial tracking, or point tracking.

Users may specify artificial radiant-heat sources within the Heatsource application program. Four different types of artificial sources may be specified: infinite parallel, point, nodal diffuse, and infinite diffuse. Both solar and infrared spectrum sources are supported. The Heatrate application program enables characterization of orbit environments, planetary surface environments, and artificial heating. Orbit-environment calculations provide for computation of solar, albedo, and planetary heating components. The Conductance-Capacitance application program facilitates the creation of a SINDA/FLUINT-compatible thermal-network model as derived from the geometry specified by the user. Nodal capacitances and intraobject conductances are automatically calculated. Interobject con-

duction paths are easily generated.

The SINDA/FLUINT application program, included with TSS, is the same SINDA/FLUINT program that is available on many platforms (Version 2.6). Models created within TSS can be processed within SINDA/FLUINT or exported to external systems. Conversely, any existing SINDA/FLUINT model can be ported into the TSS system and processed. The FLUINT Modeler application program enables the construction, display, and verification of single- or two-phase flow networks and creates SINDA/FLUINT-com-

patible input decks. This application program also supports postprocessing of the model results onto the geometric representation of the flow network.

The Thermal Radiation Analysis System (TRASYS) to Geometry Translator converts models in the TRASYS input-deck format into the TSS Geometry Input Language. The Geometry to TRASYS Translator converts models in the TSS Geometry Input Language format into the TRASYS input-deck format.

Results from TSS analyses, ASCII data, and flight data can be plotted in

the XY Plot application program, which is included with TSS. Users can work with up to eight different sets of data simultaneously. Customization of plots, comparison-plotting of sets of data, and curve fitting are also available. Geometries defined by users can be processed in the Image application program to provide photorealistic images to support engineering analysis, presentations, and documentation.

TSS has been under development for many years. It was first released in 1993. TSS is available from COSMIC (v2.0) by license for a period of ten years to approved licensees. The licensed program product includes the executable code and one copy of the supporting documentation. Additional copies of the documentation may be purchased separately at any time.

TSS is written in FORTRAN and C language for Apollo DN10000VS and HP 700-series computers running Domain and UNIX operating systems, respectively. The program requires 32MB of random-access memory and at least 500MB of disk space. For the Apollo workstations, TSS requires 40-bit-plane graphics, Domain 3-D graphics Metafile and Domain Dialogue. For the HP-series workstations, TSS requires the CRX 24Z graphics upgrade, HP-UX 9.05, and the PHIGS run-time library. A FORTRAN-77 compiler is required for the SINDA/FLUINT application.

The standard distribution medium is magnetic tape. For the Apollo computers, the program is distributed on 60MB, 0.25-in. (6.35-mm) streaming-magnetic-tape cartridge in rbak format, which is readable on a Domain Dialogue 60MB tape drive. For the HP-series workstations, the program is distributed on 4-mm tape in tar format, readable under standard UNIX environments.

This program was developed by Edward Chimenti, Steven Rickman, Robert Vogt, and Carlos R. Ortiz Longo of **Johnson Space Center**; Noel Bauman, Joseph Lepore, Phil Mackey, James Pavlovsky II, Mark Welch, and Peter Fogerson of Lockheed Engineering and Sciences Co.; and Mark Dawber, Cynthia Jone Fong, Peter Hecke, Susan Morrison, Ernie Castillo, Zu Chou, Lawrence Fried, Jerry Howard, Mike Lombardi, Jack Middleton, Tim Panczak, and Brett Preston of Lockheed Missiles and Space Co. For further information, **write in 86** on the TSP Request Card. MSC-22420

"IN THIS BUSINESS, TIMING IS EVERYTHING."



Don Erb
Co-Owner
Comptech Racing
Reynard/Honda
#49 Motorola IndyCar

"TEKSOFT GETS US TO THE FINISH FASTER."

SIMPLICITY DRIVES PRODUCTIVITY

Nothing's more demanding than running an IndyCar 220 mph for two hours in heavy traffic. Delivering the right part can make the difference between finishing first or not finishing at all.

"TekSoft provides us the ease and flexibility to generate the most complex parts, faster. Getting to the finished part is simply more productive."

POWER DRIVES PERFORMANCE

TekSoft CAD/CAM runs your entire CNC manufacturing process and supports complete CAM functions, including:

- Multi-surface milling
- Lathe
- Fabrication
- Laser & Plasma
- Wire EDM

TEST DRIVE ONE YOURSELF

Call us today to arrange a no obligation demonstration and see for yourself how TekSoft turns simplicity and power into productivity and performance.

SIMPLE. POWERFUL. PRODUCTIVE.



3320 West Cheryl Drive, Suite 240
Phoenix, Arizona 85051
FAX 602.866.9016

WINDOWS 95 & WINDOWS NT VERSIONS NOW AVAILABLE!

© 1996 TekSoft, Inc. TekSoft is a trademark of TekSoft, Inc. Windows and the Windows logo are trademarks of Microsoft Corp.



Call us to receive this **FREE** poster featuring Comptech Racing's #49 Motorola IndyCar.



Actual Size: 26" x 18" Limit one per name and address please.

Program Calculates Current Densities of Electronic Designs

The current in each component is averaged over the area occupied by the component.

NASA's Jet Propulsion Laboratory, Pasadena, California

The PDENSITY computer program calculates current densities for use in calculating power densities of electronic designs. PDENSITY reads a parts-list file for a given design, a file that contains the current required for each part, and a file that contains the size of each part. Then for each part in the design, the program calculates the current density in units of milliamperes per square inch ($1 \text{ mA/in.}^2 = 0.155 \text{ mA/cm}^2$).

The user invokes PDENSITY with the input parts list, the current-requirements file, the size file, and the name of the output file. Any parts not in the current-requirements file are reported, and the current-requirements file can be modified for particular needs.

PDENSITY is written by use of the

AWK utility for Sun4-series computers running SunOS 4.x and IBM PC-series and compatible computers running MS-DOS. The program was written to be used with the OrCad Schematic Capture Program, but also can be used with a list of parts in ASCII format. The UNIX "nawk" utility is used to run the Sun version of PDENSITY. The Sun version of the program (NPO-19588) has been successfully implemented on a Sun4-series computer running SunOS 4.1.3. The PC version of the program (NPO-19171) has been successfully implemented on a DECpc 486-series computer running MS-DOS v6.2. A sample executable file is provided for the PC version of PDENSITY. The standard distribution medium for the Sun

version of PDENSITY is a 3.5-in. (8.89-cm), 1.44MB diskette in UNIX tar format. The standard distribution medium for the PC version of PDENSITY is one 3.5-in. (8.89-cm), 1.44MB, MS-DOS-format diskette. An electronic copy of the documentation in Microsoft Word v2.0 for MS-DOS format is included on all distribution media. PDENSITY was released in 1995 and is a copyrighted work with all copyright vested in NASA.

This program was written by Brian Cox of Caltech for NASA's Jet Propulsion Laboratory.

For further information on NPO-19588, write in 63 on the TSP Request Card.

For further information on NPO-19171, write in 66 on the TSP Request Card. NPO-19588/NPO-19171

Computing Operating Characteristics of Bearing/Shaft Systems

SHABERTH incorporates up-to-date mathematical models of thermal and mechanical phenomena.

Marshall Space Flight Center, Alabama

The SHABERTH computer program predicts operating characteristics of bearings in a multibearing load-support system. Lubricated and nonlubricated bearings can be modeled. SHABERTH calculates the loads, torques, temperatures, and fatigue lives of ball and/or roller bearings on a single shaft. The program also provides for analysis of the reaction of the system to the termination of the supply of lubricant to the bearings and other lubricated mechanical elements. SHABERTH has proven to be valuable in the design and analysis of shaft/bearing systems.

The SHABERTH program is structured with four nested calculation schemes. A thermal scheme performs both steady-state and transient calculations that predict temperatures in the system in a given operating state. A bearing-dimensional-equilibrium scheme uses (1) bearing temperatures predicted by the temperature-mapping subprograms in the thermal scheme and (2) distributions of loads on rolling-element raceways as predicted by a bearing subprogram, to calculate (3) diametral clearances of

bearings in a given operating state. A shaft/bearing-system load-equilibrium scheme calculates positions of inner rings of bearings relative to the respective outer rings, such that the external loads applied to the shaft are brought into equilibrium by the rolling-element loads that develop at each inner ring in a given operating state. A bearing-rolling-element-and-cage load-equilibrium scheme calculates the equilibrium positions and the speeds of rotation of rolling elements and cages on the basis of relative positions of inner and outer rings, inertial effects, and friction.

The current version of SHABERTH contains ball-bearing subprograms that are enhanced, in comparison with similar programs, by the incorporation of several mathematical models. These include

- An elastohydrodynamic (EHD) film-thickness model that accounts for heating and lubricant-film starvation in the contact area;
- A new model for traction combined with an asperity-load-sharing model;
- A model for the hydrodynamic rolling and shear forces in the inlet zones of

lubricated contacts, which model accounts for the degree of lubricant-film starvation;

- A model of normal and friction forces between a ball and a cage pocket, which model accounts for the transition between the hydrodynamic and elastohydrodynamic regimes of lubrication; and
- A model of the effect, on fatigue life, of the ratio between the thickness of the EHD plateau film and the composite surface roughness.

SHABERTH is intended to be as general as possible. The models in SHABERTH provide for the complete mathematical simulation of real physical systems. A simulated system is limited to a maximum of five bearings supporting a shaft, a maximum of 30 rolling elements per bearing, and a maximum of 100 temperature nodes. The structure of the SHABERTH program is modular and has been designed to enable refinement and replacement of various component models as needs and opportunities develop.

SHABERTH is available in Cray and



Your brother-in-law isn't the only continuous sponge on the planet.

If you're looking for high-tech answers to your seal and gasket challenges, look to Lauren. Our continuous sponge profile and sheet extrusions of fluoroelastomers, fluorosilicones and silicones deliver the superior sealing characteristics of space-age polymers for a fraction of the cost of their solid seal and gasket counterparts. Why take a bath on your next project, when a little sponge from Lauren will do just fine. Call us today for details. Ask for a free copy of our new capabilities video.

LAUREN • 2228 Reiser Ave., S.E. • New Philadelphia, Ohio 44663 • 800-683-0676 • Fax: 216-339-7166



IBM PC versions. A preprocessor sub-program is included in the IBM PC version to provide a user-friendly means of developing SHABERTH models and executing the resulting code. The preprocessor enables the user to create and modify data files with minimal effort and a reduced chance for errors. Data are utilized as they are entered; the preprocessor then decides what additional data are needed to complete the model in question. Only these needed data are requested. The preprocessor can accommodate input of data for any shaft/bearing-system mathematical model compatible with SHABERTH. The system to be simulated can include ball bearings, cylindrical roller bearings, and/or tapered roller bearings.

The two versions of SHABERTH are available from COSMIC. The Cray version [LEW-14860, "Computing Thermal Performances of Shafts and Bearings," *NASA Tech Briefs*, Vol. 16, No. 3 (March, 1992), page 67] requires a random-access memory (RAM) of 176K of 64-bit words. The IBM PC version (MFS-28818, this article) is written for IBM PC-series and compatible computers running MS-DOS and includes a sample MS-DOS executable code. For execution, the PC version requires at least 1MB of RAM and computer that contains an 80386 or 486 processor with an 80 x 87 math coprocessor. The standard distribution medium for the IBM PC version is a set of two 5.25-in. (13.335-cm), 360K, MS-DOS-format diskettes. The contents of the diskettes are compressed by use of the PKWARE archiving software tools. The utility software to unarchive the files, PKUNZIP.EXE, is included. The standard distribution medium for the Cray version is also a 5.25-in. (13.335-cm), 360K, MS-DOS-format diskette, but alternate distribution media and formats are available upon request.

The original version of SHABERTH was developed in FORTRAN IV at Lewis Research Center for use on a UNIVAC 1100-series computer. The Cray version was released in 1988, and was updated in 1990 to incorporate fluid-rheological data for Rocket Propellant 1 (RP-1), thereby enabling the analysis of bearings lubricated with RP-1. The PC version is a port of the 1990 Cray version and was developed in 1992 by SRS Technologies under contract to NASA's Marshall Space Flight Center.

This program was written by James D. Moore of Marshall Space Flight Center. For further information, write in 13 on the TSP Request Card.
MFS-28818



Electronic Components and Circuits

Antennas for Receiving Signals Broadcast via Satellites

Small, inexpensive units have been designed for outdoor and indoor uses.

NASA's Jet Propulsion Laboratory, Pasadena, California

Four different antennas have been designed for use in receiving radio AM and FM signals broadcast via Earth-orbiting satellites at a carrier frequency of 2.05 GHz in right-hand circular polarization. These antennas are small, lightweight, inexpensive units with low-to-medium-gain, quasi-omnidirectional radiation patterns.

The first antenna, shown in the top left part of the figure, includes two crossed drooping dipoles protruding from a shaft, plus an impedance-matching tuning ring on the shaft. Each arm in one of the dipoles is 1.2 in. (30.5 mm) long; each arm in the other dipole is 1.8 in. (45.7 mm) long. The height of the

dipoles above the automobile roof or other ground plane can be adjusted to optimize performance. In one test, for example, the dipoles were set at a height of 3.2 in. (81.3 mm), yielding a radiation pattern that peaked at 60° below the zenith, with a peak gain of 4.8 dBic (where "dBic" denotes decibels with respect to isotropic, circularly polarized radiation).

The second antenna, shown in the top right part of the figure, includes a circular conductive TM_{21} -mode-radiating patch of 5.2-in. (132-mm) diameter on a honeycomb dielectric plate of 6-in. (152-mm) diameter and 0.5-in. (12.7-mm) thickness. The patch is connected, at

four locations near its periphery, to four ports of a printed-circuit-board stripline feed network that provides the amplitude and phase relationships for reception of right-hand circular polarization. This antenna is also intended for outdoor use. In a test, this antenna provided a peak gain of 6.5 dBic at an angle of 36° below the zenith.


The other two antennas are medium-gain units designed for indoor use. These antennas contain 2×2 arrays of printed-circuit square conductive patches and microstrip feed lines that provide the required amplitude and phase relationships. Both of these antennas are fabricated on dielectric substrates of




CROSSED DROOPING DIPOLES



TM_{21} -MODE CIRCULAR MICROSTRIP PATCH ANTENNA



SQUARE PATCHES WITH CONVENTIONAL FEED



SQUARE PATCHES WITH SEQUENTIAL FEED

These **Small, Inexpensive Antennas** are suitable for reception of satellite broadcasts in right-hand circular polarization at a frequency of 2.05 GHz.

Putting PC-Based Data Acquisition and Instrumentation



To Work for You

Whatever your application, Quatech can provide the solution.

Whether your starting up a new system or expanding an existing station, with reliable PC-based hardware and instrumentation your strategies will become reality. A reality that is backed by the technical support of fully trained engineers and distributors around the globe.

To find out more about the industry's most complete line of data acquisition hardware and instrumentation systems call one of our sales representatives at 800-553-1170.

Or contact us for a free 1996 Solutions Handbook.



From Application
to Solution

0.126-in. (3.2-mm) thickness. These antennas differ from each other in their microstrip feed configurations and in their lateral dimensions, which are 8.5×8.5 in. (216×216 mm) for one and 8×8 in. (203×203 mm) for the other. The measured broadside gains of the units were

12.0 and 13.7 dBic, respectively.

This work was done by Te-Kao Wu and John Huang of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 98 on the TSP Request Card. NPO-19362

Split-Waveguide Mounts for Submillimeter-Wave Multipliers and Harmonic Mixers

Advantages include ease of fabrication, reliability, and tunability.


NASA's Jet Propulsion Laboratory, Pasadena, California

A novel variation of a split-waveguide mount for millimeter- and submillimeter-wavelength frequency multipliers and harmonic mixers has been developed. The mount was designed to offer a wide range of available matching impedances, while maintaining a relatively simple fabrication sequence. The wide tuning range is achieved with separate series and parallel elements, which consist of two pairs of noncontacting sliding backshorts, at the fundamental and harmonic frequencies. The backshorts are arranged side by side between the input/output coupling arms, which makes for a very compact design with easy access to the tuner adjustments. Waveguide arms perpendicular to the tuner channels provide in-line input and output ports for multiplication or in-line signal and local oscillator (LO) ports for harmonic mixing. The mount is fabricated in two pieces, which

are nearly mirror images of each other. The design is meant to be implemented with ordinary machining techniques — principally end-milling, sawing, or scribing the block halves. All six waveguide channels are in the same plane and no electroforming is required.

These waveguide mounts are particularly well-suited for circuits in which the electrically nonlinear elements are incorporated into stripline or suspended substrate circuitry rather than the more traditional, but circuit limiting, whisker-contact structures (although these can be accommodated as well). Both theoretical and experimental measurements of the mount indicate that the generic design enables matching over a wide range of impedances at both the fundamental and harmonic frequencies.

The figure shows the layout of a 110- to 220-GHz frequency doubler using the



The Block Containing Waveguide Channels and a few discrete components is one of two nearly-mirror-image blocks that are assembled to construct a frequency doubler.



Precision Ball Bearing Screws

Standard precision ball screws are available in wide range of models 3/8" to 3" in diameter. Lead accuracies of 0.0005". 95% efficiency, controlled backlash, smooth operation. For instant information call our Tech Fax number 800-234-3369.

Request document 321 or Catalog P-978.

For More Information Write in No. 635



Ball Bearing Screws

Standard ball bearing screws from Warner Electric are available in a wide range of models, features and options. From 3/8" to 3" diameters, dynamic load ratings to 38,000 lbs., standard lengths to 12 feet. Zero backlash and bearing end journals are optional in all models. For instant information call our Tech Fax number 800-234-3369.

Request document 300 or catalog P-626.

For More Information Write in No. 636



Linear Ball Bearings and Shafting

Warner Electric now has a complete line of precision linear bearings and shafting to enhance the largest offering of linear motion products in the industry. For instant information call our Tech Fax number 800-234-3369.

Request document 502 or catalog P-1039.

For More Information Write in No. 637

WARNER

Products for Controlling Linear Motion

People Finding A Better Way

For instant access to technical information 24 hours a day...every day, call our Tech Fax number
(800) 234-3369

and enter the document number of the product you are requesting.
Or call 815/389-6691 to request a specific catalog.

WARNER ELECTRIC



449 Gardner Street, South Beloit, IL



Rapidtrak Linear Actuators

A compact, self-contained self-supporting, modular designed, linear actuator. Strokes up to 22 feet. Speeds to more than 9 feet per second. Two profile sizes. Ball screw or belt-drive designs. AC, DC, air, hydraulic, servo, step motor drive capabilities. For instant information call our Tech Fax number 800-234-3369.

Request document 431 or catalog P-958.
For More Information Write in No. 639




For More Information Write in No. 640

Programmable Actuator Systems

The Electrak 2000 actuator offers a wide choice of features; ball screws or acme screws in parallel or in-line configurations. Load rating to 2000 lbs. Repeatability to 0.0005". Stroke lengths to 24". Speeds up to 20"/sec. Life to 50 million cycles. They are programmable and menu driven. Excellent for accurate and repeatable positioning. For instant information call our Tech Fax number 800-234-3369.

Request document 425 or catalog P-1023.




Failsafe Brakes

Warner Electric's electrically released, spring actuated failsafe brakes. Ideal for holding applications. Torque rating from 1.5 lb.ft. to 200 lb.ft. High torque, long life. For instant information call our Tech Fax number 800-234-3369.

Request document 221 or catalog P-873.

For More Information Write in No. 638



Linear Actuator Systems

Warner Electric's electromechanical linear actuator systems feature full range capacity from light load, mini-actuators to high performance models capable of handling loads up to 1000 lbs. with up to 10 times more life than any actuator available before. For instant information call our Tech Fax number 800-234-3369.

Request document 409 or catalog P-786.
For More Information Write in No. 641

new mount design. The overall dimensions of the block (with the two nearly-mirror-image block halves assembled) are $29 \times 14 \times 19$ mm, where 14 mm is the distance between the input and output waveguide flanges. The 110-GHz input pump signal enters via a full height WR-8 waveguide (1.02×2.03 mm). The two opposing input tuner arms, which are also WR-8 waveguides, contain the noncontacting sliding backshorts, which provide series and parallel reactive tuning elements for matching at the input frequency. The backshorts are adjusted by use of micrometer heads. From the input tuner waveguide, the pump is cou-

pled to a quartz microstrip probe, then along a microstrip harmonic separating filter to the multiplier diode, which is located across the output tuner waveguide. The filter is composed of chrome/gold low-pass elements on a fused substrate 0.152 mm thick and 0.33 mm wide. The distance between the input and output tuner waveguides is 2.50 mm. The filter extends beyond the output waveguide to allow additional electrical matching of both the input and output harmonic frequencies or possible idlers. In the doubler, the extended filter region provides an electrical short at the waveguide wall for both fundamental

and second harmonic frequencies.

Output power leaves the block via an electric-field-plane waveguide arm perpendicular to the tuner arms. The output tuner waveguide, like the input, contains two noncontacting sliding backshorts, which provide series and parallel reactive matching elements at the output frequency of 220 GHz. The output impedance matching range is broadened by using reduced, rather than full, height waveguide (0.28×1.09 mm).

A built-in channel-waveguide-transformer brings the output guide up to standard height WR-4 (0.54×1.09 mm). The distances of the input and output port electric-field-plane arms from the input coupling probe and the multiplier diode are approximately one half of a guide wavelength at the respective center frequencies of operation. An additional filter, between the input/output tuner guides and perpendicular to the harmonic separating filter provides biasing capability for the diode. This filter ends in a wire bond to the center pin of an SMA coaxial connector which extends up from the bottom of the block.

This work was performed by Antti Raisanen, Debabani Choudhury, Robert J. Dengler, John E. Oswald, and Peter H. Siegel of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 4 on the TSP Request Card. NPO-19248

WHY

► When a customer has a problem monitoring, measuring and recording *specific* information, we make it a point to be part of the solution.

IT PAYS

► As a result, our Info Loggers have flown in airplanes, raced with Indy Drivers, driven with truckers and have even been into outer space. Our loggers operate on top, under and in buildings, in tropical and sub-zero temperatures, in and out of water and just about any place a mind can imagine.

TO TALK WITH

► They monitor, measure and record temperature, relative humidity, AC and DC current, Pulse Counts, Voltage, Pressure, Flow, RPM's and more.

THE SOLUTION PEOPLE

► Compatible software downloads all stored information to a PC for quick data analysis using graphical and spreadsheet presentation formats. Special requirement? Talk to *the solution people* at ACR Systems Inc. Your affordable solution may be closer than you think.



AT ACR
SYSTEMS INC.

Unit 210, 12960 84th Avenue
Surrey, British Columbia, V3W 1K7 Canada

Phone: (604) 591-1128 or 1-800-663-7845. Fax: (604) 591-2252

Algorithm for Detecting dc Series Arcs

Load currents are analyzed to identify fluctuations characteristic of arcs.

Marshall Space Flight Center, Alabama

An algorithm has been developed for use in automatic detection of dc series arcs in power cables, cable terminations, and junction boxes. (The algorithm can also sometimes detect arcs inside electrical loads.) A system in which the algorithm can be utilized is one that receives its power from a microprocessor-based remote power controller that includes a load-current sensor. The algorithm analyzes the digitized load-current readings for fluctuations characteristic of dc series arcs.

An algorithm, as distinguished from something simpler, is needed for automatic detection of dc series arcs be-

Products

cause the problem of identifying the arcs from load-current readings is not as simple as one might initially be inclined to think. A dc series arc is an arc that occurs whenever a switch carrying dc opens or a wire carrying dc ruptures. The arc continues until the arc current ceases to flow. Unlike an arc to ground (which is a short circuit and therefore easily detectable by conventional overcurrent-sensing circuitry), a dc series arc does not give rise to a large overcurrent; indeed, the current in a dc series arc can closely resemble normal current.


Experiments have shown that a dc series arc is characterized by a step (an increase or decrease, depending on the type of equipment) of typically about 8 percent in the load-current readings at the inception of the arc, followed by an increase in the noise component of the load current. The algorithm is based on this characteristic, and it works as follows: During the first few minutes of presumably normal operation, the digitized load-current readings are monitored to determine an initial background noise level. Thereafter, the monitoring continues, the background noise level is updated from time to time in coordination with the operation of the power-controlling microprocessor, and the noise level measured during each 10-ms interval is compared with the background level. A dc series arc is tentatively deemed to have begun whenever this short-term noise rises to several thousand times the background level during one 10-ms interval. Once an arc has thus been tentatively identified and for the next 300 ms, the number of 10-ms intervals during which this short-term noise exceeds 3 times the background noise level is counted. If the count exceeds 9, then the tentative identification is deemed to be confirmed.

Hazards that can be prevented by timely detection of dc series arcs include generation of smoke and poisonous gases, and ignition of nearby combustible materials. The algorithm has been optimized to reduce the false-alarm rate to about once per century. Of course, the algorithm offers no protection during the initial background-noise-monitoring interval.

This work was done by Greg L. Moores of Micon Engineering, Inc., for **Marshall Space Flight Center**. For further information, **write in 71** on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-26340.

Data Acquisition Software



DASYLab™ is a Windows-based, icon-driven data acquisition software package that provides effortless analysis, graphing, importing, configuration, user-interface, and operator-interface capabilities. It supports IOTech's Daq PCMCIA, portable DaqBook™, and plug-in DaqBoard™ data acquisition systems. From \$495. IOTech, Inc. (216) 439-4091.

Write in No. 615

PC Plug-in Data Acq Boards



IOTech's DaqBoards™ offer 12- or 16-bit analog inputs, expandable to 256 channels; two 500 kHz D/A outputs; 24 digital I/O lines, expandable to 192; and 5 counter-timers. Signal conditioning for thermocouple, RTD, strain gage, accelerometer, high voltage, high isolation, and many other signal types is also available. Software includes DaqView™; DOS and Windows language drivers, and support for DASYLab™, Snap-Master™, LABTECH NOTEBOOK™, and LabVIEW®. From \$795. IOTech, Inc. (216) 439-4091.

Write in No. 616

IEEE 488 Controller for Sun®, HP®, & DEC™ Workstations



These SCSI/488™ interfaces enable Sun®, HP®, and DEC™ workstations to control up to fourteen IEEE 488 devices. The units attach to a workstation's SCSI port. Each has a driver for the appropriate operating system, including Solaris™ (Sun®), HP-UX™ (HP®), and OpenVMS™ (DEC™). From \$1795. IOTech, Inc. (216) 439-4091

Write in No. 617

PCMCIA Cards



Stack the deck
in your favor
with IOTech's wide selection of
PCMCIA cards for all your needs!

Daq PCMCIA A/D Cards

12- and 16-bit, 100 kHz A/D cards, available with signal conditioning for thermocouples, RTDs, accelerometers, strain gages, and much more. Include DaqView™ software, DOS and Windows™ drivers, and drivers for a variety of graphical packages, such as DASYLab™, LABTECH NOTEBOOK™, Snap-Master™, and LabVIEW®.



Dac PCMCIA D/A Card

8 channel, 12-bit D/A card



DigiCard/24™

24-channel digital I/O card



Personal488/CARD™

IEEE 488.2 card
with full DOS,
Windows, &
Windows®95
support



ComCards™

1- or 2-channel serial
RS-232/422/485 cards



Parallel Cards

Standard & enhanced
parallel port (EPP) cards



Call for your free
IOTech catalog



25971 Cannon Rd. ▲ Cleveland, Ohio 44146
Phone: 216-439-4091 ▲ Fax: 216-439-4093

The following are trademarks or registered trademarks of their respective holders:
DASYLab - DASYTEC GmbH; DEC - Digital Equipment Corp.; DOS, Excel, & Windows -
Microsoft Corp.; HP - Hewlett-Packard; LABTECH NOTEBOOK - LABTECH LABORATORY;
National Instruments, Inc.; Snap-Master - IBM Data Corp.; Sun - Sun Microsystems, Inc.

Write in No. 618

Focal-Plane Analysis for Calculating Antenna Gain

Computation time is reduced substantially below that of the traditional method.

NASA's Jet Propulsion Laboratory, Pasadena, California

An improved method has been devised for calculating the gain of an antenna system that comprises a main reflector and an array of feed elements. In comparison with the traditional method, the improved method involves much less computation; this is an important advantage when it is neces-

sary to compute gains repeatedly, with slight variations in design at each iteration, in an effort to find an optimum design.

In the traditional method, one calculates the gain from a perspective of transmission. One begins by calculating the current density produced on the

reflector surface by each element of the array, then uses the classic radiation surface integral with an integrand proportional to $[(\text{current density}) \times (\text{a direction-dependent phase factor})]$ to obtain the far electromagnetic field generated by the element. The gain is then calculated from the sum of the far fields generated by all of the elements. The calculation of far fields for all of the elements can consume much time; the amount of computation time can become prohibitive when it is necessary to perform the far-field calculations for evaluating a number of alternative geometric configurations for the array.

In the improved method, one calculates the gain from the perspective of reception, and it is not necessary to repeat the far-field calculation for each different geometric configuration of the array configuration. Instead, one computes a near reflected field that corresponds to a far field incident from a specified direction of reception, and it is necessary to perform this part of the calculation only once for each combination of reflector-surface configuration and receiving direction; it is not necessary to repeat this part of the calculation as long as the reflector-surface configuration and far-field direction remain the same.

The improved method is based on the Lorentz reciprocity theorem and, more particularly, on one of its consequences; namely, that the antenna gain in transmission or reception (they are the same) can be computed from a convolution of two fields in the focal plane of the reflector. One of these fields is the near field mentioned above; more specifically, the focal-plane field produced by a plane wave incident on the reflector from the specified direction of reception. The other field is the focal-plane field produced by the array of feed elements excited with currents in the specified amplitudes and phases.

This work was done by Paul W. Cramer, William A. Imbriale, and Sembiam R. Rengarajan of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 92 on the TSP Request Card. NPO-19460

NEW!


Save Time & Money with the FREEPOINT 3D Digitizer

The Most Versatile and Affordable 3D Digitizer for:

- Rapid Prototyping
- Reverse Engineering
- Modeling
- Design
- Animation
- Measurement
- Inspection

FREEPOINT 3D

Real Time 3D Modeling Tool™



FREEDOM TO DIGITIZE IN 3 DIMENSIONS

Unique Digitizing Features:

- Large Volume – up to 16 x 8 x 8 ft.
- Digitize any material – including metals
- Hand-held Flexibility
- Portable

Broad Software Compatibility: Works with most leading 3D CAD software.


Call for a FREE brochure or demonstration!
410-381-6688



SCIENCE ACCESSORIES

New Dimensions In Digitizing

7125 RIVERWOOD DR. COLUMBIA, MD 21046
TEL 410-381-6688 FAX 410-290-9065



Multi-Channel, Ultra-Fast A/D Cards in Industrial PC Systems



- ✓ 250 MSPS, 8 Bit A/D Card
- ✓ 60 MSPS, 12 Bit A/D Card
- ✓ 20 MSPS, 12 Bit D/A Card
- ✓ 16 Meg Memory
- ✓ Up to 16 cards in one Industrial PC
- ✓ Industrial Grade PCs available
- ✓ Drivers in C, BASIC, Windows DLL, ...
- ✓ Free GageScope software

CS6012/PCI	PCI BUS	12 bit / 60 MSPS / 512K	\$8,995
CS6012	ISA BUS	12 bit / 60 MSPS / 512K	\$6,995
CS1012	ISA BUS	12 bit / 20 MSPS / 512K	\$4,995
CS2125	ISA BUS	8 bit / 250 MSPS / 256K	\$4,995
CS250	ISA BUS	8 bit / 100 MSPS / 32K	\$3,500
CS225	ISA BUS	8 bit / 50 MSPS / 128K	\$1,995
CSLITE	ISA BUS	8 bit / 40 MSPS / 16K	\$595

U.S. Prices listed above. International prices may vary

CALL 1-800-567-GAGE

Ask for extension 3406

4 2 4 3

GaGe

GAGE APPLIED SCIENCES INC.

1233 Shelburne Road, Suite 400

South Burlington, VT 05403

Tel : (514) 337-6893. Fax : (514) 337-8411

BBS : (514) 337-4317. CompuServe : 73042,346

e-mail: prodinfo@gage-applied.com

web site: <http://www.gage-applied.com>

For More Information Write In No. 610



Automated Monitoring of Dielectric Properties of Tree Trunks

A semiautomated instrumentation system can be left unattended to monitor several trees.

NASA's Jet Propulsion Laboratory, Pasadena, California


A semiautomated instrumentation system called a "dielectric monitoring system" (DMS) has been developed for measuring the microwave permittivities of selected components of plants — in particular, of active xylems in tree trunks. The system is built around a modified version of a commercial instrument, called a "portable dielectric probe" (PDP), which includes a coaxial probe tip that is inserted into the xylem or other component to be monitored. The DMS includes eight measurement channels for nearly simultaneous monitoring of as many as eight trees. After being set up in the field, the DMS can be left unattended to record the measurement data; thus, the DMS makes it possible to perform continuous monitoring of time-varying dielectric properties of trees in remote forest regions, where previously, the labor-intensive nature of the measurements made such continuous monitoring impractical.

The design of the DMS incorporates the PDP into a complete monitoring system. The PDP operates in conjunction with a multichannel switching unit and a data logger (see figure). The PDP includes a radio-frequency section and an analog signal-processing unit that provide both the signals needed at the probe tips for measuring permittivities and a preprocessed analog signal for the data logger. The multichannel switching unit provides the multichannel monitoring capability and provides for automatic monitoring of a dielectric calibration reference (usually air) for each of the measurement channels. The data logger includes an interface circuit that automatically controls both the channel switching and a data-storage medium that can hold data from as many as 120,000 measurements. The data logger also includes a 12-bit analog-to-digital converter for high resolution of stored measurement data.

The center conductor of the coaxial probe tip is shown extended, whereas the center conductor of the coaxial probe tip of the unmodified PDP was


flush with the flat end of the probe cylinder. The extension of the center conductor increases the reliability of contact between the probe and the specimen;

it also increases the measurement volume, thereby providing greater measurement sensitivity plus assurance that the measurement samples the dielec-



This **Instrumentation System** is set up with coaxial probes inserted in tree trunks to measure dielectric properties. The system can be left to operate unattended to gather data on permittivities as a function of time.

NEW FROM INCO SPP...
EXTRA FINE NICKEL POWDER



Inco Type 210 Nickel Powder

JUST ADD YOUR IMAGINATION
SEND FOR YOUR FREE SAMPLE TODAY

INCO SPP

10 Lawlins Park, Wycoff, NJ 07481

Shin-Muromachi Building, 4-3 Nihonbashi-Muromachi 2-Chome, Chuo-ku, Tokyo 103 Japan

1-3 Grosvenor Place, London SW1X7EA England

15/FI Wilson House, 19-27 Wyndham Street Central, Hong Kong

For More Information Write In No. 652

tric properties throughout the active xylem or other layer to be probed.

Each measurement channel consists of a switch control cable and a pair of microwave cables, one of which is connected to a two-position microwave switch. The microwave switch is toggled between each of two coaxial probe tips. For each measurement channel, one measurement probe is mounted in the

medium of interest, e.g., a tree trunk, while the other calibration probe is left exposed to the air to provide measurement of a reference material of known permittivity. The switch control cable allows for control of the microwave switch so that observations may be obtained from each of these two probe tips. The reference coaxial cable is the same electrical length as the measure-

ment cable-switch-probe tip ensemble. This is required for the PDP to properly process the RF signal and determine the reflection coefficient observed at the probe tips.

This work was done by Kyle C. McDonald and William Chun of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 11 on the TSP Request Card. NPO-19338

Modular, Hierarchical Learning by Artificial Neural Networks

Learning is streamlined by imitating some aspects of biological neural networks.

NASA's Jet Propulsion Laboratory, Pasadena, California

A modular and hierarchical approach to supervised learning by artificial neural networks is a subject of continuing research. This approach leads to neural networks that are more structured than are neural networks in which all neurons are fully interconnected. These networks utilize a general feedforward flow of information and sparse recurrent connections to achieve dynamical effects. The modular organization, the sparsity of modular

units and connections, and the fact that learning is much more circumscribed than in networks of fully interconnected neurons are all attractive features for designing neural-network hardware.

Previous approaches to learning by artificial neural networks have involved, variously, the concepts of back-propagation of error signals and gradient descent of error measures in synaptic-connection-weight space. Although very

powerful when applied to relatively simple problems, learning schemes based on these concepts alone break down as soon as sufficiently complex problems are considered. The modular, hierarchical approach was conceived to overcome this limitation.

This approach involves imitation of some aspects of learning schemes apparently followed by biological neural networks. Evolution seems to have

Push here for instant access to over



**NEW in
Volume 1.1**

- Network Support
- 12 new manufacturers
- Over 50% more data

overcome the obstacles inherent in gradient-descent learning. Learning in a biological neural network is never started from a tabula rasa. Rather, a high degree of structure is already present in the neural circuitry of a newborn organism.

Though little is known of the interaction between the prewired structure and the actual learning, it has been hypothesized that (1) complex learning tasks are broken up into simpler task modules that correspond to physical modules within a neural network, (2) learning, perhaps in dif-

ferent forms, can operate both within and across the gaps between modules, and (3) the modules can be organized in a hierarchical way. These hypotheses inspire the present modular, hierarchical approach.


The modular, hierarchical approach has been demonstrated and tested by applying it to the problem of making a neural network learn planar trajectories like circles and figure eights. The modules in each higher level of the hierarchy control the outputs of the modules one level below. The modules at the lowest level of the hierarchy contain small numbers of relatively simple neural units that can be regarded collectively, in some sense, as an oscillator that learns some simpler component of the overall motion (e.g., a sinusoid, a circle, or a Fourier component). Each lowest-level module could be a simple oscillator ring with two or three neurons, an odd number of inhibitory connections, and sufficiently high gains.

The figure illustrates an example in which these concepts are applied to learning a trajectory that comprises two perpendicular figure eights. In this case, each of four lowest-level modules contains an oscillator ring that learns one of the four loops of the trajectory. The para-

meters of the neural components in the modules can be adjusted by gradient descent to make the loops match those of the desired trajectory.

The second level of the hierarchy in this example contains two control modules. Each of these modules controls a distinct pair of oscillator modules from the lowest level, so that it ends up producing a simple figure eight. Like the modules in the lower level, these modules can be oscillator rings and their parameters can be adjusted. In particular, after the learning process is completed, they should be operating in their high-gain regimes and the period of oscillation of each must equal the sum of the periods of the modules it controls.

The highest level of the hierarchy consists of another oscillatory and adjustable module that controls the two modules in the second level, so as to produce the double figure eight. This module must also end up operating in its high-gain regime. In general, the final output trajectory is a limit cycle because it is obtained by superposition of limit cycles of the various lower-level modules. If the various oscillators relax to their limit cycles independently of each other, it is essential to provide for



The **Seven Modules** are connected sparsely in a hierarchical network designed to learn a double-figure-eight trajectory.

250,000 parts and 25,000 materials.

Announcing the Volume 1.1 release of the Autodesk Mechanical Library on CD-ROM. Where everything just clicks into place.

For intelligent parts and materials information at your fingertips, nothing beats the Autodesk Mechanical Library. This new CD-ROM data resource gives you access to supplier parts and materials from leading manufacturers worldwide.

Your annual subscription to the library features:

- The PartSpec™ CD, with over 250,000 pre-drawn parts from 32 leading manufacturers, digitized in AutoCAD® .DWG format
- The MaterialSpec™ CD, with comprehensive information on 25,000 commonly-used materials
- Pick-and-place insertion of parts into your drawings with parts retaining their attributes after insertion

- Sophisticated materials search capabilities — search by property, application, manufacturer, trade name and more
- Full compatibility with your current design automation environment, including AutoCAD and AutoCAD LT
- Semi-annual updates and toll-free support

Now, push 1-800-435-7771, ext. J11 to subscribe.

For a limited time, take advantage of our special reduced annual subscription rate of just \$349*. That's **nearly 30% off** the \$495 suggested retail price. So call today for more information, and find out how you can spend more time doing what you do best — designing.



The Autodesk Mechanical Library. Now just \$349.

Autodesk.

*U.S. dollars only. Offer good until 5/31/96. ©1996 Autodesk, Inc. Autodesk, the Autodesk logo, and AutoCAD are registered trademarks, and PartSpec and MaterialSpec are trademarks of Autodesk, Inc. All other brand names, product names, or trademarks belong to their respective holders.

adjustable delays between the various modules in order to get the proper harmony among the various phases.

In this way, a sparse network with 20 units or so can be constructed and made to execute a double figure eight.

This work was done by Pierre F. Baldi and Nikzad Toomarian of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 97 on the TSP Request Card.

This invention is owned by NASA, and

a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA Resident Office-JPL; (818) 354-5179. Refer to NPO-19077.

Ground-Based Calibration of a Microwave Landing System

Reference data are acquired simultaneously from the Global Positioning System.

John F. Kennedy Space Center, Florida

A system of microwave instrumentation and data-processing equipment has been developed to enable ground-based calibration of a microwave scanning-beam landing system (MSBLS) at distances of about 500 to 1,000 ft (150 to 300 m) from the MSBLS transmitting antenna. The system is needed to ensure the accuracy of the MSBLS near the touchdown point, without having to resort to the expense and complex logistics of aircraft-based testing. In the original application for which this system was developed, the MSBLS to be calibrated is the one that gives primary landing guidance to the space shuttle orbiter during the final 20 miles (32 km) of approach. Modified versions of this system might prove useful in calibrating aircraft instrument landing systems.

As in the case of an aircraft-based system for calibrating the MSBLS at greater distances, the basic principle of this system is to use position data from the Global Positioning System (GPS) as references, with which the MSBLS

position data are compared. However, instead of an MSBLS and a GPS receiver aboard an aircraft, this system includes an MSBLS and a GPS receiver installed in a trailer. The MSBLS and GPS receiving antennas are collocated at the top of a 50-ft (15-m) tower that is erectable from the trailer. Thus, the position of the collocated antennas simulates the position of a landing spacecraft or aircraft. To ensure the necessary precision of the GPS data, the system includes a GPS reference station located at a benchmark near the MSBLS transmitting antenna.

Once set up at the benchmark, the GPS reference station continues to receive signals from the GPS satellites, recording GPS code carrier-phase data throughout the calibration procedure. During the procedure, the MSBLS and GPS data received via the collocated antennas are recorded as the tower is positioned with a towing vehicle on and near the runway, at various distances and directions from the MSBLS trans-

mitting antenna. Because the rates of acquisition of MSBLS and GPS data are different, a 1-pulse-per-second time reference signal transmitted via the GPS is used to synchronize the collection of both sets of data. After an initialization interval of 10 min, the mobile equipment can be moved to various locations, and data can be collected while the moves are underway. The GPS receivers provide real-time carrier phase position for the reference data, thus allowing the landing-system analysis to take place while acquiring the data.

This work was done by John J. Kiriazes, Marshall M. Scott, Jr., and Alfred D. Willis of Kennedy Space Center and Temel Erdogan and Rolando Reyes of I-NET, Inc. For further information, write in 40 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Kennedy Space Center; (407) 867-2544. Refer to KSC-11802.

Coherent-Phase Monitoring of Cavitation in Turbomachines

Vibration signals are processed to extract measures of cavitation.

Marshall Space Flight Center, Alabama

A digital electronic signal-processing system analyzes the outputs of accelerometers mounted on a turbomachine to detect vibrations characteristic of cavitation. It is desirable to detect and prevent cavitation in turbomachinery because cavitation can degrade performance, erode turbine blades, cause excessive structural vibrations, and eventually result in breakage.

The operation of this and older electronic cavitation-detection systems is based on a unique vibrational phenome-

non associated with cavitation: when cavitation occurs in a rotary machine (e.g., a turbomachine), the wide-band noise generated by the collapse of cavitation bubbles becomes amplitude-modulated by the periodic components of motion associated with rotation (such as components at the fundamental frequency of rotation and its harmonics). This phenomenon gives rise to a periodicity in the accelerometer outputs; however, this periodicity is hidden in the sense that it is undetectable

by ordinary linear spectral analysis.

Older cavitation-detection systems implement a technique called "full-wave rectification wide-band demodulation" (FWRWBD), which involves envelope detection of an isolated high-frequency band of an accelerometer output that includes a high-frequency, wide-band noise floor. The onset and existence of cavitation are determined by the recovery of periodicity in the detected signal, while the magnitude of the modulation is used to determine the severity

To get the other 7 scope hints, mail this card today.

1. ☐ Yes, send me your free booklet.

I'm also interested in receiving (check all that apply):

2. ☐ Competitive comparisons.
3. ☐ "10 Steps to Selecting the Right Oscilloscope."
4. ☐ A phone call about an evaluation unit.
5. ☐ A phone call from an applications engineer.

☐ Mr. ☐ Ms. ☐ Dr.

First/M.I./Last

Title

Company

Dept./Bldg./Mail Stop

Address

City/State/ZIP

()

Telephone

Extension


NTB 3/96

TMEMD548/NTB/1148



HP 54615B

- 500 MHz bandwidth
- 1 GSa/s sampling rate
- 1 ns peak detect



\$6,995
U.S. list price

Funny how all scopes look wonderful on paper.

The real questions come when you try to use one on the job. Is it catching narrow glitches? Am I really protected from aliasing problems? Why doesn't it respond faster when I spin a knob? And what am I missing while it's struggling to process old data?

Beyond the numbers, to real-world performance.

It's not that the new HP 54615B digital scope doesn't look great on paper, too. Check out the 1 GSa/s sampling, 500 MHz bandwidth, 1 ns peak detect (at all sweep speeds) and display

updates of up to 0.5 million points/second. But it's how this performance works for you that makes all the difference.

With not one but three processors churning through the data, the HP 54615B responds instantly and dramatically reduces dead time between data blocks (so it doesn't struggle to keep up with the input signal). And patented alias reduction minimizes the imaginary signals that show up on other scopes.


So call HP DIRECT to try the new HP 54615B and discover the difference between paper performance and real performance.

**"Get your hands on a scope
that'll get the job done. Call
me at HP DIRECT."
1-800-452-4844,
Ext. 1159.**

Check out our on-line
HP Basic Instruments
(BI) Catalog at
<http://www.hp.com/info/BI07>.



There is a better way.



of cavitation. Unfortunately, any discrete components (frequency components of structural vibrations) present in the high-frequency band in question give rise to peaks in the resulting demodulated signal. This limits the utility of FWRWBD in that it is difficult to distinguish between these peaks and signal peaks contributed by recovered hidden periodicity.

The present system is designed to overcome the limitation imposed by interference from discrete components. It is based on the discovery that cavitation can be identified solely by its hidden coherent-phase information. The system digitally implements a technique called "coherent-phase wide-band demodulation" (CPWBD), using phase-only (PO) filtering along with envelope detection to search for the unique coherent-phase relationship associated with cavitation and to minimize the influence of large-amplitude discrete components.


The figure schematically illustrates the flow of information in the CPWBD algorithm. PO filtering is performed prior to a process in which a power spectral density is computed in the form of (a) a discrete Fourier transform that is the product of (b) a frequency-band-limiting rectangular function and (c) the convolution

of the discrete Fourier transform of the raw input signal with itself. The phase-only filter retains the coherent-phase relationship associated with the hidden periodicity that one seeks to identify. However, because of the amplitude-normalization effect of the phase-only filter, the system is no longer overwhelmed by independent discrete interference.

The amplitude of the hidden periodicity recovered via the PO part of the CPWBD algorithm is also subjected to some normalization. Therefore, the output of the PO part of the CPWBD algorithm should be viewed as a normalized "coherence" function for detecting the onset and existence of the wide-band-modulation (WBM) phenomena associated with cavitation. In order to detect the magnitude of the WBM signal and thereby gauge the intensity of cavitation, an "amplitude-medium" (AM) filter is introduced. This filter avoids the large vector-representation contribution of discrete interference while retaining the amplitude information about the degree of contribution toward the vector construction among various wide-band noise components. Therefore, the output of the AM part of the CPWBD algorithm should be viewed as a nonnormalized "spectrum" function for detecting the strength of the

WBM signal associated with cavitation. This work was done by Jen-Yi Jong of AI Signal Research, Inc., for Marshall Space Flight Center. For further information, write in 3 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-26313.



The CPWBD Algorithm recovers hidden periodicity, indicative of cavitation, from a noisy wide-band accelerometer output.

TRAINING...

YOUR KEY TO SUCCESSFULLY COMMERCIALIZING TECHNOLOGY

The National Technology Transfer Center (NTTC) offers seven core courses designed to give persons involved in technology transfer the knowledge and skills needed to better understand the basics and specifics of successfully commercializing technology. The NTTC's courses include:

Overview of Technology Commercialization:

Introduces the tools and basic knowledge needed to be successful in technology commercialization.

Intellectual Property Negotiations:

Defines the roles of both negotiating parties and the requirements for completing a successful licensing arrangement.

Outreach Skills for Federal Laboratory Personnel:

Provides the essential interpersonal communication, resource identification and problem solving skills needed for successful outreach to industry.

Managing Technology Commercialization:

Identifies the essential teamwork and problem solving skills to choose the most competitive technology commercialization plan.

Mastering Technology Marketing:

Establishes the strategies and tactics needed to apply a successful marketing effort for technology commercialization.

Fundamentals of Industrial Extension:

Introduces and builds upon the essential concepts, processes and skills that allow industrial extension agents to better answer the challenges faced by American industry.

Project Management for Industrial Extension:

Develops management processes, skills and resource utilization techniques needed to improve the performance of smaller manufacturers.

In addition to open enrollment offerings, each course can be customized to serve the specific needs of an your organization.


For schedule & pricing information call

1-800-678-6882



National Technology Transfer Center
Wheeling Jesuit College
316 Washington Avenue
Wheeling, WV 26003

THE BREAKTHROUGH SCIENCE BEHIND OUR NEW THERMACAM IR FPA CAMERA PUTS YOUR SCIENCE WAY AHEAD.



Digital storage of 12-bit images on a PCMCIA memory card eliminates floppy disks. Just plug the card into your PC for image processing and report generation.



For scientific applications, in small test chambers and constricted settings, ThermoCAM's compactness simplifies experiment set-up.

What if you were designing breakthrough capability and convenience into R&D thermal analysis instrumentation? You'd probably create a totally portable, self-contained infrared imaging system. One with 256 x 256 pixel, full-screen temperature measurement, a 12-bit dynamic range, and outstanding spatial resolution.

Well, consider it done. Inframetrics' ThermoCAM™ focal plane array radiometer is a true performance and portability breakthrough. Weighing just six pounds complete with integral power source, ThermoCAM is the ideal solution for scientific applications.

ThermoCAM offers full screen temperature measurement and outstanding spatial resolution.

And with just this rugged, palm-sized sensor, you can take full IR measurement and data storage capability into the field.

Engineering the world's smallest radiometer began with the smallest cryo-cooler, Inframetrics' patented Microcooler. Optimized electronics, custom ASICs, efficient diffractive optics, and a PCMCIA digital memory


card achieved breakthrough size and weight reduction. There's a full-color LCD display/viewfinder, plus remote and video links. And just 12 watts powers it all. Better still, Windows®-based ThermoGRAM image processing creates reports faster than you thought possible, right on your PC. Put ThermoCAM's science to work on your next breakthrough. Call Inframetrics today: (508) 670-5555.



inframetrics
The Infrared Specialists

Corporate Headquarters
16 Esquire Road
North Billerica, MA 01862
Tel: 508/670-5555
Fax: 508/667-2702

Inframetrics Europe
Mechelse Steenweg 277
B-1800 Belgium
Tel: 32 2 252 5712
Fax: 358 200 740 760 or
32 2 252 5388





Integrated Oxygen-Recovery System

A reactor converts carbon dioxide and water to oxygen and methane without emitting hydrogen.

Marshall Space Flight Center, Alabama

A developmental system for revitalizing breathing air in an enclosed environment converts carbon dioxide and water to oxygen and methane. These chemical conversions take place in a reactor module which contains a solid-metal-

cathode water electrolyzer integrated with a Sabatier reactor. According to design estimates, a fully developed version of the system sized to maintain breathable air for four persons would occupy 67 percent less volume, weigh

60 percent less, and consume 3.4 percent less power than would a system of the same capacity but in which the electrolyzer and Sabatier reactor would be distinct components. Although oxygen is the primary desired end product in the system as originally contemplated, the product methane may also be of value in an industrial version of the system.

As in other systems, electrolysis of water in the reactor module breaks the water down into oxygen and hydrogen, the oxygen leaving the anode and the hydrogen leaving the cathode. The cathode is a tube that is part of an electrode assembly immersed in an aqueous electrolyte containing 55 percent KOH. The assembly also contains a porous anode that surrounds the cathode. A zirconia separator lies between the anode and the cathode (see Figure 1).

While still in monatomic form from the electrolysis, the hydrogen diffuses from the outside (electrolyte side) to the inside of the cathode tube, combining into hydrogen molecules at the interior surface. The hydrogen is used in the Sabatier reaction, in which carbon diox-




Figure 1. A **Reactor Module** in the integrated oxygen-recovery system features a simple, compact design. It contains both an electrolyzer and a Sabatier reactor.




Figure 2. **Hydrogen From Electrolysis Diffuses** through the wall of the cathode into the interior space containing the methanation catalyst.

where would the most powerful development tool be without the recycling genius of edwin hoogerbeets?

If Edwin Hoogerbeets were a developer, he'd be a proud man. Because new Microsoft® Visual C++ 4.0™ is based on the very principle he lives by: Never create from scratch.

Who is Edwin Hoogerbeets? A recycling genius who sees every used object as an opportunity for creative brilliance. The same way a developer might if he or she used new Visual C++ 4.0. No other development tool offers such reusability, allowing you to deliver more robust applications in less time.

Now you can recycle just about anything—but you don't have to

be a genius to do it. The new Component Gallery allows you to store and reuse your own C++ components and OLE controls, as well as 3rd-party components. And, MFC 4.0 gives you more than 150 classes and 120,000 lines of code you don't have to write or test.


The new Developer Studio makes reuse intuitive. With ClassView, you can view the relationships between classes. You'll even have one-click access to the MSDN Development Library, Microsoft Visual Test, Fortran PowerStation, and Microsoft Visual SourceSafe™ version control system. And of course, expanded C++ language

support, including namespaces and RTTI, gives you added flexibility.

Now that you have a better idea of what's possible when you recycle, start with a Visual C++ Subscription, which includes the Visual C++ development system 4.0, plus three additional Subscription Releases shipped automatically.

For more information about the Visual C++ 4.0 Subscription, or to get your free Developer Roadmap CD, call (800) 719-5577. You can also get information at <http://www.microsoft.com/visualc> or by calling one of the resellers listed below. Who knows? You just might become the next Edwin Hoogerbeets.

For More Information Write In No. 502



Component Gallery.
Quick access to OLE controls and reusable C++ components.

MFC 4.0 Library.
Adds latest support for Windows® 95 controls.

Client-Server Support.
Built-in Jet database engine and ODBC support to access enterprise data.

Custom AppWizard.
Now create your own AppWizard for your unique application needs.

Multiple Platform Support. Target Intel®, RISC®, and Macintosh®** platforms with a single codebase.

ASAP Software Express
(800) 883-2911

Programmer's Shop
(800) 446-1185

Programmer's Paradise
(800) 892-1187

Software Spectrum
(800) 840-8194

Microsoft

WHERE DO YOU WANT TO GO TODAY?™

*Versions of Visual C++ 4.0 for RISC and Macintosh available separately. ©1995 Microsoft Corporation. All rights reserved. Microsoft and Windows are registered trademarks and Visual C++, Visual SourceSafe and Where do you want to go today? are trademarks of Microsoft Corporation. Intel is a registered trademark of Intel Corporation. Macintosh is a registered trademark of Apple Computer, Inc.

ide and hydrogen react in the presence of a catalyst to form water and methane. Heretofore, the Sabatier reactor would have been a separate unit.

The advantages of this system arise from the placement of the methanation catalyst inside the cathode tube instead of in a separate reactor unit. This enables transfer of the hydrogen directly and nearly instantaneously from one reaction to the other, so that little or no

free hydrogen leaves the reactor. Another advantage of this system is that the water consumed in the electrolysis is reclaimed in the Sabatier reaction. Yet another advantage is that even the heat generated by the Sabatier reaction can be used to help maintain an elevated reactor temperature that facilitates electrolysis. This reduces the power consumed by the electrolyzer. Besides the production of oxygen, the methane pro-

duced may be of commercial value.

This work was done by F. H. Schubert, R. J. Davenport, and M. G. Lee of Life Systems, Inc., for Marshall Space Flight Center. For further information, write in 38 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-26266.

Selective Oxidizer for Removal of Carbon Monoxide


Multiple catalytic stages at progressively lower temperatures operate without becoming poisoned.

Lewis Research Center, Cleveland, Ohio

A catalytic apparatus selectively oxidizes most of the carbon monoxide (without also oxidizing the hydrogen) in a stream of reformed fuel gas that is fed to a low-temperature fuel cell. It is necessary to oxidize most of the carbon monoxide because the CO content of a typical stream of reformed fuel gas is of the order of 1 percent, whereas a low-temperature fuel cell cannot tolerate CO in concentrations ≥ 25 parts per million (ppm). Catalysts that can be used to oxidize CO selectively include platinum on alumina and a commercial catalyst known as "Selectoxo."

To provide for the oxidization of the CO, a small amount of oxygen or air is mixed into the stream of reformed fuel gas. The gas then flows through a series of catalytic beds. The beds are cooled under thermostatic control, such that each succeeding bed is maintained at a temperature lower than that of the preceding bed (see figure). The reasons for this staged operation at progressively lower temperatures are the following:

- A catalytic bed at a higher temperature [$\approx 350^\circ\text{F}$ (177°C)] typically reduces the level of CO levels from about 10,000 ppm (1 percent) to hundreds of ppm. Such a bed operates stably, with no increase in its outlet CO concentration with time. In other words, the catalyst in such a bed does not become poisoned by the CO.
- A catalytic bed at a lower temperature [$\approx 170^\circ\text{F}$ (77°C)] can initially reduce the concentration of CO from 10,000 ppm to 10 ppm. However, at this high inlet concentration of CO at the lower temperature, the bed is not stable in the sense that its outlet concentration of CO increases with time. In other words, the catalyst becomes passivated; that is, poisoned by the CO.



Catalytic Beds at Different Temperatures can oxidize most of the CO content in the inlet fuel gas stream for a long time without becoming poisoned. A single, lower-temperature bed would become poisoned, while a single, higher-temperature bed would not reduce the concentration of CO to an acceptably low level.

The use of multiple catalytic beds at progressively lower temperatures eliminates the poisoning. The first and hottest bed receives the highest concentration of CO (10,000 ppm) and enough oxygen to oxidize the CO. Because this bed operates at high temperature, it is not poisoned. This hottest bed reduces the concentration of CO from 10,000 ppm to hundreds of ppm.

With its lower CO content, the stream of gas is then fed to a cooler bed, along with more oxygen. In the cooler bed, the CO content is reduced from hundreds of ppm to a level between 0 and 15 ppm. Because the gas that enters the second bed contains much less CO than does the gas that enters the first bed, the second bed is less susceptible to poisoning by CO and its life is extended accordingly.

This concept has been verified by an experiment on a prototype of the apparatus containing two catalytic beds. The first bed was operated at 350°F (177°C) with 1 percent of CO in the inlet gas. The

second bed was operated at 170°F (77°C). At the end of 330 h, the concentration of CO at the outlet from the first bed and the inlet for the second bed was 275 ppm, and the concentration of CO at the outlet of the second bed was 6 ppm. In contrast, the concentration of CO at the outlet of a single catalytic bed operating with an inlet CO concentration of 1 percent at a temperature of 170°F (77°C) increased from an initial level of 5 ppm to a level of 60 ppm after 135 h.

This work was done by John C. Trocciola, Craig R. Schroll, and Roger R. Lesieur of International Fuel Cells Corp. for Lewis Research Center. For further information, write in 66 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Lewis Research Center; (216) 433-2320. Refer to LEW-15630.



KRYTOX®

High Performance Fluorinated Lubricants

KRYTOX Applications:
VALVES AND O-RINGS, PUMP
SEALS & BEARINGS IN CHEMICAL
SERVICE, OXYGEN SERVICE
EQUIPMENT, ELECTRIC MOTOR
BEARINGS, AND CLEAN ROOM
ENVIRONMENT.

CALIFORNIA
12261 Foothill Blvd.
Sylmar CAL. 91342
818 896-4714

ILLINOIS
6348 Oakton St.
Morton, Grove ILL. 60053
847 966-2022

CONNECTICUT
George Washington Hwy.
Danbury, CONN. 06810-7378
203 743-4447

CANADA
514 Carlingview Dr.
Rexdale Ontario M9W 5R3
416 675-3204



KRYTOX Fluorinated Lubricants offer: High Temperature Stability
up to 650°F. **Oxygen Compatibility:** safe for oxygen service. **Chemical inertness.** Insoluble in common solvents. **Low Outgassing. Non-Flammability.** **Compatibility** with plastics, rubber, ceramics and metals. **Extended Service Life** of critical components: reduces downtime and maintenance costs. **Mil-spec grades. No silicone.**

miller-stephenson



mail to:
**miller-stephenson
chemical co., inc.**
George Washington Hwy.
Danbury, Conn. 06810-7378

FOR TECHNICAL
INFORMATION CALL
800-992-2424
(8-4 Eastern Time)
IN CANADA 800-323 4621
(8-4 Eastern Time)

KRYTOX® is a registered trademark of DuPont

For More Information Write In No. 411

SPECIAL INTRODUCTORY OFFER

Please attach your business card and/or fill out address below

ENCLOSED IS **\$5.00** FOR EACH 1/2 OZ. SAMPLE OF :

- ☐ KRYTOX OIL ☐ KRYTOX GREASE
☐ FOR LITERATURE ONLY

INTENDED USE _____

NAME _____ DEPT/TITLE _____

COMPANY _____

ADDRESS _____

PHONE _____

1236-11P/20
NTB/3Q

Silicon Carbide Transistor for Detecting Hydrocarbon Gases

A porous gate would allow passage of gas molecules.

NASA's Jet Propulsion Laboratory, Pasadena, California

A proposed silicon carbide variable-potential insulated-gate field-effect transistor would be specially designed for use in measuring concentrations of hydrocarbon gases. Devices like this one should prove useful in numerous automotive, industrial, aeronautical, and environmental monitoring applications.

The device (see figure) would include a sensing gate that would comprise an open-metal-grid electrical contact (such as chromium) on a layer of porous undoped SiC that has been photo-electrochemically etched in a 6H-SiC wafer. The pores in the undoped SiC layer would be oriented perpendicular to the top of the device by the etching process. The sensing gate would lie on an aluminum nitride insulating layer on top of a layer of n⁺-doped SiC mounted on a suitable dielectric support. Drain and source contacts would be attached to the n⁺ layer, and a variable potential contact would be attached to the metal grid.

Hydrocarbon gas molecules would diffuse through the open metal grid into the porous SiC layer, where they would be adsorbed onto the surfaces of the pores. The hydrocarbon-gas sensor operates by dissociating or electrochemically oxidizing these hydrocarbons adsorbed to the inner surfaces of the SiC detection layer formed by the porous SiC. Dissociation or oxidation reactions are driven by a varying potential applied to the detection layer. Different hydrocarbon species undergo these reactions at different applied potentials so that the device is able to discriminate among various hydrocarbon species. Hydrogen ions produced by the dissociation reactions would travel to the surface of the aluminum nitride insulating layer, giving rise to an electric field that would, in turn, result in a depletion layer in the n⁺-doped SiC channel on the opposite side of the insulator. As in other field-effect transistors, the mag-

nitude of this electric field and thus the extent of the depletion layer would affect the amount of current flowing between the source and drain.

The device can operate at temperatures between 100 °C and at least 600 °C, allowing hydrocarbon detection in hot exhaust gases. The dissociation reaction is detected as a change in the current flow through the transistor. The SiC detection layer can be augmented by replacing the metal grid with one composed of a catalytic metal, which provides a signal without an applied potential at higher operational temperatures. Comparisons between the catalytically produced signal and the varying-potential produced signal may further help identify the hydrocarbons present.


The magnitude of the variable potential on the porous SiC layer would be a measure of the strength of the molecular bond that could be broken by the applied electric field. Thus, to the extent

to which the strengths of molecular bonds could be used to distinguish among chemical species, the applied potential needed to obtain a nonzero reading could be taken as an indication of the detected molecular species. The magnitude of the current in the source-to-drain channel would indicate the concentration of the species.

The number of molecules adsorbed on the surfaces of the pores could eventually become excessive. In that case, the potential applied to the variable-potential contacts would be reversed and increased to drive off the adsorbed molecules.

A prototype sensor composed of the gate structure of the transistor has been fabricated and is undergoing tests. Preliminary results have demonstrated an ability to discriminate between inert gases and hydrocarbon gases such as methane and propylene from about 100 °C to 400 °C.

This work was done by Virgil B. Shields, Margaret A. Ryan, and Roger M. Williams of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 74 on the TSP Request Card.



Bond Breakage due to dissociation and electrochemical oxidation in the pores of the porous SiC layer would generate ions, which would migrate to the surface of the aluminum nitride. There, the electric field generated by the accumulated ions would affect the transistor current according to the basic principle of operation of a field-effect transistor.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial

development should be addressed to the Patent Counsel, NASA Resident Office-JPL; (818) 354-5179. Refer to NPO-19428.

Swivel Total-Temperature Probe

A probe aligns itself with airflow to measure total temperature at high angle of attack.

Dryden Flight Research Center, Edwards, California

Figure 1 illustrates a swivel total-temperature probe. This is an improved probe designed to be mounted at the wingtip of an airplane and to be used for measuring the total temperature of the air when the

airplane flies at high angles of attack.

Flight at high angles of attack has recently become more popular in the fighter community for its potential in tactical maneuvering. Current total-temperature

probes on fighter aircraft were not designed for flight at high angles of attack. A total-temperature measurement is combined with a mach number to compute the ambient temperature, which is




Figure 1. The **Four Fins and Swivel Mount** enable this probe to align itself aerodynamically with the local flow of air. Thus, the stagnated-flow condition needed for accurate measurement of total temperature can be achieved.

NEW FROM ASTRO-MED!

**30 Channels!
Brilliant Monitor!
Huge Memory!
Laser Resolution Chart!**

TRUE FIELD RECORDER®



- Bright, High Response Monitor
- 10, 20 or 30 Waveform Channels
- Laser Quality (300 dpi) Chart Resolution
- Huge 512 KSample Memory per Channel for Data Capture and Analysis
- True Portability: Internal Battery and AC
- Record up to 500 V Peak (Isolated) at 25 kHz Response
- Analyze Data with FFT, etc.
- On-Board Floppy Drive for Setup and Memory Transfer
- Wide Format 11-Inch Chart

The all-new Dash 10 lets you receive up to 30 waveform channels (DC to 25 kHz), see the data in real time on the bright high-speed vacuum fluorescent monitor, record with laser quality fidelity, and *at the same time* capture the data for playback and analysis. Now you can do all this on a truly portable package powered by internal battery or AC. The Dash 10 comes with a powerful software package, has a floppy disk for updates and data archiving, plus RS-232 and GPIB.

Phone, fax or write for details!

Ai Astro-Med, Inc.

Astro-Med Industrial Park, West Warwick, Rhode Island 02893
Phone: (401) 828-4000 • Toll-Free (800) 343-4039 • Fax: (401) 822-2430
In Canada Telephone 1-800-565-2216

For More Information Write In No. 527

Sales and Service Centers throughout the U.S. and Canada

Astro-Med is system certified to ISO 9001

necessary for computing the true airspeed and Reynolds number. It is questionable whether total-temperature measurements at high angles of attack will be necessary on production fighters because control laws and flight-operation decisions are typically based on mach number, calibrated airspeed, or equivalent airspeed; none of these quantities depends on measurement of total temperature. However, true airspeed and Reynolds number are of interest to the flight-research community. Consequently, there was a need to develop a total-temperature probe for flight research at high angles of attack.

A standard total-temperature probe is potentially subject to large errors at high angles of attack because (1) its orientation is fixed and thus cannot be adjusted to stagnate the flow (as is necessary for measuring total temperature) at high angles of attack and (2) deicing heat at the low airspeeds associated with high angles of attack can distort probe readings. When using a fixed total-temperature probe, errors of the first-mentioned type can be mitigated by mounting the probe on the underside of the fuselage to take advantage of a flow-straightening effect of the fuselage at high angle of attack, while errors of the second-mentioned type can be mitigated only by turning off deicing heaters.

The swivel probe, which does not contain deicing heaters, was designed to align itself aerodynamically with the local airflow. The swivel total-temperature probe includes a type-K (Chromel/ Alumel) thermocouple within an inner radiation shield embedded in a tube similar to a pitot-tube on a wingtip-mounted air-data boom.

The performance of the swivel total-temperature probe has been evaluated in flight tests at the NASA Dryden Flight Research Center, using the F-18 High Alpha Research Vehicle (HARV). Excellent results have been achieved in dynamic flight at angles of attack as large as 70° . At the time of submission of information for this article, seventy flights had been completed, with no structural or instrumentation failures.

The data plotted in Figure 2 include results for a fairly dynamic high-angle-of-attack pushover/pullup maneuver. Ambient-temperature profiles from a fuselage-mounted fixed probe, the swivel probe, and a standard-day calculation are shown. The swivel-probe data have been adjusted for an instrumentation bias, the cause of which has not yet been ascertained. The data obtained from the swivel total-temperature probe follow the trends of the standard-day temperature profile much more closely than do the




Figure 2. **These Data Were Obtained** in a flight test that involved highly dynamic maneuvering at high angles of attack.

data from the fixed probe. The errors in the fixed-probe data include the high-angle-of-attack and deicing-heat errors mentioned above. Inasmuch as the flow-straightening effect of the F-18 fuselage mitigates much of the high-angle-of-attack error, a major part of the fixed-probe error is attributed to deicing heat. Also shown in Figure 2 is a plot of the difference between the true airspeeds computed from temperature readings of the fixed and swivel probes during the maneuver in question. The magnitude of the difference was as much as 25 ft/s (7.6 m/s), which is approximately 8 percent of the true airspeed.

These results are preliminary. Work is continuing in an attempt to (1) understand the cause of the bias in the swivel-

probe temperature measurements and (2) document the accuracy of the swivel-probe measurements at numerous static and dynamic flight conditions that involve high angles of attack. The fixed total-temperature probe works remarkably well at high angles of attack with the deicing heater turned off; if such operation is allowable, flight-research data of acceptably high quality can be obtained by use of a fuselage-mounted fixed total-temperature probe.

This work was done by Tim Moes, Doug Nichols, Dirk Vanderloop, and Rich Rood of Dryden Flight Research Center. For further information, make contact with Tim Moes by electronic mail at moes@wilbur.dfrc.nasa.gov. DRC-95-21

Testing Thermophotovoltaic Cells With Black-Body Radiation

Test conditions can be varied conveniently and are reproducible.

NASA's Jet Propulsion Laboratory, Pasadena, California

A method of testing thermophotovoltaic (TPV) cells involves maintaining the cells at various temperatures while exposing the cells to black-body radiation at various intensities from black-body sources at various other temperatures. This method provides for simulation and evaluation of performance under a variety of operating conditions and could thus become a standard testing method for government and industry.

In a TPV apparatus, heat is first converted into photons via a thermal emitter, and these photons in turn are converted to electricity via TPV cells, which are similar to ordinary photovoltaic cells except that they are fabricated to have a bandgap that corresponds to the peak of the spectrum of radiation from the thermal emitter. In principle, the energy-conversion efficiency of such an apparatus can exceed that of a conventional photovoltaic cell if the apparatus comprises a thermal emitter of high emissivity and bandgap-matched TPV cells.

Heretofore, testing of TPV cells has involved measuring their current-vs.-voltage responses during irradiation from lamps or from selective emitters. Such tests have revealed little about performances of cells under various operating conditions because the test conditions (emission temperature and/or emission spectrum, emission intensity, and cell temperature) have rarely been varied. Furthermore, such tests have not been reproducible because the emission temperatures and/or spectra have been incompletely characterized and highly specific to the thermal emitters used.

The present method overcomes these limitations, providing both variability and reproducibility. The black-body spectrum is characterized by Planck's equation and is easily reproducible with a standard black-body emitter. A black-body emitter can be set at various emission temperatures, thus altering the spectrum of the emission as needed to test TPV cells. The intensity of black-body radiation incident on a TPV cell under test can be varied by simply placing the cell at various distances from the black-body emitter. Because the black-body

spectrum is known, the results of tests at various emission temperatures and intensities can be used to predict responses of TPV cells to radiation from non-black-body sources.

This work was done by James J. Lin and Dale R. Burger of Caltech for

NASA's Jet Propulsion Laboratory.

For further information, **write in 68** on the TSP Request Card.

NPO-19333

Pressure Control Questions? See the problem solvers!

Visit us at Booth #2231 during National Manufacturing Week's Design Engineering Show

We make a wide range of pressure regulators and valves for a variety of applications including ground support equipment, test stands, gas reduction and control systems. We help people solve critical design problems by applying our high pressure/high flow hydraulic and pneumatic know-how to their specific needs. We can help you too.

Easy maintenance, consistent performance

Compact modular design facilitates control panel installation and simplifies maintenance. Tescom pressure regulators have gained recognition for their accuracy and sensitivity in applications from analyzers to aerospace.

Get us involved!

Tescom regulators come in pressure reducing, back pressure, dome loaded, two-stage and electronically controlled styles. Options include media compatible materials, pressure ranges (from 5 to 20,000 PSIG), port types and flow capacities ($C_v=.01$ to 8). We'll also create a custom control if that's the best solution.



ISO 9001
Quality System
Certified Company

TESCOM
CORPORATION

INDUSTRIAL CONTROLS DIVISION
12616 Industrial Blvd, Elk River, MN 55330
Call: 1-800-447-9643



Skutterudite Compounds for Power Semiconductor Devices

These materials exhibit high hole mobilities, high doping levels, and high electronic figures of merit.

NASA's Jet Propulsion Laboratory, Pasadena, California

New semiconducting materials with *p*-type carrier mobility values much higher than those of state-of-the-art semiconductors have been discovered. The nine compounds, antimonides CoSb₃, RhSb₃, IrSb₃, arsenides CoAs₃, RhAs₃, IrAs₃, and phosphides CoP₃, RhP₃ and IrP₃, exhibit the same skutterudite crystallographic structure and form solid solutions of general composition Co_{1-x-y}Rh_xIr_yP_{1-w-z}As_wSb_z. Some of these compositions have shown great potential for application to thermoelectric devices.

There are also a number of more complex skutterudite compositions including solid solutions and ternary compounds.

This family of semiconducting materials offers great potential for utility in (a) high-frequency power-semiconductor devices like power field-effect transistors, (b) these and other electronic devices at temperatures above 150 °C where Si cannot be used, and (c) other electronic devices (e.g., tunnel diodes and lasers) made of heavily doped materials. These skutterudite compounds are relatively easy to prepare, and some of them are reasonably inexpensive. Provided lower carrier concentrations can be achieved for these new materials, they might even challenge current state-of-the-art lightly-doped electronic materials used in a variety of junction devices.

The antimonides CoSb₃, RhSb₃, IrSb₃, and arsenides CoAs₃ and RhAs₃ all exhibit semiconducting behavior, with band-gap values ranging from 0.63 to 1.18 eV. The phosphide compounds, currently under investigation, are expected to have even wider band gaps. Due to the exceptionally high hole mobilities, *p*-type skutterudites exhibit high electrical-conductivity values ranging from 2 to $5 \times 10^5 \Omega^{-1} \text{ m}^{-1}$ for a hole concentration of $1 \times 10^{25} \text{ m}^{-3}$.

The room temperature mobility values of *p*-type skutterudites are 1 to 100 times higher than that for *p*-type Si and GaAs at similar carrier concentrations, as seen in the first figure. RhSb₃ exhibits




Figure 1. In **Hall Mobility Versus Carrier Concentration** at 300 K for *p*-type skutterudite compounds, data are compared to *n*-type and *p*-type state-of-the-art electronic materials. (*N*-type CoSb₃ data are also included.)

the greatest hole mobility, $8000 \times 10^{-4} \text{ m}^2\text{V}^{-1}\text{s}^{-1}$ for a carrier concentration of $2.5 \times 10^{24} \text{ m}^{-3}$, which is about 70 times higher than p -type GaAs and still 5 times higher than n -type GaAs. Skutterudites with n -type conductivity can be obtained by doping with selected elements. The electron mobilities of n -type CoSb_3 are comparable to the values obtained for p -type Si and GaAs. Due to the preparation techniques used thus far, skutterudite samples with carrier concentration $< 7.0 \times 10^{22} \text{ cm}^{-3}$ have not yet been obtained, but it is expected that the carrier mobility will increase with decreasing carrier concentrations. The temperature dependencies of the carrier mobilities of the skutterudites also compare favorably with those of state-of-the-art semiconductors. Even at 550°C , the hole mobility of IrSb_3 has been observed to be about $600 \times 10^{-4} \text{ m}^2\text{V}^{-1}\text{s}^{-1}$ for a carrier concentration of $6.5 \times 10^{24} \text{ m}^{-3}$ — about 4 times the value obtained for n -type Si.

The second figure shows the power semiconductor figures of merit for p -type skutterudites and n -type state-of-the-art semiconductors Ge, Si, and GaAs calculated for a carrier concentration of $1 \times 10^{25} \text{ m}^{-3}$. This graph demonstrates that the high mobilities at high doping levels of the p -type skutterudites more than offset their low thermal-conductivity values (one fourth of GaAs), even when comparing to the high electron mobility n -type state-of-the-art electronic materials. This means that the temperature rise of junctions above ambient temperature will be negligible, minimizing heat dissipation problems. Also, the mobilities of the skutterudites decrease slowly with temperature, and this raises the possibility of operating electronic devices at temperatures much higher than possible when using devices made of Si.

This work was done by Jean-Pierre Fleurial, Thierry Caillat, Alexander Borshchevsky, and Jan Vandersande of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 94 on the TSP Request Card.

In accordance with Public Law 96-517, the contractor has elected to retain title to this invention. Inquiries concerning rights for its commercial use should be addressed to:

William T. Callaghan, Manager
Technology Commercialization
JPL-301-350
4800 Oak Grove Drive
Pasadena, CA 91109

Refer to NPO-19378, volume and number of this NASA Tech Briefs issue, and the page number.

Power Semiconductor Device Figures of Merit:
PHC = Power Handling Capability
BFM = Baliga Figure of Merit
BHFFM = Baliga High Frequency Figure of Merit





Figure 2. Figures of Merit are shown for p -type skutterudite and state-of-the-art electronic materials for power semiconductor devices. (All data for a carrier concentration of $1 \times 10^{19} \text{ cm}^{-3}$ are normalized to n -type Si.)



**In high-heat torches,
ceramic insulators just don't
cut it like DuPont Vespel®.**

DuPont Vespel® polyimide insulators last up to six times longer in plasma arc torches than fragile ceramic. In fact, Vespel® delivers superior strength and durability at all operating temperatures.

If you want a cost-effective solution that works, specify the parts that last. Vespel®.

To put Vespel® to work in your application, call 1-800-426-7246.



Vespel®
Only by DuPont

Modified Process for Formation of Silicon Carbide Matrix Composites

The modification reduces damage to SiC fibers during formation of an SiC matrix.

Lewis Research Center, Cleveland, Ohio

A modified version of a process for making SiC-fiber/SiC-matrix composite material reduces damage to the SiC (SCS-6) fibers and to the carbon-rich coatings on the fibers. In both the unmodified and modified versions of the process, the matrix material that surrounds the fibers is reaction-formed sili-

con carbide (RFSC); it is made by a succession of infiltration and pyrolysis steps, as explained more fully below. Ideally, the carbon-rich surface layers on the fibers should be retained as low-shear-strength interfacial layers that make the composite less brittle. In the unmodified process, these carbon-rich

layers are destroyed and the underlying SiC fibers are damaged, also as explained more fully below.


In both the unmodified and modified versions of the process, the first step is to infiltrate a stack of SiC fiber mats with a liquid polymer-forming mixture that comprises a high-char-yield monomeric resin, a pore-forming agent, a curing agent, and carbon powder filler. The mixture is cured to encase the fiber mats in a porous polymer matrix. The resulting composite intermediate product is heated to drive off the pore-forming agent and pyrolyze the matrix to a porous carbon char.

In the unmodified version of the process, the next step is to infiltrate the porous carbon matrix with liquid silicon or a silicon alloy. The liquid silicon or silicon alloy reacts with the carbon matrix to form a matrix of mostly silicon carbide with other phases mixed in. Unfortunately, the liquid silicon also reacts with the carbon-rich surface layers on the SiC fibers, consuming those layers and attacking the underlying SiC fiber material. Such attack can be prevented by use of protective coats on the SiC fibers, but of course, protective coating increases the cost.

In the modified version of the process, the damage to the SiC fibers is reduced, without need for protective coating. The modification consists of the addition of a second polymer-infiltration-and-pyrolysis step to increase the carbon content of the porous matrix before infiltration with liquid silicon or silicon alloy. The polymer-forming mixture used in this step is similar to that used in the first step except that it does not contain carbon powder. Next, the matrix is infiltrated with liquid silicon or silicon alloy. As before, the silicon reacts with the carbon matrix material to form a silicon carbide matrix, but in this case, the silicon carbide fibers and their carbon-rich surface layers remain intact.

This work was done by Donald R. Behrendt of Lewis Research Center and Mrityunjay Singh of NYMA, Inc. For further information, write in 41 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Lewis Research Center; (216) 433-2320. Refer to LEW-15690.



Here's the clincher
for anyone who
designs for assembly.

Less is more. Less parts, less assembly steps, less assembly time – all yield more productivity and more cost reductions. To achieve this, designing for assembly (DFA) is critical.

PEM® products address this requirement. Just punch or drill a hole and press a PEM fastener into place. PEM self-clinching fasteners install permanently into this sheets. There are fewer parts and fewer total pieces to handle during assembly. We offer threadless and multi-function fasteners to further meet your DFA needs. These include SNAP-TOP® (shown in

photo above) standoffs which eliminate the need for screws, locating pins for quick alignment of mating parts, P.C. board fasteners and many others.

If you want less to give you more, contact us at: **1-800-237-4736**. We can show you how PEM fasteners and presses can help you meet your DFA needs.

For instant info, call:
The PEMFAX™ Information System

1-800-736-6863

Specify document number 7131

Clinch it with PEM®
FASTENERS & PRESSES

See us at
The National Design Show
Booth #1647

145

Penn Engineering & Manufacturing Corp.
P.O. Box 1000 • Danboro, PA 18916-1000

©1995

DSM Desotech is

for Custom UV/EB Coatings

1ST


1ST Commercial UV Coating for Optical Fiber

1ST EB Curable Coating for Magnetic Media

1ST UV Curable SMC Sealer

1ST Commercial UV Curable Rapid Prototyping Resins

1ST UV Curable Paper Transparentizing Resin



DSM Desotech Inc.

DSM

Phone: 800-223-7191 or (847) 468-7721 Fax: (847) 468-7785

For More Information Write In No. 415

Epitaxial Silicon Doped With Antimony

High purity can be achieved in layers of arbitrary thickness.

NASA's Jet Propulsion Laboratory, Pasadena, California

High-purity epitaxial silicon doped with antimony can be made by chemical vapor deposition, using antimony pentachloride (SbCl_5) as the source of dopant and SiH_4 , SiCl_2H_2 , or another conventional source of silicon (see figure). Epitaxial silicon


doped with antimony is needed to fabricate impurity-band-conduction photodetectors that operate at wavelengths from 2.5 to 40 μm ; in contrast, impurity-band-conduction photodetectors previously made from silicon doped with arsenic

operate in the narrower wavelength range of 2.5 to only 28 μm .

Previously, in chemical vapor deposition in which organometallic compounds were used as sources of dopants, it was found that the carbon in those compounds gave rise to carbon contamination in the deposited materials. The absence of carbon in the compounds used in the present method eliminates that particular source of contamination.

Epitaxial silicon doped with antimony can be deposited to arbitrary thickness by the present method. Demonstration deposits have been made in thicknesses up to 25 μm , with residual impurity concentrations as low as 10^{12} atoms/ cm^3 and with antimony-dopant densities from less than 10^{17} to more than 4×10^{18} atoms/ cm^3 .

This work was done by James E. Huffman and Bradley L. Halleck of Rockwell International Corp., Science Center for NASA's Jet Propulsion Laboratory. For further information, write in 72 on the TSP Request Card. NPO-19425



SbCl_5 is the source of antimony dopant in silicon deposited from chemical vapors. SbCl_5 is a liquid at room temperature and can be used in a typical chemical-vapor-deposition reactor like those in common use.

You Can't Afford to Miss

CLEO[®] '96

The world's most important
Conference and Exhibit
for lasers and electro-optics

JUST GOT EVEN BETTER.

INTRODUCING ...
L * E * A * P

**LASER & ELECTRO-OPTICS
APPLICATIONS PROGRAM**

Training and technology solutions
for design and manufacturing engineers!

- Imaging Systems Design
- Measurement How To's
- Case Studies in Product and Instrumentation Design

Lasers and Electro-Optics for Science
• R&D • OEM • End User • Engineering •

Featuring Special Applications Programs for
• Biology and Medicine • Imaging Systems Technology •

Use the free CLEO **Fax-on-Demand**
Service for comprehensive conference and
exhibit information. **Dial 800-828-7753.**

For more information, contact:
OSA Corporate Services
2010 Massachusetts Avenue, NW
Washington, D.C. 20036
Tel. 800 723 CLEO
Fax 202 416 6100
Email cleoex@osa.org

For More Information Write In No. 612

**CONFERENCE ON
LASERS AND
ELECTRO-OPTICS**

AND

**QUANTUM
ELECTRONICS AND
LASER SCIENCE
CONFERENCE**

**Anaheim
Convention
Center**
ANAHEIM, CA

**Technical
Conference**
JUNE 2-7, 1996

Exhibit
JUNE 4-6, 1996

Sponsored by:

**OSA
IEEE/LEOS
APS**


In Cooperation with:

**Quantum Electronics Division
of the European Physical
Optical Society**

**Japanese Quantum Electronics
Joint Group**

C
L
E
O
-
Q
E
L
S
-
9
6

FEDERAL LAB
Electronics
TECH BRIEFS




from the root of your ideas towering products grow

INTRODUCING ACCEL EDA™ – the all-new environment for PCB design. The result of our Sequoia Project, ACCEL EDA joins the power and flexibility of P-CAD® with the speed and ease-of-use of Tango®. Scale new heights with advanced features for mixed signal designs and our integrated InterRoute™ shape-based routing tool. Expand the environment with tight interfaces to Viewlogic™, CCT™ and popular analysis tools. All backed by the service and support that has made ACCEL and its value-added partners the leaders in desktop EDA.

ACCEL

EDA

POWERFUL PCB DESIGN FOR WINDOWS™



◀ AN OBJECT-ORIENTED DATABASE ENABLED THIS SPLIT POWER PLANE TO RETAIN ITS INTELLIGENCE AND PASS DRC.

CALL FOR YOUR
FREE EVAL SOFTWARE,
OR TO SET UP
AN ON-SITE DEMO.



CALL TODAY. See how ACCEL EDA can help you grow good ideas into great products.



ACCEL Technologies, Inc.
800 488-0680 Sales
619 554-1000 Service
619 554-1019 Fax

FEDERAL LAB Electronics TECH BRIEFS

Federal Lab Electronic Tech Briefs Supplement to NASA Tech Briefs March 1996 Issue Published by Associated Business Publications in cooperation with the Federal Laboratory Consortium for Technology Transfer

ELECTRONIC TECH BRIEFS

- 4a Simple Analytic Tool for Photovoltaic Module Diagnostics
- 4a Mapping Pixel Windows to Vectors for Parallel Processing
- 6a Secure Communications Using Quantum Cryptography
- 10a Diffusion-Barrier Contacts for Solar Cells
- 10a Neutron Diffraction Determines Stresses in Materials
- 12a CCD Detects Two Images in Quick Succession
- 12a Electroabsorption in Doped Asymmetric Double Quantum Wells
- 14a Temperature-Compensated Sapphire Microwave Resonator

- 16a Using a Sealed Tube Neutron Generator for Fossil Fuel Exploration
- 16a CVD of Thin Films From Single Organometallic Precursors
- 19a Transportable Molecular-Beam Mass Spectrometer
- 20a Ferroelectric Phase Shifters for Electronic Scanning

DEPARTMENTS

- 2a News Briefs
- 21a New Products

On the cover:

A team of scientists and engineers at Sandia National Laboratories' Albuquerque facility are pioneering the development of micromachinery. In the photo, a microgear smaller than a human hair drives a gear 30 times its size at 4800 rpm. Sandia researchers say theirs was the first silicon micromotor to drive external gearing and to be built entirely by microelectronic fabrication. The rectangular brackets on the large gear prevent it from warping. It functions as an optical shutter when light passes through the rectangular opening (partially shown, bottom right) in certain gear positions. *Photo courtesy Sandia National Laboratories.*

FREE CATALOG PRECISION OPTICS, LASERS & OPTICAL INSTRUMENTS

Inside you'll find:

- Optical Components
- Test Equipment
- OEM Optics
- Video Systems
- Machine Vision
- Critical Measuring
- Positioning Equipment
- Lasers & Laser Optics
- Magnifiers & Comparators
- Microscopes & Telescopes

**OVER 8,000
OPTICAL
PRODUCTS**



At Edmund Scientific, we specialize in providing technical design and research solutions with our extensive line of precision optics and optical instruments—all of which are in stock and available for immediate delivery. Call today for your FREE 236 page catalog.

Edmund Scientific Co.

Dept. 16B1, N954 Edscorp Bldg., Barrington, NJ 08007-1380
Phone: 609-573-6250 Fax: 609-573-6295

CALL FOR YOUR FREE COPY 1-609-573-6250

Switch to LUMITEX... the long-life, low-power backlighting solution.

LUMITEX Fiber-Optic Panels provide unmatched design flexibility for switch applications

- Up to 100,000 hours service life
- One LED can provide high, uniform brightness for one or more switches
- Superior tactile response ensures positive actuation feedback
- Costs less than EL and other lighting alternatives

For more information or technical assistance, contact LUMITEX (phone: 1-800-969-5483; fax: 216-243-8402) or your local LUMITEX representative.




Lumitex, Inc.
Creators of Woven Light
8443 Dow Circle
Strongsville, OH 44136



Both sides of this B.E. Aerospace Passenger Control Unit are lit from one LED.


Die cut capability -
lets you adapt LUMITEX Panels to meet specific design requirements

PANEL BACKLIGHTING




Thin, uniform, heat free backlighting of panel graphics, bezels & nameplates.

MEMBRANE SWITCH BACKLIGHTING



Fiber optic backlighting of membrane switches with plastic and metal domes, flat panels and elastomeric keypads

LCD BACKLIGHTING



Superior alternative to EL for backlighting LCD's

Features & Benefits

- Thin (.013" minimum) & Flexible
- Low Tooling, Unit, Assembly & Maintenance Cost
- Uniform Brightness
- EMI & Heat free
- Wide Temperature (-40 °C to +80 °C) & Humidity (0% to 100%) extremes
- Low Power Requirement
- No Inverter Required



Poly-Optical® Products, Inc.

Let There Be Light™

17475 Gillette Avenue Irvine, CA 92714-5612

Phone 714/250.8557 FAX 714/250.1840

Internet: <http://www.poly-optical.com/products>

E-mail: popi@ix.netcom.com

Suppliers of plastic optical fiber devices for light, image, and data transmission.

See Thomas Register & EEM Catalogs

NEWS BRIEFS

News of the Industry and Federal Laboratories

University of Michigan scientists have conceived an electron accelerator capable of producing the shortest electron pulses on record and accelerating them to very high energies. According to Donald Umstadter, associate research scientist in the U-M's Center for Ultrafast Optical Science, coupling advanced laser technology with tabletop particle accelerators may make the latter as common in scientific research laboratories as the electron microscope. The development of chirped pulse amplification (CPA) in 1987 made it possible to generate very short laser pulses with peak powers as high as 100 trillion watts. Gerard Mourou, director of the U-M center, explains that focusing such power on a spot many times smaller than the period at the end of a sentence produces beams of enormous intensity. "The electric field surrounding this focal spot is strong enough to trap subatomic particles like electrons and accelerate them to high energies within just a few centimeters, instead of many kilometers as in conventional particle accelerators," Mourou says. Among a series of U-M experiments last year, scientists demonstrated the first collimated electron beam accelerated by a laser alone, running laser pulses through a gas jet to produce a plasma wave capable of accelerating electrons to energies of 1 billion eV in a distance of one centimeter. The National Science Foundation supports research at the center.

Researchers at the National Institute of Standards and Technology (NIST) have developed a new method for calibrating performance measurements on monolithic microwave integrated circuits (MMICs). These microelectronic chips are finding a place in wireless communications and "smart" transportation systems, but they challenge conventional means of charting performance. Dylan Williams and Roger Marks of NIST's Electromagnetic Fields Division (Boulder, CO) have come up with a way of deriving accurate results at high frequencies on a wide variety of MMICs fabricated with both coplanar waveguide and microstrip transmission lines. For more information contact Robert Judish, Div. 813.06, NIST, Boulder, CO 80303-3328; (303) 497-3380; E-mail: judish@boulder.nist.gov.

The Naval Research Laboratory has awarded Spire Corp. (Bedford, MA) a contract to further development of two innovative electronic circuits: monolithic complementary heterojunction bipolar transistor (CHBT) push-pull power amplifiers and operational


amplifiers. Phased-array radar and mobile phone communications can utilize high-efficiency microwave and millimeter-wave power amplifiers, and operational amplifiers find broad application in analog electronics requiring high speed A/D and D/A converters. Spire will use selective metallorganic chemical vapor deposition to integrate both NPN and PNP heterojunction bipolar transistors on one wafer in a planar topography. The company plans to involve end users in the work during the circuit design phase.

The Materials Research Society gave Federico Capasso of Bell Laboratories (Murray Hill, NJ) its medal, honoring outstanding innovations and discoveries that promise to advance materials science significantly, for his work in engineering semiconductor research and design. A 19-year veteran of Bell Laboratories, Capasso pioneered a technique known as bandgap engineering, which can create materials with electrical and optical properties that do not exist in nature. Mark Melliard-Smith, chief technical officer at AT&T Microelectronics, called Capasso's discovery of artificially structured materials "as significant to the semiconductor industry as is genetic engineering to biology." By controlling layer thickness in materials grown with molecular beam epitaxy, Capasso and his Bell Labs research team have opened the way for a new family of semiconductor devices, including detectors, lasers, and transistors.

Scientists at the Department of Energy's Oak Ridge National Laboratory (ORNL) and the University of Tennessee have combined forces in the Joint Institute for Molecular-Based Engineering and Science (JIMBES). The institute will exploit the neutron and x-ray scattering methods and molecular-level computational techniques spawned at the two sites, applying physical and biological sciences to the development of new products and processes. The Small Angle Neutron Scattering facility at ORNL enables researchers to perform molecule-level experiments that complement their calculations.

BIOSYM/Molecular Simulations, a San Diego-based developer of molecular simulation systems, has given the University of Chicago \$10 million in computer software under a cooperative research and development agreement. University scientists and employees of the company will explore ways in which these computer tools can enhance research and development, technology infrastructure, curriculum design, networking, training, and new forms of imaging such as virtual reality. The University will assume a leading role in molecular research next year when the Advanced Photon Source, a \$480-million synchrotron, opens at Argonne National Laboratory, which is operated by the University for the Department of Energy.

EMSS Quantum Leap FOR MECHATRONICS



TRANSIENT SOLUTIONS FOR ELECTROMECHANICAL SYSTEM SIMULATION


EMSS is a technology breakthrough in the design and analysis of electromechanical systems. This leap in technology combines finite element analysis (FEA), mechanical dynamics and electronic circuit equations in a comprehensive, easy-to-use software package for electrical and mechanical engineers.

With EMSS, electromagnetic devices designed with Ansoft's Maxwell software are simulated under true operating conditions. Voltage and current excitations from the drive circuitry combined with electrical and mechanical loads and mechanical motion are accurately simulated on MS Windows based PCs and Unix workstations.

Ansoft, the leader in electromagnetic analysis, has bridged the gap between electrical, mechanical and electronic engineers with one easy-to-use software package that drastically reduces time to market. Applications include: solenoids, transformers, sensors, and a host of other electromechanical devices.

EMSS includes a schematic capture module to drive transient simulations, offering graphical editing of electrical circuit models with automatic node numbering. The equivalent electrical circuit can be solved in either Maxwell SPICE or exported to Analogy's Saber format.

Once the circuit has been defined and solved, the results can be viewed in the signal post processor. Magnetic FEA simulations need only be completed once and used for both initial conditions and time domain simulations - saving critical design time.



TAKE THE LEAP. Call 412-261-3200
for a FREE 30 day evaluation package.

For More Information Write In No. 463



Ansoft Corporation
Pittsburgh, PA 15219-1119 USA
TEL (412) 261-3200
FAX (412) 471-9427
Internet: EMinfo@ansoft.com
http://www.ansoft.com

Simple Analytic Tool for Photovoltaic Module Diagnostics

A nondestructive technique measures shunt resistance of individual cells to quickly identify electrical performance problems.

National Renewable Energy Laboratory (NREL), Golden, Colorado

Shunt resistance is one of the most basic and informative parameters of photovoltaic (PV) performance. Low shunt resistance of individual cells should be one of the first red flags in identifying electrical performance problems with PV modules. Until now, however, once a module was encapsulated, it was no longer practical to measure those resistances.

Researchers at the NREL recently developed a method that allows easy and accurate measurement of the shunt resistance, from fractions of an ohm to thousands of ohms, of each cell of a completed series-connected encapsulated module, without damaging the module. The technique is quick and simple, and requires only standard inexpensive electronic equipment.

Electrical shunts are low-resistance leakage paths that divert current away from the intended power load in PV systems. For PV modules with otherwise effective materials and design, shunt losses are a principal symptom of problems that can cause cell failure or poor performance.

Shunt resistance is a particularly powerful diagnostic parameter. It applies to any normal light condition, not just the one under which it was measured. Because shunt resistance is quantitative, you can set threshold values for quality control and compare val-

ues from different cells or modules. You can also check the values again after stress testing or regular use, or if the module later fails. Shunt-resistance values can also be used in computer models to predict the performance of modules under the varying intensity of actual light conditions for a particular location. Shunt-resistance measurement can detect problems within individual cells that are not readily detectable by traditional full-module current-voltage (I-V) tests. And the NREL technique is most accurate for the low shunt-resistance values that indicate problem cells.

Taking less than a minute per cell to measure, the NREL technique gives cell-by-cell shunt resistance for modules with any number of series-connected cells (nearly all PV modules currently produced). It does so without having to de-encapsulate--remove the protective cover material--or otherwise damage the module. NREL researchers know of no other such nondestructive test for individual-cell shunt resistance.

This technique requires an AC signal generator, a DC voltage supply, an operational amplifier, and a phase-sensitive amplifier, all common laboratory equipment. This simple technique is based on sequentially blocking the light to each cell in a module, measuring the open-circuit resistance, and subtracting

the open-circuit resistance of the fully exposed module. If that difference is small, the cell has low shunt resistance that will significantly impair its performance.

Individual-cell shunt-resistance testing is valuable for all phases of the PV product's life. Measuring shunt resistance can verify the adequacy and optimization of cell fabrication steps; it can be used for module performance characterization and qualification testing; during manufacture, it can be an excellent quality-control and quality-assurance tool; and it is very helpful for failure analysis.

The technique is a simple diagnostic tool that gauges one of the most informative parameters of PV cell and module performance. It allows quick and easy testing of series-connected cells for any size module without damaging it. It is particularly valuable for assessing thin-film PV modules, many of which, even before encapsulation, do not allow access to individual cells without causing damage.

*This work was done by Tom Basso and Tom McMahon of the **National Renewable Energy Laboratory**. Inquiries concerning patent status and availability of rights and licenses should be directed to the NREL Technology Transfer Office at (303) 275-3008.*

Mapping Pixel Windows to Vectors for Parallel Processing

The mapping is performed by matrices of transistor switches.

NASA's Jet Propulsion Laboratory, Pasadena, California

Arrays of transistor switches have been devised for use in forming simultaneous connections from (1) a square subarray (window) of $n \times n$ pixels within an electronic imaging device that contains an $np \times np$ array of pixels to (2) a linear array of n^2 input terminals of an electronic neural network or other parallel-processing circuit. In

mathematical terms, the transistor switches implement binary switching matrices that map the pixel window to an n^2 -dimensional vector (see figure); that is, the brightness-level output signal of each pixel constitutes one component of the vector, while the vector constitutes the collection of inputs to the parallel-processing circuit.

This mapping method helps to realize the potential for rapidity in parallel processing for such applications as enhancement of images and recognition of patterns. In providing simultaneous connections, this method overcomes the timing bottleneck of older multiplexing, serial-switching, and sample-and-hold methods.



Get A Grip On Your Vibration Measurements.



When you're faced with a unique vibration measurement problem, look to Endevco for an innovative solution.

We offer the industry's widest range of piezoelectric, ISOTRON™, piezoresistive, and variable-capacitance accelerometers. Plus our new servo-force-balance devices.

Unlike other manufacturers, we use many different sensing materials and technologies, including micro-machined silicon,

in our designs. So we'll help you select the sensor with the best performance characteristics for your application. Whether you're measuring a few μG 's or 200,000 G's.

Plus Endevco makes a complete line of electronic instruments and low-noise cable assemblies. So we're your ideal source for total vibration measurement solutions.

And fast delivery and unsurpassed value are assured.

For details on how we can help put your vibration measurement on solid ground, just call (800) 982-6732.




To request your free Endevco Dynamic Measurement Poster, with key formulae, conversion tables, and constants, call (800) 982-6732 or e-mail us at freebie@endevco.com.



ENDEVCO 

M MEGGITT
AEROSPACE

30700 RANCHO VIEJO ROAD, SAN JUAN CAPISTRANO, CA 92675 USA, TEL (800) 982-6732 FAX (714) 661-7231



All The Pixels in the Selected 8×8 Window are mapped simultaneously to positions along a 64-element linear array or, equivalently, to components of a 64-dimensional vector.

In addition, these older methods lack flexibility of connection patterns, whereas in the present method, the connection patterns can be varied at will by changing the matrix elements. Changing connection patterns can result in rearrangement of the sequence of components of the vector. Changing connection patterns can be used for a variety of purposes; for example, rotating or translating the window image fed to the parallel processor.

The mapping is performed in two stages. In the first stage, the mapping is from the pixels of the selected window to an intermediate windowlike $n \times n$ array of nodes. For this purpose, there must be a total of p^2 switches fanning in to each node from the corresponding pixels of the p^2 windows, and for each node, one of these switches is turned on to receive the signal from the corresponding pixel of the selected window. Thus, this mapping re-

quires $n^2 p^2$ switches and is represented by an $np \times np$ matrix, which is denoted as T .

It is possible to select an $n \times n$ -pixel window that straddles one or more boundaries between adjacent $n \times n$ subdivisions of the overall $np \times np$ array of pixels. In such a case, the T -mapping yields vector components in the incorrect sequence. The second-stage mapping corrects the sequence. This mapping is represented by an $n^2 \times n^2$ matrix, M , and requires n^4 switches — one switch from each of the n^2 nodes to each of the n^2 input terminals of the parallel processor. M is also used to rearrange the components of the vector as needed for the desired transformation (e.g., rotation or translation) of the window image.

The "brute-force" method for effecting the same mapping with a flexible connection pattern requires $O(n^4 p^4)$ switching transistors [where $O(x)$ denotes a number proportional to a number of the order of x]. For reasonable values of n and p (e.g., $n, p \geq 8$), the circuitry needed to implement so many switches can be very complex and large, and its parasitic capacitance can be excessive. The present method can be implemented with simpler, smaller, and less expensive circuitry because it requires a smaller number of switching transistors; namely, $O(n^2 p^2 + n^4)$.

This work was done by Tuan A. Duong of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 99 on the TSP Request Card. NPO-19431


Secure Communications Using Quantum Cryptography

Security over "open" fiber networks can be obtained through shared cryptographic key material with single-photon transmissions.

Los Alamos National Laboratory, Los Alamos, New Mexico

Cryptography, the science of secret communications, is becoming increasingly important with the growth of computer networks and electronic transmissions. When personal, financial, military, or national security information is transferred from place to place, it becomes vulnerable to eavesdropping tactics that have catastrophic potential. The goal of encrypting information can be accomplished if the sender and recipient both possess a secret random bit sequence (binary numbers), known as "key" material, which is used for encryption by the sender and decryption by the recipient.

Key material is therefore a valuable resource even though it conveys no information itself. But the initial step of "key distribution," whereby the two parties acquire the key material, must be



The **Single-Photon Laser Source (L)** initiates the quantum key-generation process by sending a signal on the quantum channel to a detector that sorts out the correspondences between the parties' 0s and 1s, setting up a common subset as shown by the "distilled keys" (checks).

FLUKE®

A scope that does both analog and digital? I'd like a closer look.

Sometimes a digitized waveform

isn't enough.


So, I must check

the analog waveform.

CombiScope gives me

both views

at the touch of a button.




It's your responsibility. But each new problem has hidden tricks, so you check them and re-check them.


The Fluke CombiScope™ is the most powerful scope with DSO and analog modes that show the whole picture. It's packed with the features a professional needs. The exclusive Autoranging feature lets you move from test point to test point while the scope automatically adjusts itself. Eighteen automated voltage, delay and time measurements

are standard. Seven versatile models make sure you're covered. And FlukeView™ software for Windows® adds PC power to your CombiScope.

When the pressure is on and the problems are tough, a closer look can mean getting closer to the solution. Take a look at the Fluke CombiScope today.



Analog mode



Digital mode



Don't assume anything. Call Fluke at 1-800-44-FLUKE.

accomplished with a high level of confidence that a third party cannot acquire even partial information about the bit sequence.

With conventional communications, which can be subject to passive monitoring by an eavesdropper, it is impossible to generate a certifiably secret key, and so cumbersome physical security measures for key generation, distribution, storage, and destruction after use are required. Secure key distribution becomes possible, however, if the two parties can communicate with single-photon transmission using the emerging technology of quantum cryptogra-

phy, or more accurately, quantum key distribution (QKD).

The security of QKD is based on fundamental principles of quantum physics. A unique technology facilitates the unbreakable encryption of communications between secure "islands" over "open" optical fiber networks by allowing key generation to take place at the time it is required.

Two parties (Alice and Bob in the figure) start a quantum key-generation procedure by producing their own independent sets of random bits. They possess a quantum channel and a public channel over which they can

compare their numbers to distill a common subset.

Alice proceeds by preparing a single photon with her laser source (L) for each bit in her set of numbers in one of two possible ways, depending on whether her number is a 0 or a 1. Each photon is then sent over the quantum channel. Bob, who also proceeds through his numbers bit by bit in synchronization with Alice, performs one of two possible measurements on each photon, depending on whether his number is a 0 or a 1.

A photon will never trigger Bob's detector (D) if his number is different from Alice's, but it will do so with a 50% quantum-mechanical probability if their numbers are the same. Bob labels a number from his set as a "hit" if he detects a photon and then passes this information (but not the number itself) to Alice over the public channel. Alice then labels her numbers that were hits on Bob's end, and a shared secret key emerges as the common set of hit bits.

QKD only identifies 50% of the bits shared by Alice and Bob, but this inefficiency is the price of immunity to eavesdropping: physical laws ensure that Alice's two preparations (0 or 1) cannot be distinguished with 100% probability by either Bob or the eavesdropper. So eavesdroppers who attempt to tap into the quantum channel are unable to intercept the key data because they cannot attach 0 or 1 labels to the photons that Alice sends. Furthermore, Alice and Bob can detect eavesdropping because the methods used to "siphon" photons off the quantum channel irreversibly alter their states.

Los Alamos is developing a fiber optical implementation of QKD. For long propagation distances (greater than 1 km), the production and detection of single photons at a wavelength of 1.3 micrometers is required. Because there are no commercial single-photon detectors available at this wavelength, the first task was to develop this capability. The team has already demonstrated key distribution in a laboratory environment with an all-fiber QKD prototype. It is expected that a quantum-cryptographic link can be established over optical fibers between two areas separated by a distance of 7.5 km.

*This work was done by the Physics Division of **Los Alamos National Laboratory**. For more information, contact Dr. Richard J. Hughes, Neutron Science and Technology Group (P-23), MS D406, LANL, Los Alamos, NM 87545; (505) 667-3876; E-mail: hughes@lanl.gov.*

Toshiba 2Mb Video RAM

For powerful graphics, draw on our 2Mb VRAM.



Organized 256K X 8, our 2Mb VRAM is picture-perfect.

With two operating modes to choose from—Fast Page Mode (FPM) and Extended Data Out (EDO)—it offers increased speed and performance. The dual ports let you draw and refresh at the same time. And it's available in SOJ packaging.

For more information on Toshiba 2Mb VRAM, just call us at the number below, or visit us at <http://www.toshiba.com/taec> on the Internet.

Our memory will serve you well.

TOSHIBA

TOSHIBA AMERICA ELECTRONIC COMPONENTS, INC.

This is the world's most advanced data recorder.



And dat's DAT.

Less is more.

The Sony PC200 Series is an entire new generation of data recorders. The smallest go-anywhere recorders available. With features and performance that put them in a class by themselves. And with configurations from 2 to 64 channels, bandwidths from DC to 100 KHz, and even a hybrid for simultaneous wideband analog and/or digital data, there's a model to precisely fit your requirements.

The DAT advantage.

Sony pioneered DAT, and we know how to get the most out of it. The new PC200 Series can record up to 6 hours of data with an overall transfer rate of up to 3.072 Mbps. Good data, with a signal to noise ratio greater than 82dB. Nothing else comes close.

The ins and outs.

Since small size enhances portability, Sony provides an RS232 for onsite remote control via laptop, palmtop, your choice. Going the other way, the SCSI IF500 interface provides optimum data transfer to your PC or workstation. Because the faster your data becomes information, the better.

The soft stuff.

Imbedded in every PC200 Series recorder is Table of Contents software utilizing the first two minutes of tape to summarize its contents for fast and easy searches on the computer. You can write each recording block's sub data such as ID, ADDRESS, and RANGE. Even TIME CODE. And, with Sony's powerful PCscan™ data acquisition software, turning your data into information was never easier.

The Sony advantage.

Of course, when you choose the PC200 Series data recorders, you choose Sony, and you know what that means in terms of constant technology advancement and leadership, rugged reliability, and full support. Only Sony could make data recording exciting. Give us a call and we'll tell you just how exciting it gets. All DAT and more.

SONY®

Sony Magnescale America, Inc.

137 West Bristol Lane • Orange, CA 92665
(714) 921-0630 • FAX (714) 921-1162

Sony is a registered trademark of Sony Corporation

For More Information Write In No. 466

Diffusion-Barrier Contacts for Solar Cells


The barriers enhance performance at low temperatures and low light intensities.

NASA's Jet Propulsion Laboratory, Pasadena, California

Diffusion-barrier contacts can be incorporated into silicon-based solar photovoltaic cells to reduce degradation of performance at low temperatures and low light intensities. Heretofore, the low-temperature, low-light-intensity performances of such cells have been degraded by interactions that occur between metal contacts and silicon during fabrication.

The present diffusion-barrier contacts are thin, electrically conductive strips of TaSiN, which are deposited on the front surface of each affected cell. The strips of the front-surface metal contact grid are then deposited on the diffusion-barrier contacts (see figure). The diffusion-barrier contacts prevent diffusion of metal into the silicon at the high processing temperature.

This work was done by Paul M. Stella, Frederick S. Pool, and Marc Nicolet of



Electrically Conductive Diffusion Barriers of TaSiN prevent diffusion of metal from the overlying metal contacts into the underlying silicon during processing at high temperature, thereby improving performance during subsequent use in low-intensity light at low temperature.

Caltech and Peter A. Iles of Applied Solar Energy Corp. for NASA's Jet Propulsion

Laboratory. For further information, write in 8 on the TSP Request Card. NPO-19513

Neutron Diffraction Determines Stresses in Materials

The Intense Pulsed Neutron Source can assess quality and life expectancy.

Argonne National Laboratory, Argonne, Illinois

With a unique combination of analysis and research instruments developed at Argonne National Laboratory, scientists can use the lab's Intense Pulsed Neutron Source (IPNS) to interrogate materials that make up ceramic engine parts, nuclear reactor components, and advanced jet engines and make predictions about their quality and life expectancy.

Large residual stresses can develop in composites during fabrication, and determination of these stresses is crucial for predicting composite performance. By learning how cooling, heating, and processing affect residual stress, stronger and tougher composites can be developed. The only effective, nondestructive way to measure internal residual stress in composites is with neutron diffraction. Neutrons penetrate materials and permit bulk measurement of strain, whereas x-rays measure only surface stresses.

IPNS is a pulsed source with six detector banks that can provide diffraction data in various spatial directions simultaneously. A number of companies and laboratories are using this data to understand the processing of composites and to validate computer models that predict mechanical properties. The result could

be improved processes that make better composites.

Argonne tests critical materials for industry, such as advanced ceramic and metal-matrix composites, high-temperature superconducting materials, and nuclear reactor component mockups. The information supplied to industry is used to modify product design. This work is conducted by a research team of physicists, mechanical engineers, ceramists, and instrument scientists from three Argonne divisions using information from IPNS.

With neutron penetrations of up to many millimeters, neutron diffraction offers the unique capability of providing bulk measurements. If both macrostresses, from welding or surface finish, and microstresses (those on the scale of the microstructure) are present, the macrostresses are averaged out within the sampling volume, thus making the microstresses directly accessible. This is a significant advantage over x-ray diffraction, which measures only near-surface stresses that may include macrostresses.

The application of neutron diffraction to the determination of stress is a relatively new technique that has been validated at Argonne mainly for composites, but also for large components such as


turbine rotors, large bearings, and large welds. At present, through the user program, IPNS is available to any industry interested in determining residual as well as applied stress. The facility is also accessible to university users. Components can be studied at IPNS while undergoing changes in temperature, pressure, and atmosphere during measurement. Strain can be measured to a sensitivity of one part in 10,000.

This work was done by Dick Hitterman, Dave Kupperman, Saurin Majumdar, Jim Richardson, and J.P. Singh of Argonne National Laboratory. These researchers hold a patent on a neutron stress monitor for composites.

IPNS is a national user facility. Beam time can be obtained on one of the instruments by having a proposal approved by the oversight committee or by purchasing time from the IPNS division. If an experiment is assigned time on an instrument, Argonne staff will be available to assist a company's staff in completing the work.

Companies interested in working with this facility are encouraged to mail or FAX a letter to the Industrial Technology Development Center, ITD-900, 9700 S. Cass Ave., Argonne, IL 60439; FAX (708) 252-5230.

" Ω Improvement"



Introducing the world's best high resistance meter. The Keithley Model 6517.

It's your most accurate solution for high resistance measurements, with 0.01% accuracy Ω The quickest, measuring $10^{12}\Omega$ with 65ms settling time for up to 125 rdgs/s Ω The easiest to use Ω Built-in programs let you test components or materials and measure resistivity or insulation resistance Ω An internal source can sweep voltages up to 1kV Ω Plus, it records time stamp, temperature and relative humidity with every measurement Ω And, since it's also an electrometer, it can measure very low currents and small charges Ω

For a demonstration, call
1-800-552-1115 Ω For specifications by FAX,
call Spec Direct™ anytime at 1-800-936-3300 and
request document #1703 Ω

KEITHLEY

CCD Detects Two Images in Quick Succession


Readout is performed slowly to minimize noise.

NASA's Jet Propulsion Laboratory, Pasadena, California

A prototype special-purpose charge-coupled device (CCD) is designed to detect two $1,024 \times 1,024$ -pixel images in rapid succession (typically, separated by < 100 ns). When fully developed, this CCD would be operated in synchronism with a pulsed laser, stroboscope, or other pulsed source of light to form pairs of images of rapidly moving objects.

The basic design of this CCD is similar to that of a standard 3-phase, buried-channel CCD, except that within each pixel, an implant is added to each phase, and a light shield is added to phase 3 (see figure). A typical sequence of operations involves two flashes of light separated by the desired interval of the order of 100 ns. During the first flash, the first image is formed in phases 1 and 2 of the pixels (but not in phase 3 because of the light shields). During the interval of darkness between the first and second flashes, this first image is transferred to phase 3, where it is stored for subsequent readout.

The second image is formed in phases 1 and 2 during the second flash of light



This **Modified Three-Phase CCD** is operated in synchronism with two pulses of light to detect two images. The first image is formed in phases 1 and 2, then quickly transferred to phase 3. The second image is formed and stored in phases 1 and 2. Then the two images are read out in a slow scan.

and is then stored in phases 1 and 2 for subsequent readout. Thereafter, the first and second images are read out from the CCD by clocking phases 1, 2, and 3 of the pixels in the appropriate sequence. The readout time is chosen to be much longer than the interval between flashes (readout is performed in a slow scan) to

minimize readout noise. The design level of readout noise is about 3 electrons, root mean square, per pixel.

This work was done by James R. Janesick and Andy Collins of Caltech for NASA's Jet Propulsion Laboratory. For further information, **write in 93** on the TSP Request Card. NPO-19291

Electroabsorption in Doped Asymmetric Double Quantum Wells

The modulator uses real-space electron transfer to provide efficient absorption modulation.

Rome Laboratory, Photonics Center, Griffiss Air Force Base, New York

Electro-optic nonlinearities in semiconductor heterostructures have become an important means of transducing electronic data onto optical signals for communications systems. The most common nonlinearity employed to produce electroabsorption and electro-refraction in semiconductor quantum wells is the quantum confined Stark effect (QCSE). For materials systems such as (Ga,In)As/(Al,In)As quantum wells latticed-matched to InP, which are compatible with the optical fiber transmission windows of 1.3 and 1.5 μm , the QCSE is small, because of the relatively low electron and heavy-hole effective masses and the restriction on suitable well widths, i.e., 40 and 85 \AA respectively. Although recent results utilizing the (Ga,Al,In)As/(Al,In)As on InP system have demonstrated improved material quality and device performance at these wavelengths, improvements in the electro-optic characteristics of these materials is still required. One novel electroabsorption

mechanism is based on selective doping of (Ga,In)As/(Al,In)As asymmetric double quantum wells (ADQWs).

The team designed an ADQW structure in which an excess conduction-band electron density is intentionally formed by selectively doping the wide-well (WW) n-type as shown in Figure 1(a). The presence of excess electrons bleaches the absorption near the band-edge of the WW. The lowest energy transition in the WW is thus given by:

$$\hbar\omega = E_{\mu=0} + \mu_e(F) + E_{\parallel}^v$$

where $E_{\mu=0}$ is the lowest-energy WW transition in the absence of excess electrons, $\mu_e(F)$ is the field-dependent electron quasi-chemical potential with respect to the lowest allowed energy in the WW, and E_{\parallel}^v is the in-plane hole energy required for momentum conservation. Hence, the equation indicates that the WW absorp-




Figure 1. **Conduction and Valence Band** structures of the doped ADQW modulator in the (a) unbiased $F=0$ and (b) unbiased $F \neq 0$ states. The shaded regions represent states occupied by excess electrons.



INTERNAL MEMO

CONFIDENTIAL

TO: WB
FROM: Eve, Engineering
RE: Why isn't Marketing telling engineers MicroSim PSpice® A/D is the best analog & mixed simulator?

In our recent advertising, we seem to have focused exclusively on our new products, MicroSim PCBoards and MicroSim Schematics. Need we remind Marketing that Engineering and 22,000 customers think MicroSim has the best analog and mixed simulation software, bar none? Look at the facts!

- At over 10,000 models, we have thousands more models than competitors.
- MicroSim is the only company with native mixed analog/digital simulation for PCs. It's thousands of times faster and more accurate than all the competitors using generic macro models of digital parts. Our extensive libraries include both typical and worst-case timing!
- Users get 10 times the analysis information — and 10 times the value — from our graphical waveform analyzer. For example, it not only evaluates waveforms to extract percent overshoot, but it even plots the change in overshoot vs. component value. The critical design insight we provide yields fewer design iterations, shorter design cycles, and significantly better quality.
- With our MicroSim PSpice Optimizer, customers get higher yields and better performance (more speed, less power, less distortion, higher bandwidth, etc.)

And now with our new version 6.2, we really leave the competition in the dust. Plus don't forget we have the best technical support in the industry...and it's free.

Tell Marketing to wake up and smell the simulation!

*You've made
your point —
I'll make Marketing
feature PSpice in
the next ad. -WB*



Call 800-245-3044 for your free MicroSim PSpice evaluation software.

MicroSim is a trademark and PSpice is a registered trademark of MicroSim Corporation. Copyright © 1995 MicroSim Corporation. All rights reserved.

tion edge will be blue-shifted with respect to the absorption edge in the absence of excess electrons, i.e., $\mu_{e=0}$. An electric field applied perpendicular to the plane of the quantum wells will reduce the energy separation between the lowest electron levels in the wide and narrow wells as shown in Fig. 1(b). As a result, the excess electrons localized in the WW can tunnel to the narrow well (NW), a process known as real-space electron transfer. The transfer of the electrons reduces $\mu_{e=0}$, resulting in the recovery of the absorption near the WW band-edge and causing an apparent red-shift of the WW absorption edge.

The doped ADQW modulator structure was grown by molecular beam epitaxy on n-type (100) InP substrates. The electrical bias was applied via an *n-i-n* diode consisting of a 0.35- μm layer of n-type $\text{Ga}_{0.3}\text{Al}_{0.18}\text{In}_{0.52}\text{As}(\text{Si}, 2 \times 10^{18} \text{ cm}^{-3})$ followed by a 0.865- μm intrinsic region and capped with a 0.2- μm layer of n-type $\text{Ga}_{0.3}\text{Al}_{0.18}\text{In}_{0.52}\text{As}(\text{Si}, 2 \times 10^{18} \text{ cm}^{-3})$. The intrinsic region consisted of 30 periods of 100-angstrom $\text{Al}_{0.48}\text{In}_{0.52}\text{As}$ barrier/70-angstrom $\text{Ga}_{0.47}\text{In}_{0.53}\text{As}$ wide-well doped n-type over the central 40-angstrom $(\text{Si}, 1 \times 10^{12} \text{ cm}^{-2})$ /35-angstrom $\text{Al}_{0.48}\text{In}_{0.52}\text{As}$ tunnel barrier/50-angstrom $\text{Ga}_{0.47}\text{In}_{0.53}\text{As}$ narrow-well, all between two layers of 500-angstrom undoped $\text{Al}_{0.48}\text{In}_{0.52}\text{As}$. The diodes were processed into mesa diodes 150 μm in diameter with ring-top contacts to allow optical transmission experiments. The modulator sample was mounted in a closed-cycle helium cryostat and held at a temperature of 50 K.

The measured absorbance spectra at bias fields of 0 and 74 kV/cm, corresponding to applied voltages of 0 and 6.4 respectively, are shown in Fig. 2. The




Figure 2. Measured Absorbance Spectra of the doped modulator for applied fields of 0 and 74 kV/cm. The inset shows the measured absorption spectra of the undoped structure at the same applied fields.

peaks in the zero-field spectrum are the light- and heavy-hole excitonic absorption features associated with the lowest-energy transition in the NW. The excitonic features associated with the WW, however, are completely bleached by the presence of the excess electron density. In fact, due to band-filling in the first WW electron subband, the WW absorption is bleached to wavelengths approaching the NW band-edge. With the applied field present, the absorption associated with the WW recovers while the absorption associated with the NW becomes bleached. It should be stressed that the observed changes are not due to the QCSE. In undoped $(\text{Ga}, \text{In})\text{As}/(\text{Al}, \text{In})\text{As}$ -coupled quantum-well systems consisting of similar well widths, excitonic absorption features persist to much higher applied fields than those considered in this work. Hence, the observed absorption changes can only arise from the real-space transfer of electrons from the WW to the NW.

The characteristics of the doped modulator were compared to the electroabsorption characteristics of an undoped ADQW structure. The red-shift of the band-edge for the undoped sample is quadratic with increasing field, as expected from the QCSE (see inset of Fig. 2). However, the red-shift of the band-edge exhibited by the doped sample is much larger with increasing field and has an almost linear field dependence. In fact, for an applied field of approximately 50 kV/cm (corresponding to an applied voltage of only 4.3 V) the red-shift of the doped sample is more than six times larger than the red-shift of the undoped sample.

In this novel electroabsorption mechanism based on selective doping in ADQW structures, the modulator uses real-space electron transfer to provide efficient absorption modulation. The doped modulator exhibits a significantly larger red-shift with applied field than an undoped structure that uses the QCSE. Efforts are currently under way to optimize the coupled quantum-well design and diode structure for room-temperature operation.

This work was done by M.F. Krol of Rome Laboratory's Photonics Center, R.P. Leavitt and J.T. Pham of the US Army Research Laboratory, and B.P. McGinnis and N. Peyghambarian of the Optical Sciences Center, University of Arizona, Tucson, AZ. No further information is available.

Inquiries concerning the rights for the commercial use of this technology should be addressed to Rome Laboratory Office of the JA, Griffiss AFB, New York 13441.

Temperature-Compensated Sapphire Microwave Resonator

Ultrastable operation can be achieved at relatively low cost.

NASA's Jet Propulsion Laboratory, Pasadena, California

A sapphire-dielectric-ring microwave resonator that operates in a "whispering-gallery" electromagnetic mode features a differential-thermal-expansion design that provides temperature compensation for ultrahigh frequency stability. Heretofore, sapphire-ring resonators have been temperature-compensated by addition of paramagnetic impurities, but this approach has proven effective only at temperatures ≤ 6 K. The present resonator is a prototype of a type of sapphire resonator designed to minimize frequency fluctuations caused by temperature fluctuations at a nominal temperature equal to or even somewhat greater




Figure 1. The Thermal Expansion of the Copper Post causes the frequencies of the electromagnetic modes of the resonator to increase with temperature, while thermal effects in the sapphire cause the frequencies to decrease with temperature. These opposing effects can be utilized for temperature compensation.

than the temperature of liquid nitrogen (77 K). The ancillary equipment needed for operation in this higher temperature range is smaller and less expensive, and liquid nitrogen can be used as the coolant.

This resonator includes an upper and a lower sapphire ring separated by a small gap and spaced apart by a central copper post that is almost as tall as the rings are. The use of the small gap preserves the high Q (quality factor; a measure of the sharpness of resonance, defined as $2\pi \times$ the energy stored in the electromagnetic field in the resonator \div the energy dissipated per cycle of oscillation) of the whispering-gallery modes of interest while giving a steep variation of frequency with the size of the gap. The tall copper post gives a relatively large motion due to thermal expansion. The central position of the copper post minimizes its tendency to degrade Q because the electromagnetic energy of the modes of interest is concentrated near the radially outermost surfaces of the sapphire rings.

Compensation occurs as follows: As the temperature increases, the mode frequencies decrease because of concomitant thermal expansion of the sapphire and a concomitant increase in the relative permittivity of the sapphire. However, because the thermal expansion of the




Figure 2. **Complete Temperature Compensation** of a 7.23-GHz mode of this resonator can be achieved by operating at 87.09 K, where the slope of the frequency-vs.-temperature curve goes to zero.


copper post exceeds that of the sapphire, the gap widens. The resulting increase in the volume of the gap (relative permittivity of vacuum = 1, as compared with relative permittivity of sapphire ≈ 10) tends to increase the frequencies of the modes. At some temperatures, these opposing effects can cancel each other; in other words, result in complete temperature compensation.

Figure 2 shows the measured temperature dependence of frequency for a

mode with a nominal frequency of 7.23 GHz that is compensated at a temperature of 87.09 K. In this case, one could achieve a frequency stability characterized by a change in fractional frequency no greater than 10^{-14} during a typical observation interval 100 s long if one could maintain the temperature stable to within 43 μ K. This requirement can be satisfied by use of conventional temperature-regulation equipment developed for frequency-standard oscillators. The projected fractional frequency instability of 10^{-14} of this resonator is less than that of a typical highest-quality quartz resonator, which is about 2×10^{-13} .

This work was done by G. John Dick and David G. Santiago of Caltech for NASA's Jet Propulsion Laboratory. For further information, **write in 54** on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, NASA Resident Office-JPL [818-354-5179]. Refer to NPO-19414.



Reliability designed in means more switch operations over time and guaranteed, first-time, every-time actuation.

All DIP Switch products conform to MIL-83504, ISO-9001 and B8560 qualifications:

- Standard DIP Switches — spring and ball contact system provides three times the contact pressure, more reliability with shock and vibration immunity. Choose from SPST, SPDT and DPDT circuitry in Surface Mount, Machine Insertable, Piano, Rocker or Slide switches.
- Series 94 Rotary DIP Switches — more than 320,000 switching operations in octal, BCD, hexadecimal and equivalent complement code outputs with shaft lengths to 0.375" (9.525mm).
- Series 95 Tact Switches — both 11.5mm square and 6.9mm x 3.5mm designs offer positive tactile feel, perpendicular or right-angle actuation.

More Than 350,000,000 Sold

For more information contact us:

Phone: 708/354-1040

Fax: 708/354-2820

Internet: <http://www.grayhill.com>

Grayhill

An ISO-9001 Company

561 Hillgrove Avenue

P.O. Box 10373

LaGrange, Illinois 60525-0373 USA

Using a Sealed Tube Neutron Generator for Fossil Fuel Exploration

A modified unit is designed to help find oil.

Nevada Test Site, Special Technologies Laboratory, Dept. of Energy, Las Vegas, Nevada

In the oil exploration industry, the standard method of performing downhole measurements involves inserting a small neutron generator into a mud-filled hole. The surrounding earth is then probed by a 14-MeV pulsed neutron source, and the ensuing gamma-ray spectra are observed as a function of time. Though the objective is to obtain data about the local geologic properties, the signals are superimposed on high background noise because of counts originating from the measurement apparatus itself. Obviously, it would be helpful to know the origin of each gamma ray and to be able to accept or reject the count accordingly. (At present, this background is estimated using the Monte Carlo analysis method, and subtracted from the data.)

DOE's Nevada Test Site (now Bechtel Nevada) scientists, working for EG&G Energy Measurements' Special Technologies Laboratory in California, modified a version of the sealed tube neutron generator to perform this function. Using such a tube with associated particle imaging methodology, one can determine the positional origin and the energy of each contributing gamma ray. Using the associated particle imaging technique may provide an advantage when performing downhole measurements to identify underground oil formations. Along with the background noise prob-


lem, the current technology lacks directional resolution.

In addition to alleviating the problems arising from a high and unidentified background, knowing the origin of each observed gamma ray would be instrumental in addressing other issues involving more detailed information about the surrounding geological strata. For instance, detection of an underground "pool" of oil sandwiched between two strata would suggest using a horizontally drilled section to facilitate more efficient pumping. The angle of stratified layers is another currently nondiscernable

parameter that would optimize pumping efficiency.

Because drilling an oil well is still very expensive and risky, any technology that significantly increases the chances of success is particularly valuable. Scientists have made initial contacts with an industrial partner to test this technology in the field.

This work was done at the Dept. of Energy's **Nevada Test Site**. For more information, contact Dr. Bruce Whitcomb, Principal Scientist, Office of Research and Technology Applications, Bechtel Nevada, PO Box 98521, M/S NLV006, Las Vegas, NV 89193-8521; (702) 295-3164.



Schematic of Associated Particle Imaging.

CVD of Thin Films From Single Organometallic Precursors

These films are superior to films deposited from multiple precursors.

Lewis Research Center, Cleveland, Ohio

A method of forming thin inorganic films involves chemical vapor deposition (CVD) from single organometallic precursors. The method is especially suitable for depositing high-quality passivating or buffer layers of GaS on GaAs semiconductor substrates. The method is also applicable to formation of high-quality films for purposes other than buffering or passivation, and to different materials in which another element from the same group in the periodic table of elements is substituted for all or a portion of each

element in the GaS/GaAs system.

Previous methods of forming passivating or buffer layers on GaAs involved multiple chemical precursors. These methods resulted, variously, in layers that contained impurities, were of uneven composition, were unstable, were toxic, and/or had to be deposited at temperatures so high that substrates became degraded. In contrast, the present method involves no toxic constituents, minimizes impurities, and yields films that have substantially uniform crystal structure and composition.

The apparatus used in this method (see figure) includes a flow-through reactor housing connected via valves to (1) a vacuum pump, (2) a source of carrier gas (typically, argon, hydrogen, or nitrogen), and (3) an optional source of oxygen or a gas that can be decomposed to release oxygen (e.g., N_2O). The precursor material is placed in a holder in the chamber upstream from the substrate.


A heater plate outside the chamber near the precursor heats the precursor, through the wall of the reactor housing, to a tem-

perature high enough to vaporize a sufficient quantity of the precursor; typically, this temperature is between 100 and 250 °C. A flow of carrier gas entrains the precursor and carries it toward the substrate. Another heater plate outside the reactor housing heats the substrate to a temperature at which the precursor is pyrolyzed; typically, this temperature is between 250 and 550 °C.

Upon arrival in the vicinity of the substrate, the precursor molecules are pyrolyzed by heat radiated from the substrate. The nonvolatile product (e.g., GaS) of the decomposition of the precursor molecules is deposited on the substrate, forming the film. The heaters and the flow of gas are turned off to stop the deposition when the deposit attains the desired thickness (typically between 2,000 and 5,000 Å).

The precursor can be any of a number of organometallic compounds that contain butyl groups and the elements to be deposited. The composition and molecular structure of the deposited film depends on the precursor. For example, a precursor of $[(Bu)_2Ga(S^iBu)]_2$ (where "Bu" denotes tertiary butyl) yields a film of amorphous GaAs.

An important class of examples is that of precursors that have cubane molecu-



The **Organometallic Precursor Material** is vaporized, carried to the substrate, and pyrolyzed to form a deposit on the substrate.

lar structures or that acquire cubane molecular structures during vaporization or pyrolysis. These precursors yield films that have cubic or cubiclike crystalline structures, which are often desired because they can be lattice-matched with substrates of similar crystalline structure. For example, the cubane-structured precursor $[(Bu)_2GaS]_4$ forms a cubic-phase GaS passivating film that is lattice-matched to a GaAs substrate.

The optional source of oxygen is for use in forming an insulating oxide layer on the outer surface of the passivating film. When

the film has been deposited to the desired thickness, the valve from the source of oxygen is opened; exposure to the flowing oxygen or oxygen-containing gas results in formation of the oxide surface layer.

*This work was done by Aloysius F. Hepp of **Lewis Research Center**; Andrew R. Barron of Harvard University; Michael B. Power and Andrew N. MacInnes of Gallia, Inc.; and Phillip P. Jenkins of Sverdrup Technology, Inc. For further information, write in 58 on the TSP Request Card.*
LEW-15636

Optical Encoders...available now from Grayhill

Grayhill's Series 61 Optical Encoder delivers the reliability your application needs...when your production schedule demands it!

Now you can have Grayhill reliability in an optical encoder switch.

Use it as a mouse...a tuning function...a frequency selector...or to measure low RPM...whatever your design requires.

The Grayhill Series 61 Panel-Mount Optical Encoder delivers over 1 million cycles of operation. And we can deliver them now, not later, at competitive prices.

The Series 61 offers:

- Standard resolution—16, 24 and 32 positions.
- High resolution—25, 32, 50, 64, 100 and 128 pulses per channel per revolution.
- Lower power consumption with single 5Vdc power supply.
- Choice of integral data input pushbutton.
- Custom design capabilities. Options include operating torque, terminations, pushbutton operating force.
- Design and production compliance to ISO-9001.

For more information, call 708-354-1040 and request Bulletin #646. Or dial the DataXpress number for immediate product data.



Grayhill
INC.
An ISO-9001 Company

561 Hillgrove Avenue
P.O. Box 10373
LaGrange, IL 60525
Phone: 708/354-1040
Fax: 708/354-2820

DATAEXPRESS 1-800-244-0559

Tecplot

Interactive Data
Visualization for
Scientists & Engineers

The Package Chosen by Thousands


Tecplot is the versatile and powerful, interactive software package that thousands of engineers and scientists have chosen for visualizing their technical data. With Tecplot you can easily create XY plots, contour plots, vector plots, mesh plots, carpet plots, 3D stream ribbons, isosurfaces, light-source-shaded surfaces, and many other plots. You can visualize complex data defined in one, two, or even three dimensions. You can even visualize data on its original non-rectangular grid (e.g., multi-block curvilinear, triangular, quadrilateral, 8-node bricks, and tetrahedral), preserving its original variation of grid resolution and retaining exact grid boundaries. Tecplot was elected "Best Data Visualization Software" of 1994 by the readers of Scientific Computing and Automation Magazine.

The Total Data Visualization Solution

Tecplot tightly integrates basic plotting and graphing with advanced scientific visualization techniques in one versatile package, making Tecplot the comprehensive solution to all your data visualization needs. Tecplot is easy to use, yet has the power, capacity, and flexibility to please even the most demanding research scientist. Tecplot's versatility and cross-platform support makes it ideal for a wide range of scientific and engineering applications. When considering a company-wide data visualization solution, think Tecplot.

Explore, Analyze, and Understand Your Data

Are you spending too much time programming or getting frustrated trying to do scientific visualization with regular plotting programs? Use Tecplot to focus on your real work and begin producing results from the moment you read in your data. Tecplot enables you to interactively explore and analyze your data to gain new understanding and insights. With Tecplot, you can create beautiful, publication-quality plots in minutes.



Courtesy of M. Connelly, Bechtel-Hanford, Inc., Hanford, Washington.

Available for
Unix, Linux, VMS
Workstations and PC's.

What Our Users Are Saying

"Tecplot is the best engineering and scientific plotting package. I wish I could have used it when I was doing my Ph.D."

-H. Chen, Adv. Laser and Fusion Tech., Quebec

"The best scientific plotting package around! Best technical support, too! I love it and have told everyone about it!"

-R. Ott, SWL, Inc., NM



"The quality and flexibility of the plots produced by our research group has significantly improved since we started using Tecplot."

-M. Overholt, Cornell University, NY


"Very easy to learn and use, but still extremely powerful."

-G. Land, Ingersoll-Rand Co., VA

Courtesy of R. D. Henderson and G. E. Karamadakis, Dept. of Mech. & Aero. Engineering, Princeton University. Near-wake streamwise velocity field with massless particles show results of new unstructured spectral element method.



Courtesy of M. Connelly, Bechtel-Hanford, Inc., Hanford, Washington.



Courtesy of Bruce Rosen, South Bay Simulations, Inc., Babylon, N.Y. Computed results by SPLASH free-surface flow code.

For More Information

To receive more information about Tecplot and how it may benefit you, please contact us.

Phone: 1-800-676-7568 or 206-827-3304

Fax: 206-827-3989

E-Mail: tecplot@amtec.com

Web Site: <http://www.amtec.com>

For More Information Write In No. 474

Amtec Engineering, Inc.

P.O. Box 3633

Bellevue, WA 98009-3633



Educational Discounts Available!

Transportable Molecular-Beam Mass Spectrometer

A powerful, versatile tool saves time and energy.

National Renewable Energy Laboratory (NREL), Golden, Colorado

Researchers at NREL are producing a transportable molecular beam mass spectrometer (TMBMS). This prototype, similar in performance and cost to a full-sized molecular beam mass spectrometer (MBMS), is one-fifth the size and requires only an electrical connection. Power consumption is cut in half. Most of the equipment fits on a rolling cart 1 m X 1.6 m (39 in. X 63 in.), so it can be readily transported by truck and set up at a new location.

NREL scientists developed the TMBMS because molecular beam mass spectrometry is an integral part of their development of several highly promising thermochemical conversion technologies. Other recent uses include continuous emission monitoring and solar detoxification research. Future continuous emission monitoring applications might include industrial stacks and hazardous waste incineration.

This new mobile version of the MBMS has tremendous potential. Conventionally, many research projects or commercial processes must rely on batch sampling, in which analysis is done after the fact and there is risk of altering samples in the process of collecting them, or settling for monitoring only certain compounds. The TMBMS can identify many chemical compounds at the same time, and can also handle high temperature, high pressure, moist or particulate-laden emissions, or product streams.


Another key advantage of molecular beam mass spectrometry is that it detects the chemical effects of short-duration events, such as the rapid acceleration of an engine or a momentary upset in the feed rate of a chemical process. It can also identify transitory compounds before they change to the final product.

The TMBMS measures the mass of individual molecules in a gas stream. To do this, it continuously extracts gases and vapors through a small nozzle, which then undergo free-jet expansion into the first of three vacuum chambers. A second nozzle extracts the core of the expanded sample, creating the molecular beam in the second vacuum chamber. Finally, the molecules are ionized in the third vacuum chamber, which contains one of two types of mass spectrometer.

One type, the time-of-flight spectrometer, functions by pulsing the ions into a tube and measuring how long it takes them to reach the detector. The other type, the quadrupole spectrometer, uses electronically controlled radio frequency and electrical fields that filter ions, one mass at a time, into the detector.

NREL scientists are continuing to improve and test the TMBMS with an eye toward working with an instrument manufacturer for commercial production. They also continue to find new uses for it. In the meantime, NREL will make the two prototypes available to other researchers under cooperative agreements. Molecular beam mass spectrometry is a powerful analytical tool that creates new opportunities for research in gas-phase chemical processes and emissions monitoring. By making the tool into a transportable device, NREL offers a wide range of researchers a valuable resource.

Matt Ratliff, Dave Gratson, Tom Milne, and the Industrial Technologies Division of the National Renewable Energy Laboratory are responsible for creating the TMBMS. Inquiries concerning the patent status and availability of rights and licenses should be directed to NREL's Technology Transfer Office; (303) 275-3008.



Schematic of the Transportable Molecular Beam Mass Spectrometer system. In stage 1, the pressure of the sample vapor stream drops dramatically, causing it to undergo free-jet expansion and adiabatic cooling. In stage 2, the core of the expanded sample is collimated by an orifice of 1.0-1.2 mm to form the molecular beam. In the mass spectrometer (here a quadrupole), the molecules of the beam are ionized and mass-analyzed.

LITERATURE SPOTLIGHT

Free catalogs and literature for *Federal Lab Tech Briefs* readers. To order, write in the corresponding number on the Reader Information Request Form (preceding page 81).



TOOLS, TOOL KITS, CASES AND TEST EQUIPMENT

Installation/repair tools, tool kits, test equipment, telecom equipment, LAN testers & instrument/shipping cases are detailed in this 300+ page full-color catalog. Includes

products for field service & depot repair. Indexed catalog features over 100 standard tool kits & complete information on "customizing" to meet specific customer requirements. Complete specs & prices are provided for all products. Tel: 800-866-5353; Fax: 800-234-8286.

Specialized Products Co.

For More Information Write In No. 380



SERIAL DATA DIRECT INTO SOFTWARE

The SoftwareWedge™ enables users to direct serial data from any instrument or device directly into Excel, Quattro, VB, statistical and industrial software—any

Windows, DOS, NT, or Win 95 application. Data from process control and laboratory instruments, gages, sensors, PLCs, analyzers, bar code readers, electronic balances, and telephone systems—any serial device—can be collected easily and accurately. TAL Technologies, Inc., 2027 Wallace St., Philadelphia, PA 19130; Tel: 215-763-7900 or 800-722-6004; Fax: 215-763-9711; E-mail: tal1@taltech.com; http://www.taltech.com.

TAL Technologies, Inc.

For More Information Write In No. 381



ILLINOIS CAPACITOR ANNOUNCES 1996 CATALOG

Illinois Capacitor's 208-page Catalog and Engineering Guide contains complete information on the company's aluminum electrolytic, film, ceramic, and power capacitors. It's all you need to make a knowledgeable capacitor selection. Available capacitance range, voltage ranges, operating temperature, case styles, IC-authorized distributor listings. Illinois Capacitor, Inc., 3757 W. Touhy Ave., Lincolnwood, IL 60645; Tel: 708-675-1760; Fax: 708-673-2850.

Illinois Capacitor, Inc.

For More Information Write In No. 382

LOW COST PCB PROTOTYPE SYSTEM



The LPKF Protomat 91S System provides faster turnaround and better throughput of circuit board prototypes than other methods. There is NO better value in prototype PCB fabrication systems—here's why:

- Takes your Gerber or HPGL files and produces Analog, Digital, RF or Microwave circuit board prototypes.
- Windows software with programmable insulation width, multiple tool rub out, and full tool management.
- Small footprint from a fully integrated system package.
- Environmentally safe all mechanical process.
- Fast payback - typically 3-12 mos.
- Full 1 year warranty.

**ASK ABOUT OUR AUTOMATED
THRU-HOLE PROCESS**

CALL TODAY 1-800-345-5753

FAX: (503) 643-3662

**LPKF CAD/CAM
SYSTEMS INC.**

6190 S.W. Arctic Drive Beaverton, Or. 97005

For More Information Write In No. 480

Still strain-gauging your parts?



**Next time measure your stresses
nondestructively. Because if it's not
broken, why break it.**

TEC PRODUCTS and LAB SERVICES
10737 Lexington Drive, Knoxville, TN 37932

423-966-5856 fax: 423-675-1241

For More Information Write In No. 471

Ferroelectric Phase Shifters for Electronic Scanning

These devices could yield low-cost scanning antennas for commercial applications.

Physical Sciences Directorate, Army Research Laboratory, Fort Monmouth, New Jersey

Electronic scanning antennas are functionally important in future commercial and military communications and radar systems. Most current radar scanning is mechanical, relying on a gimbal arrangement to physically rotate/elevate a radar antenna. Gimballed scanning is slow, gravity-sensitive, and susceptible to mechanical failure. Electronic scanning is preferable because it is rapid and inertialess.

At present several technologies for phase shifting in electronic scanning are available against which the ferroelectric kind must compete. Among them are phase shifters using semiconductor devices and those using ferrite material. Semiconductor devices have an advantage in their small size, but are limited to small-signal applications, since high-power semiconductors have degraded microwave characteristics. Currently, most electronic scanning antennas are controlled by ferrite (magnetic) phase shifters. These are low-loss, and though they perform well, their size and cost limit the number of electronic scanning antennas in use today.

Ferroelectric phase shifters are significantly lower in cost and smaller in size than the ferrite kind. The former are compatible with planar technology, and those being developed at ARL will have *in situ* calibration to stabilize them against environmental change. Planar ferroelectric phase shifters are designed to operate as electrical delay lines, creating phase shift through changes in the velocity of the microwave signal.


The planar ferroelectric phase shifter developed at ARL consists of a DC voltage block, matching transition, and metallized section of ferroelectric material ($\text{Ba}_{1-x}\text{Sr}_x\text{TiO}_3$). The DC block and transition are part of the planar conducting circuit. More recently, techniques have been developed at ARL to produce multiple phase shifters on a single piece of ferroelectric material. This development will further reduce the size and cost of ferroelectric phase shifters, creating the potential for low-cost electronic scanning antennas for commercial applications.

Methods are being developed for real-time calibration of phase shifters, thus permitting dynamic compensation of phase due to aging or environmental stress. This is compatible with the future need for self-diagnosing systems.

These phase shifters are characterized by a 360° phase shift at 4 GHz, an insertion loss of 2.5 dB, and measurements of $5 \times 1 \times 0.3$ mm.

The performance characteristics of ferroelectric phase shifters are compatible with the industry state of the art. They will significantly reduce the size and cost of electronic scanning phased array radars.

This work was done at the Army Research Laboratory, Ft. Monmouth, NJ 07703-5601. For further information, contact Richard Babbitt or William Drach, ARL; (908) 427-2284.



Schematic showing details of Ferroelectric Phase Shifter.

DESIGN ENGINEERING PRODUCT SHOWCASE

New Products and Services for NASA Tech Briefs readers. For more information, write in the corresponding number on the Reader Action Request Form (preceding page 81).



OMEGA UNIVERSAL GUIDE TO DATA ACQUISITION & COMPUTER INTERFACES™

OMEGA Engineering Inc. is pleased to announce the release of its latest publication, OMEGA Universal Guide to Data Acquisition and Computer Interfaces, Fall 1995/Winter 1996 edition. Products that can be found in the book include: alarm monitors, auto-dialers, communication adapters and converters, dataloggers, parallel interfaces, PLCs, plug-in boards, serial interfaces, signal conditioners, and software.

OMEGA Engineering Inc.

For More Information Write In No. 300

HIGH-SPEED ISOLATED TEMPERATURE/VOLTAGE INTERFACE




The OMB-MULTISCAN-1200 features channel-to-channel isolation for temperature and voltage measurements. Its high-speed scan rate allows the operator to scan temperature and voltage inputs at a rate of 147 channels per second. System expansion up to 744 channels is available through low-cost expansion chassis.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 303



DAS-1800 PLUG-IN BOARDS FOR IBM-COMPATIBLE COMPUTERS

The DAS-1800 Series plug-in boards feature continuous, high-speed, gap-free data acquisition under Windows or DOS. An on-board FIFO buffer and dual-channel DMA allow the acquisition of large amounts of data without losing data. The DAS-1800HC models feature 64 single-ended inputs of 32 differential inputs at up to 333 ksamples/sec. The DAS-1800ST has maximum acquisition at different gains, pre-post and about triggering, two analog outputs and digital I/O.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 306



COLLECT FOR WINDOWS DATA COLLECTION THROUGH RS-232

Collect for Windows allows you to collect data from virtually any RS-232 instrument, and put it directly into programs such as Excel, Lotus 1-2-3, Quattro Pro and others. Multiple applications may be open and receiving data simultaneously from different instruments. As data is received in your application, calculations can be performed instantly and the results displayed. For more information on this new product, contact OMEGA, or use our OMEGAfax™ service to request Document #6335 by calling 1-800-848-4271 from any Touch-Tone phone.

OMEGA Engineering Inc.

For More Information Write In No. 301



HIGH-RESOLUTION PLUG-IN BOARD FOR IBM PCs AND COMPATIBLES

The new WB-ASC16 Series boards from OMEGA provide eight channels of 16-bit analog input for a wide variety of input types. Three models are available in this series. The WB-ASC16-TC accepts thermocouple, millivolt and voltage signals directly. The WB-ASC16-GP accepts both millivolt and voltage inputs. The WB-ASC16-RTD accepts RTD temperature sensors directly. All boards also include eight channels of digital I/O individually programmable as input or output.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 304

VOLTAGE INPUT BOARD OFFERS PLUG-IN SOLUTION



The new model DAS-TC is an easy-to-use, highly accurate IBM PC and compatible plug-in solution for measuring thermocouple and voltage inputs. Up to 16 differential inputs are provided as well as one cold junction compensation (CJC) sensor input. Automatic calibration, gain selection, CJC thermocouple linearization conversion to degrees or volts and averaging are performed by an on-board microprocessor. To connect signals to DAS-TC, accessories provide screw terminal connections for all I/O lines.

OMEGA Engineering Inc.

For More Information Write In No. 307



SINGLE-CHANNEL ASYNCHRONOUS SERIAL INTERFACE

OMEGA introduces the OMG-ULTRA-485 single-channel RS422/485 asynchronous serial interface. The OMG-ULTRA-485 is an ideal interface for factory automation equipment and PLC communication. The ULTRA-485 is perceived by the system to be an RS-232 port, so no special software drivers are required. Maximum data communication distance between PCs is 5000 ft., coupled with data rates up to 115K BPS.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 302



LIGHTNING/SURGE PROTECTORS GUARD AGAINST HIGH-VOLTAGE TRANSIENTS

The new CAT-22 Series lightning/surge protectors are designed to accommodate high voltage transients caused by lightning or other electrical disturbances that can easily destroy semiconductor junctions. The CAT-22 Series redirects these transients to earth ground. The protection circuits incorporate multiple separate stages of limiting high voltage transients: gas tubes, avalanche diodes, and MOV thyristors.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 305



HIGH-SPEED DATA ACQUISITION FOR NOTEBOOK/DESKTOP PCS

The OMB-DAQBOOK-100 plug attaches directly to the parallel port on the PC. It can transfer data bi-directionally at up to 170 Kb/sec. The unit provides the following features: 16 analog inputs, expandable to 256; 2 analog outputs; 24 general-purpose I/O channels, expandable to 192; 16 high-speed digital inputs; and 5 frequency/pulse I/O channels.

OMEGA Engineering Inc.

<http://www.omega.com>

For More Information Write In No. 308



FREE CATALOG "OPTICS FOR INDUSTRY"

Free 130 page catalog from Rolyn, world's largest supplier of "Off-the-Shelf" optics. 24-hour delivery of simple or compound lenses, filters, prisms, mirrors, beamsplitters, reticles, objectives, eyepieces, plus thousands of other stock items. At off-the-shelf prices. Rolyn also supplies custom products and coatings in prototype or production quantities.

Rolyn Optics

706 Arrow Grand Circle, Covina, CA 91722-2199
Tel: 818-915-5707; Fax: 818-915-1379.

For More Information Write In No. 310



WORLD OF CLAMPING

The World of Clamping Catalog 5/95 describes and illustrates toggle and special clamps with vertical and horizontal hold-down, straight-line, latch, and squeeze action. Spacing products, hydraulic devices, and CAD databases are covered, along with applications. De-Sta-Co, Box 2800, Troy, MI 48007; Tel: 800-245-2759.

De-Sta-Co

For More Information Write In No. 311



New small, lightweight quick disconnect rotary switches from Janco are tough enough for environmentally demanding conditions. The AD/BD

series features a specially designed container and quick disconnect package that facilitates fast, simple, switch installation and removal. Send for the AD/BD Innovator Literature for available switch options for reducing assembly and maintenance turnaround time. Janco Corporation, 3111 Winona Ave., Burbank, CA 91504; Tel: 818-846-1800; Fax: 818-842-3396.

Janco Corporation

For More Information Write In No. 312



CONSTANT FORCE SPRINGS & REELS

Colorful, 12-page brochure provides details on a line of stock and custom designed spring-powered devices for the OEM design engineer. Includes power springs, NEG'ATOR® constant force extension springs, constant force spring motors, prestressed spiral springs, stock spring-powered reels, motor assemblies, RW® laminar springs. Contains typical applications and selection guide. Ametek, U.S. Gauge Div., Sellersville, PA 18960; Tel: 215-257-6531; Fax: 215-257-3058.

Ametek, U.S. Gauge Division

For More Information Write In No. 313




RUGGED MINIATURE SWITCH

The Series 70 is an environmentally rugged line of lighted and unlighted switches. Wet, dusty or oily duty. DPDT MOM or ALT switch actions. Mounts on 0.700" centers with 0.880" depth. Lighted pushbuttons use T-1 MFB lamps. Variety of display types, colors, and styles. StacoSwitch, 1139 Baker St., Costa Mesa, CA 92627; Tel: 714-549-3041; Fax: 714-549-0930.

StacoSwitch

For More Information Write In No. 314



LIGHTED SWITCH CONTROLLER

The Interface Controller, IFC, provides flexible, low-cost digital I/O. Up to 16 inputs and 64 outputs @ 250 milliamps and 50 VDC. Serial communication to the host processor via RS-232 or RS-422/485 ports. Simple software driver set. Small size, easy direct mount or DIN Rail mount. StacoSwitch, 1139 Baker St., Costa Mesa, CA 92627; Tel: 714-549-3041; Fax: 714-549-0930.

StacoSwitch

For More Information Write In No. 315



ELECTRO-MAG- NETIC DESIGN SOFTWARE

The legendary Vector Fields suite of software, including the TOSCA, ELEKTRA and OPERA packages, combines classical finite element techniques with user friendly interactive graphics for high accuracy 2D and 3D simulation and design of all types of electromagnetic equipment.

Vector Fields Inc.

1700 North Farnsworth Avenue
Aurora, IL 60505

Tel: 708-851-1734 Fax: 708-851-2106

For More Information Write In No. 316



MECHANICAL COMPONENTS

PIC Design's new Catalog 43 is bigger than ever—288 pages, including new Modular Framing Elements, Linear Motion Systems & Positioning Tables, and expanded lines of Lead Screws & Nuts, Belts & Pulleys, Ball Slides, Shoulder Screws, Bearings, Shafting, Couplings and much more, all in inch and metric dimensions. PO Box 1004, Middlebury, CT 06762. Tel: 800-243-6125; Fax: 203-758-8271; E-mail: info@picdesign.com.

PIC Design

For More Information Write In No. 317



FIBERGLASS LAMINATED EPOXY 155 °C

Design Data pamphlet features materials, properties, and tolerances for glass epoxy components. It shows designers how to specify from open stock tools, for potting forms, bobbins, coil forms, structural, and circuit board manufacturing aids. Stevens Products, Inc., 128 N. Park St., E. Orange, NJ 07019. Tel: 201-672-2140.

Stevens Products, Inc.

For More Information Write In No. 318




ALGOR PROVIDES "4- WAY" INFO ON THE WORLD WIDE WEB

Algor's Internet place has detailed information on four product lines. Discover Houdini, Algor's automatic CAD solid model to 8-node "brick" mesh converter. Learn about Algor FEA, including case histories. Preview engineering videos, books and multimedia. See all new integrated piping/vessel/plant design software. If you do not have Internet access, call for free info. Algor, Inc.; E-mail: info@algor.com; URL: http://www.algor.com; Tel: 412-967-2700; Fax: 412-967-2781.

Algor, Inc.

For More Information Write In No. 319



BOOK WITH DISK DELIVERS REAL- WORLD FEA INSTRUCTION

A comprehensive FEA reference/textbook that offers a unique blend of theory & real-world engineering examples. Dr. Constantine Spyarakos, well-known finite element stress & vibration analysis expert, has created a reference for all mechanical engineers from designers to "gurus." Richly illustrated hardcover book includes every example problem on a disk. Subjects include: FEA basics, element types, modeling, types of analysis & the interpretation of results. Tel: 1-800-482-5467; URL: http://www.algor.com/apd.htm; E-mail: apd@algor.com.

APD

For More Information Write In No. 320



NEW KIND OF MULTIMEDIA VIDEO TEACHES FEA LESSONS

Finite Element Analysis in Action! is a new kind of instructional video for engineers. Available on VHS tape or interactive, multimedia CD-ROM, the video packs a lot of information into a short running time of only 26 minutes. Live lab experiments and FEA analysis are conducted to show how to better use any FEA software. Demonstrates specific modeling and analysis techniques. Tel: 1-800-482-5467; URL: http://www.algor.com/apd.htm; E-mail: apd@algor.com.

APD

For More Information Write In No. 321

NEW PRODUCTS

New High-Speed A/D Converter Family

Micro Networks, Worcester, MA, announces a new family of high-speed analog-to-digital (A/D) converters with a wide range of commercial and military applications. Two of the three models, the MN5930 and MN6250, have a sampling rate of 30 MHz; rate for the MN5925 is 20 MHz. The MN5925 and MN5930, monolithic devices packaged in a plastic DIP configuration, operate over the 0-70 °C temperature range; the MN6250, a mixed-signal multichip circuit, has a T/H amplifier, reference, and timing circuitry in a single 32-pin ceramic clip package.

For More Information Write In No. 775



Integral EMI Filter in DC/DC Converter

The high-density ADDC02805S 28-V-to-5-V (20 A) DC-to-DC converter from Analog Devices, Norwood, MA, has on-board EMI filtering, input transient protection, and system-level functions to simplify complex power-supply systems. The 2.5" x 1.5" hybrid devices guarantee up to 100 W of continuous output power over a wide range of input conditions (16-50 V DC). Temperature operating range, factory testing, and price vary for three versions: industrial grade, ruggedized industrial grade, and MIL-STD-883D tested.

For More Information Write In No. 776




Embedded ATA Data Storage System

SanDisk Corp., Santa Clara, CA, introduces the Flash Chipset, which it calls the

world's smallest embedded solid-state ATA data storage system. The device provides product developers with very low-power, high-capacity storage for integration into lightweight mobile electronics. It is available in 2, 4, and 10-MB capacities, and with full ATA/IDE disk drive compatibility can be designed into many platforms and operating systems.

For More Information Write In No. 777



Real-Time Data Acquisition and Control

New from Microstar Laboratories, Bellevue, WA, is the DAPL 2000, a 32-bit operating system for real-time data acquisition and control. Time quantum for task switching can be set in 1-μs increments from 200 μs to 5 ms. Standard DAPL commands include FFT, FFT32, FIRFILTER, and FIRLOW-PASS, and custom DSP commands can be easily implemented in C.

For More Information Write In No. 778

VME Waveform Capture Board

The VDA500 waveform capture board from Signatec, Corona, CA, has an analog bandwidth of DC-500 MHz, an 8-bit 500-MHz digitizer, 256 kilobytes of on-board memory, and a data transfer rate of 200 MB/s. Memory is expandable to 1 gigabyte or more with external memory modules. The VDA500 has two input channels and a multiplexer to select one of the two as the digitizing source. On-board crystal clock circuitry makes possible selecting 1 of 28 digitizing frequencies between 312.5 kHz-500 MHz.

For More Information Write In No. 779



Floating-Point Digital Signal Processor

Signalogic, Dallas, TX, offers the Sig32C-8^x 32-bit floating-point digital signal processor with up to 640k x-32 SRAM, and eight channels of analog I/O on a 7.5-in. PC plug-in board. Each channel has 16-bit analog-to-digital and digital-to-analog converters and programmable input gain, output attenuation, and sampling rate. Sigma-delta technology gives the channels anti-aliasing and reconstruction filters for high out-of-band rejection and linear phase.


For More Information Write In No. 780



Boards for Processing Large Data Banks

The CV 6 range of digital signal processor boards from Spectrum Signal Processing Inc., Burnaby, B.C., Canada, provide an easily configurable range of VME platforms for applications requiring precision analysis of large amounts of data. Radar and sonar applications will exploit the high-speed CV6 VME64 interface by transferring large data blocks to the 64-MB shared DRAM, while imaging applications benefit from the broadcast write feature. The CV6 board is available with six memory options.


For More Information Write In No. 781



Graphics Board Drives 8-bit or 24-bit Displays

Peritek Corp., Oakland, CA, makes available the VCL-V, a highly integrated VMEbus "intelligent graphics generator." Features include high-resolution digital flat panels: up to 1280 x 1024 can be driven with 4096 colors, and 640 x 480 panels with 262k to 16M colors. With a programmable PLL pixel clock generator, the unit can generate many varieties of video sync, allowing connection to most current and older analog and digital displays.

For More Information Write In No. 782



\$450

Three quadrature encoder inputs (TTL or RS-422)

Four 12-bit D/A outputs

Eight 12-bit differential A/D inputs, 50 kHz rate

Watchdog timer may be connected to PC bus reset

48 bidirectional digital I/O for solid state relay boards

Call (503) 684-8005
Fax (503) 684-8164

SENSORAY

For More Information Write In No. 460

ALLIEDSIGNAL Instrument Systems



Exceptional reliability can be found in our precision, snap-acting bimetal thermostats. Meeting the qualifications of M24236/1 and NASA GSFC S-311-641, our high-reliability thermostats can be found on most satellite and spacecraft applications. We can design custom thermal switch configurations to meet the toughest operating conditions. From aerospace to locomotives, from the NASA Space Transportation System to machinery, our thermostats provide low-cost, reliable thermal protection for many years.


AlliedSignal Instrument Systems
PO Box 97001
Redmond, Washington 98073-9701
206-885-8010 206-883-2104 Fax

For More Information Write In No. 461

SANYO Solar Cells

Sanyo is the largest manufacturer of amorphous solar cells in the world. Standard product line includes: 14 indoor models (1.35 to 3.0V @ 8 to 42 μ A), 32 outdoor models (1 to 15V @ 35 to 350mA), thin-film bendable, flexible, see-through power modules, and photosensors. Custom designs for power increase or shape available. SANYO Energy (U.S.A.) Corporation, 2001 Sanyo Ave., San Diego, CA 92173; Tel: 619-661-6620; Fax: 619-661-6743.

SANYO Energy (U.S.A.) Corporation



For More Information Write In No. 469

RevPoint 3D System




AFFORDABLE 3D INPUT

The RevPoint 3D System is a complete package that provides real-time 3D input with all the software you'll need for Reverse Engineering, Rapid Prototyping, 3D Modeling, or Design. As simply as you would use a tablet stylus, place the 3D probe on the surface of an existing part, and you are now working in 3D. Fully interactive, the RevPro digitizer always updates your position on the screen in real time. The RevPoint 3D system also exports your work as DXF, DWG, IGES, IBL, STL, CADL, or ASCII formats. SoftWorld International, 133 Admiral St., Bridgeport, CT 06601; Tel: 203-367-7789; Fax: 203-367-8331.

SoftWorld International

For More Information Write In No. 322



GET YOUR HANDS ON THE PROTECTOR® GLOVE BOXES CATALOG

Thumb through this 28-page, full-color catalog detailing Labconco's controlled atmosphere and multi-hazard glove boxes. Find complete information on built-in options including the automatic pressure controller with foot pedal and purge/fill controller. Call 800-732-0031.

Labconco

For More Information Write In No. 323



GET A GRIP... ON TEST AND VERIFICATION!

New CodeTEST tools from Applied Microsystems provide unit, integration and system testing, comprehensive software performance analysis, coverage analysis, and trace and memory allocation analysis, with non-sampled measurements, across your entire program. Know how your code performs, how much code your test exercises, and if memory allocation works as planned. Call for your free brochure and annotated screen-shot package—1-800-895-0831.

Applied Microsystems Corporation

For More Information Write In No. 324



NEW 1995-96 COLE-PARMER® INSTRUMENTS CATALOG

The new, free 1995-96 Cole-Parmer Instruments catalog contains over 1700 full-color pages and features

more than 40,000 products covering scientific instruments, equipment, and supplies. The catalog includes a detailed 40-page product index and table of contents, informative introductory pages for many of the catalog sections, "Hot Tips," and an 8-page section of late-breaking products. Contact Cole-Parmer Instrument Company—in the USA or Canada, call toll-free 1-800-323-4340.

For More Information Write In No. 325



METAL BELTS AND DRIVE TAPES

This general product brochure describes the various attributes that make metal belts and drive tapes an exceptional and exciting option for design engineers. Manufactured by Belt Technologies for 25 years, this unique family of products has helped design engineers overcome challenging application requirements in the electronics, aerospace, biomedical, optical and packaging industries. Belt Technologies, Inc., PO Box 468, Agawam, MA 01001; Tel: 413-786-9922; Fax: 413-789-2786.

Belt Technologies, Inc.

For More Information Write In No. 326




HI-TEMP MATERIALS TO 3200° F

Aremco produces a complete line of high-temperature ceramics, adhesives, coatings, sealants, tapes, greases, castables and potting compounds. These materials are used throughout industry in the design of sensors, electrical components and analytical instruments, as well as in the maintenance of high-temperature industrial process equipment. Aremco Products, Inc., PO Box 429, Ossining, NY 10562-0429; Tel: 914-762-0685; Fax: 914-762-1663.

Aremco Products, Inc.

For More Information Write In No. 327



NO DESIGN CHANGE REQUIRED

Standard or custom, Heavy Duty electronic cabinets give you all the flexibility you need from a single source. Meet requirements for earthquake protection, dust-proofing, shock and vibration, EMI/RFI, FCC/VDE, EMP/TEMPEST, metric and more without changing the design of your system. Equipto Electronics Corporation, 351 Woodlawn Ave., Aurora, IL 60506-9988; Tel: 800-204-RACK; Fax: 708-897-5314.

Equipto Electronics Corporation

For More Information Write In No. 328



SEE OUR CATALOG ONLINE AT [HTTP://WWW.CIR.COM/](http://WWW.CIR.COM/) AND/OR CALL 1-800-811-5201, EXT. 5, 24-HRS A DAY FOR YOUR FREE COPY.

128 pages, offering Industrial PCs, DAC/PLC, Test Equip., Educational Robotics, Semiconductors, PCs, PC Components, Breadboarding Supplies, ICs, Passives, Tools and More!

Circuit Specialists

For More Information Write In No. 329



RJ VISTA RJ45 WITH BUILT-IN LEDS

Amphenol's RJ Vista is a family of RJ45 modular jack connectors with built-in LEDs, designed for category

5 performance. Available in single and multi-port, shielded and non-shielded, and with a variety of LED colours. Amphenol Canada Corp.; Tel: 416-291-4401.

Amphenol Canada

For More Information Write In No. 330



MULTICHANNEL PULSE GENERATORS

Multichannel pulse generators provide a unique combination of functions and flexibility. Capabilities include digital control of pulse width, delay and output polarity on all channels; special pulse modes (external, burst, single-shot and duty cycle); quick recall of up to 12 saved configurations; and isolated outputs for reliable operation in electrically noisy environments. Available with two, four or eight channels. Quantum Composers, Inc. Intelligent Software, Instruments & Controls; Tel: 406-586-3159; Fax: 406-586-3220.

Quantum Composers, Inc.

For More Information Write In No. 331



AMPHENOL CANADA FILTERED CONNECTORS

- ARINC 404 & 600
- MIL-C-24308
- MIL-C-83513

New catalog provides the latest information on Amphenol Canada's high-reliability filtered connectors

outlining the advantages of our patented solderless, stress-isolated design. Amphenol Canada; Tel: 416-291-4401; Fax: 416-292-0647.

Amphenol Canada

For More Information Write In No. 332



1996 PCMCIA PRODUCTS CATALOG

The new PCMCIA-PC CARD standard has brought many new devices such as Video Capture, 16-bit Stereo, CD-ROM, Wireless Communication and PC Card Camera Cards. ENVOY DATA has just released its new catalog with these new products plus many other products like: Memory, I/O (serial, parallel, SCSI, A/D, etc.), along with Industrial Card and Drives, Multimedia, Industrial, and Engineering tools for PCMCIA applications. ENVOY DATA Corporation, 953 E. Juanita Ave., #A, Mesa, AZ 85204; Tel: 602-892-0954; Fax: 602-892-0029.

ENVOY DATA Corporation

For More Information Write In No. 333

SL-GMS

...for unprecedented performance


Build high-precision, animated screens for visual display. Build interactive screens to control real-time applications.

SL-Graphical Modeling System (SL-GMS) a fully object oriented graphics tool — the most advanced available—dramatically simplifies your work in creating interface screens of any complexity and animating them with your application data. The screen you build with SL-GMS is more than a prototype — it is your high performance, optimized graphics product.

■ Automated Traffic Management System



■ Fluidized catalytic cracking unit



■ Telecommunications network monitoring



SL supports UNIX (& X Window) on SUN, HP, IBM, MIPS, DEC (VAX/Alpha, OpenVMS/OSF-1), Intel: Windows NT, OS/2, SCO, QNX®. SL-GMS generates pipe-line display-code to reach real-time, native speeds on SGI.

For more details call: 1-415-927-1724


We are a cutting edge company always looking for talented Software Engineers. Send resume to: Kanela Espinoza

SL Since 1984
Sherrill-Lubinski
SL Corporation

240 Tamal Vista Blvd., Corte Madera, CA 94925
© 1995 Sherrill-Lubinski Corporation
All trademarks and registered trademarks mentioned are property of their respective companies.

For More Information Write In No. 420

Design Engineering Product Showcase



DERWENT WORLD PATENTS INDEX

Over 7 million inventions are contained within this single online source of international patents. Use DWPI to follow R&D efforts and trends, prevent duplication of R&D efforts and much more. Patent drawings can be viewed on your screen or downloaded for printing. Tel: 800-451-3451; E-mail: info@derwent.com; Web Page: <http://www.derwent.co.uk>.

Derwent

For More Information Write In No. 334



BENCH- TOP CNC MACHINES

Our series of bench-top CNC machines are among the least expensive machining centers on the market, small in footprint, yet large in capability. These systems allow engineers to produce prototypes and rapidly test form, fit and function of new part designs. These portable systems set up wherever needed, in a manufacturing plant or engineering office, actually on a benchtop. Light Machines Corp., 444 E. Industrial Park Dr., Manchester, NH 03109; Tel: 800-221-2763; E-mail: info@imcorp.com

Light Machines Corp.

For More Information Write In No. 336



TEMPERATURE CHAMBERS & THERMAL PLATFORMS

Faster Thermal Testing is the standard for our temperature chambers and thermal platforms. This brochure describes components with ramp rates to 100°C per minute and accuracies to within a few hundredths of a degree. Programming options offer RS232 or IEEE 488 input of up to 100 discrete steps. Chambers with gas, mechanical or boosted (combination) cooling offer burn-in, cycling or single-zone thermal shock designs. Eight standard sizes offer superior thermal conditioning and power dissipation. Sigma Systems Corp., 3163 Adams Ave., San Diego, CA 92116; Tel: 619-283-3193.

Sigma Systems Corp.

For More Information Write In No. 338



FREE LAMP CATALOG

PSC LAMPS, Inc. is one of America's fastest growing sources of replacement specialty lamps for A/V, Photographic, Stage, Studio, Video, Television, Micrographic, and Graphic Arts equipment, plus Medical & Electronic instruments. Customer satisfaction is key to our continuing success. We offer the best brands including Osram Sylvania, GE, Philips, Ushio, and Wiko at the right price, no minimum order & two-day delivery at no extra cost! For a free catalog, call 800-772-5267; Fax: 800-257-0760. PSC LAMPS, Inc., 1 Fishers Rd., Pittsford, NY 14534-9511; E-mail: <http://www.roccplex.com/pscslamps>

PSC LAMPS, Inc.

For More Information Write In No. 340



CAD/CAM SIMPLICITY, POWER & PRODUC- TIVITY

TekSoft's 3D/Surf Mill for Windows® provides users with the ease of use and flexibility to generate tool paths faster and more efficiently. True bi-cubic, parametric surface creation and NURBS surface support are packed into TekSoft CAD/CAM's advanced surfacing system. For FREE literature or more information, call 602-948-7261.

TekSoft CAD/CAM Systems


For More Information Write In No. 335



The TRIM-LOK one-piece and two-piece Locking Gaskets provide an inexpensive fixed window installation. They lock the glass in place, provide an efficient seal and are easy to install. The large range of dimensions will satisfy most applications. Custom sizes and profiles are available. For more information regarding TRIM-LOK Locking Gaskets, write to TRIM-LOK, 6855 Hermosa Circle, Buena Park, CA 90622-6180; Tel: 800-497-6353.

TRIM-LOK

For More Information Write In No. 337




NEW! 1996 MECHANICAL COMPONENTS GUIDE

Free! Nordex Design Guide 102. New items: Lead Screws, Hi-Torque 2, 3, 5mm Belts & Pulleys, 3 & 6 Beam Flex Couplings, Thermoplastic Linear Bearings, Miniature Anti-Backlash Gears, Constant Velocity Couplings, Flexible Chain & Sprockets, Ball Slides & Cross Roller Slides, Pressbearings, and Much More! Nordex Inc., 50 Newtown Rd., Danbury, CT 06810; Tel: 800-243-0986 or 203-792-9050; Fax: 203-790-8992.

Nordex Inc.

For More Information Write In No. 339



POSITIONING/ MOTION CON- TROL CATALOG

NEW, detailed 160 page catalog covers NEAT's expanding line of precision positioning and motion control components and systems. Featured are single axis, X-Y, multi-axis, rotary, high vacuum, air bearing, and microscope stages. NEAT also provides a complementary line of stepping and servomotor drives and controls. NEAT specializes in providing modified, custom, and turnkey SOLUTIONS to a wide range of positioning and motion control applications. Please contact our Sales Engineers at 800-227-1066, or send E-mail to neat@tiac.net for more information.

New England Affiliated Technologies

For More Information Write In No. 341

**A VARIABLE SPEED
DIGITAL DATA
RECORDER CAPABLE
OF SPEEDS UP TO
64 Mb/SEC.
A CAPACITY OF 27.5 GB.
A COST OF A MERE
 $\frac{1}{10}$ ¢/MB.**




For more information, call 1-800-Metrum-2.

ENOUGH SAID.

M E T R U M

For More Information Write In No. 599



Computer Programs

COSMIC: Transferring NASA Software

COSMIC, NASA'S Computer Software Management and Information Center, distributes software developed with NASA funding to industry, other government agencies and academia.

COSMIC's inventory is updated regularly; new programs are reported in *Tech Briefs*. For additional information on any of the programs described here, send in the Information Request Form or contact COSMIC directly.

If you don't find a program in this issue that meets your needs, visit the COSMIC World Wide Web pages to browse the catalog for programs in your area of interest. The COSMIC Software Catalog is available in print and free of charge on diskette, on-line, by E-mail, or FTP.

COSMIC is part of NASA's Technology Transfer Network.

COSMIC®

The University of Georgia
Athens, GA 30602-4272

T.L. Peacock, Director

(706) 542-3265

Fax: (706) 542-4807

service@cosmic.uga.edu

<http://www.cosmic.uga.edu>



Mathematics and Information Sciences

Computing Displacements and Strains From Video Images

There is no need for custom or expensive equipment.

Subpixel digital video image correlation (SDVIC) is a technique for measuring in-plane displacements on the surfaces of objects under loads, without contact. This technique can be used for analyses of experimental research specimens or actual service structures of virtually any size or material. Only minimal preparation of test objects is needed, and there is no need to isolate test objects from minor vibrations or fluctuating temperatures. The technique is implemented by the SDVIC software, which produces color-graduated, full-field representations of in-plane displacements and their partial derivatives with respect to position along both principal directions in each image plane. From these representations, linear strains, shear strains, and rotation fields can be determined.

The SDVIC software is based upon an algorithm for locating small regions of a random pattern after the pattern has been deformed. The SDVIC software determines values for in-plane displacements and strains by correlating the positions of subsets of pixels in the original image with those in the deformed image on the basis of pixel gray levels in the digitized versions of the images. The sizes of subsets to be pattern-matched can be customized, thus enabling the correlation of many random patterns. Several techniques, including a coarse-fine search and the Newton-Raphson method, are available

for subset pattern matching. A bilinear interpolation routine provides subpixel resolution necessary for most displacement and strain measurements.

To utilize SDVIC, one needs a black-and-white video camera to acquire images of the test article before and after loading. Camera-lens combinations can be altered to enable analyses of test articles of virtually any size. A personal-computer-based video circuit board is typically used to digitize the images. The images are then correlated by a personal computer equipped with the SDVIC software. All of the components needed for a typical system are commercially available. There is no need for custom equipment, which can be expensive or difficult to find.

In order to correlate properly images based upon subset gray-level patterns, one must have a characteristic pattern on the surface of the test article. This pattern can be one that occurs naturally, (for example, the microscopic grains and grain boundaries of a metal as viewed under magnification), or the pattern can be applied by dusting the specimen with fine particles or spraying the specimen with white and black spray paint. Application of a pattern typically requires only a few minutes and a few dollars for several specimens.

SDVIC is written in C language for IBM PC-series and compatible computers running MS-DOS. The minimum requirements for execution of SDVIC include an 80386 processor, Microsoft Windows v3.1, an SVGA monitor, 2MB of random-access memory (RAM), and 5MB of swap space. For best results, an 80486/66-MHz processor, 8MB of RAM, and 32MB of swap space are highly recommended. SDVIC can be executed with Windows v3.1 in the enhanced mode. A sample executable code is provided on the distribution medium. If there is need to recompile the source code, then Microsoft Software Developers Kit v3.1 and

Microsoft C compiler v6.0 are required. An electronic copy of the documentation in Microsoft Word for Windows v2.0b format is included on the distribution medium. The standard distribution medium for SDVIC is a set of four 3.5-in. (8.89-cm), 1.44MB, MS-DOS-format diskettes.

This program was written by Stephen R. McNeill of the University of South Carolina, Samuel S. Russell of Marshall Space Flight Center, and Matthew D. Lansing of the University of Alabama in Huntsville. For further information, write in 77 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-26289.



Physical Sciences


Program Models a Laser Beam Focused in an Aerosol Spray

A Monte Carlo analysis is performed on packets of light.

The Program for the Analysis of a Laser Beam Focused Within an Aerosol Spray (FLSPRY) was developed for theoretical analysis of the propagation of a laser pulse optically focused within an aerosol spray. FLSPRY can be applied, for example, to analyze a laser ignition arrangement in which a focused laser pulse would be used to ignite a liquid aerosol fuel spray. Scattering and absorption of laser light by the individual

(continued on page 73)

MSC/PATRAN is the OPEN CAE environment.



W I D E O P E N



MSC/PATRAN defines the concept of the open CAE environment. It's boundless. Broad. Deep. Full-featured. Fast. Extensively integrated. Fully programmable. And ready to use.

MSC/PATRAN is tightly integrated with MSC/NASTRAN and provides direct CAD geometry access that is second to none in the industry.

Unique preference tools give analysts the flexibility to access the solver of their choice,

using the syntax specific to that code. From small

companies to large corporations, MSC/PATRAN users create

customized applications to suit their

particular needs. Enhancing MSC/PATRAN's

advanced functionality is an easy-to-learn, easy-to-

use, Motif-compliant user interface. Experience the wide-open performance that

MSC/PATRAN can deliver to your organization. Call 800-642-7437, ext. 500

today for our informative brochure. Don't get left behind.

Simply **P**owerful.™



**The
MacNeal-Schwendler
Corporation**



KALEIDAGRAPH FOR MAC & WINDOWS

Transform your complex data into elegant graphs. Use algebraic and statistical functions to manipulate over 8 million data points. Graph up to 20 variables with precise control of plot elements. Powerful curve fitting and flexible error bars clarify visual results.

Synergy Software

For More Information Write In No. 675



SAMPLE ISSUE SCITECH JOURNAL

Free sample issue of the *SciTech Journal*, monthly technical publication of MacSciTech Association. Includes technology features, product and book reviews, new product announcements, and regular columns on the OS Wars, Engineering Problem Solving, and Color by Numbers.

MacSciTech Association, 49 Midgley Lane, Worcester, MA 01604; 508-755-5242; Fax: 508-795-1636.

MacSciTech Association

For More Information Write In No. 676




BOOKENDS PRO VERSION 3.2: ADVANCED BIBLIOGRAPHY/REFERENCE MANAGEMENT SOFTWARE

Attach any file to a reference database opening it in the application that created it; display pictures, QuickTime movies; sort, validate Editor, Journal, Author, Keyword Lists. Import from on-line services, CD-ROMs. User-defined import templates, Format Bank, Sophisticated Find and Search. Westing Software, Inc., 134 Redwood Ave., Corte Madera, CA 94925; Tel: 1-800-325-1862; Fax 415-945-3877; e-mail: westing3@aol.com; <http://www.westinginc.com/westing>

Westing Software, Inc.

For More Information Write In No. 677



Data Desk 5.0® is a Mac-based data analysis/statistics program. It uses exceptional speed and dynamic plots and tables to allow you to quickly find trends and relationships in your data. The program provides a complete set of plots and procedures and a visual programming language.

Data Description, Inc.


For More Information Write In No. 678



digiMatic® for Windows or Macintosh revolutionizes the tedious process of extracting usable data from any graphic, plot, chart, or diagram. All scientists, indeed, anyone who needs accurate, editable (X,Y) data from existing graphs, charts, spectral data, chromatograms, or virtually any other type of data image will want to use digiMatic. For more information, e-mail: ghuvar@huvar.com; World Wide Web: <http://www.huvar.com/feb/>

digiMatic

For More Information Write In No. 679



EXTEND is a powerful simulation tool that allows you to explore new ideas and try out concepts before committing valuable time and resources. Ideal for modeling industrial and commercial operations, engineering processes, scientific experimentation, and for reengineering business processes.

Imagine That, Inc.

For More Information Write In No. 680




LS FORTRAN FOR POWERMAC

LS FORTRAN is an ANSI standard FORTRAN 77 compiler for Power Macintosh. Special features include extensions for VAX, Cray, Data General, and Microsoft PC FORTRAN as well as special diagnostic debugging options. To receive a FREE brochure, send e-mail to info@fortner.com, call 800-252-6479, or fax 703-689-9593.

Fortner Research LLC

For More Information Write In No. 681



Call today for the best in electronics design tools on the Macintosh®. If you have requirements for Schematic Capture, PCB Layout, Simulation, FPGA Design, Verilog or VHDL, we can show you how to get your work done in less time. Call today, toll-free! (800) 444-9064; Fax (604) 522-3972; e-mail: info@capilano.com; www: <http://www.capilano.com/>

Capilano Computing


For More Information Write In No. 682



SPARROW offers advanced, multiparameter data acquisition and instrument control systems for the Macintosh computer. Our Kmax software is designed for applications involving industry standard modular electronics such as CAMAC, VME, VXI, GPIB and RS-232/422. The Kmax environment can be easily extended to support other interfaces or customized by the user for his specific needs.

Sparrow

For More Information Write In No. 683




MATH & SIMULATION CD-ROM

Over 600MB of information, demos, shareware, Internet resources, and articles related to mathematics, modeling and simulation on the Macintosh. 5600 files include 20+MB of Mathematica and Maple Notebooks, math and simulation software, and specific programs for engineering, chemistry, physics, and more. MacSciTech Association, 49 Midgley Lane, Worcester, MA 01604; 508-755-5242; fax: 508-795-1636.

MacSciTech Association

For More Information Write In No. 684




EXPERIMENT DESIGN SELF-STUDY

Learn how to make breakthrough improvements in your process or product. Includes: annotated viewgraphs from popular "Experiment Design Made Easy" workshop; Design-Ease® student software (Mac or Windows); simulations; case studies; \$100 workshop coupon! Money-back satisfaction. Stat-Ease Corporation 800-801-7209; Fax: 612-378-2152

Stat-Ease Corporation

For More Information Write In No. 685




SPYGLASS TRANSFORM

Spyglass Transform is the best tool available for analyzing matrix and image data. It recognizes a variety of file formats and handles enormous datasets quickly and easily. Now you can interactively test your ideas using a variety of its built-in functions. To receive a FREE brochure, send e-mail to info@fortner.com, call 800-252-6479, or fax 703-689-9593.

Fortner Research LLC

For More Information Write In No. 686



DATA ACQUISITION CD-ROM

Over 650MB of information, vendor demos, shareware, and technical articles related to acquiring, analyzing, and visualizing data on the Macintosh. Includes all publicly available LabVIEW virtual instruments (and 6MB Japanese VIs), NIH Image, NCSA imaging tools and more. MacSciTech Association, 49 Midgley Lane, Worcester, MA 01604; 508-755-5242; Fax: 508-795-1636.

MacSciTech Association

For More Information Write In No. 687



StatView's intuitive interface makes it easy to create sophisticated statistical analyses and presentation quality graphs in no time at all. MacUser Eddy winner, six time Macworld World Class winner. 100% Power Mac native. Call 1-800-666-STAT for details.

Abacus Concepts

For More Information Write In No. 690



PROPERTIES OF MATERIALS SOFTWARE

TAPP-thermophysical and thermodynamic properties of over 30,000 pure compound phases. MAPP-mechanical and physical properties of over 6,000 structural alloys and polymers. ESM Software, 2234 Wade Ct., Hamilton, OH 45013; (513) 738-4773; Fax (513) 738-4407; ESMicro@aol.com

ESM Software

For More Information Write In No. 688




STATISTICAL DISCOVERY SOFTWARE JMP 3.1 FROM SAS INSTITUTE INC. FOR MACINTOSH

AND POWER MACINTOSH (NATIVE)
JMP promotes data exploration and a better understanding of your data. JMP features: linear and nonlinear model fitting, including regression, ANOVA, MANOVA and random effects models. JMP also features statistical quality control analysis, survival analysis, and integrated design of experiments. Graphs and tables are dynamically linked. Phone (919) 677-8000 ext. 5071 or <http://www.sas.com/soft/jmp/>

SAS Institute Inc.

For More Information Write In No. 691



MACANALYST & MACDESIGNER TOOLS

Design your software with the industry leading software engineering tools, MacAnalyst and MacDesigner. OOA/OOD methods include Booch, OMT, Shlaer/Mellor, Fusion, Coad/Yourdon and Jacobson with code generation and reengineering. Integrated data modeling, SA/SD, real-time extensions and requirements traceability are also supported. Call today for technical brochures.

Excel Software

P.O. Box 1414 • Marshalltown, IA 50158 USA
p. 515-752-5359 • f. 515-752-2435 • casetools@aol.com

For More Information Write In No. 689



MACSCITECH ON THE WORLD WIDE WEB

The place for Mac-based engineering and science, <http://www.macscitech.org/>. Includes back issues of *SciTech Journal*, industry news, OS Wars, special deals on products, and more. **The Consultant's Network** lists

consultants available for hire for such projects as data acquisition, modeling/simulation. MacSciTech Association <http://www.macscitech.org/>

MacSciTech Association

For More Information Write In No. 692

(continued from page 70)

aerosol droplets are evaluated by use of electromagnetic Lorenz-Mie theory.

Initially, propagation of a laser beam is modeled by use of a simple modified paraxial-ray theory, which would limit applications to relatively "optically thin" sprays. To keep from limiting the application of the program to "optically thin" sprays, a Monte Carlo analysis of the laser beam has been adapted to FLSPRY. The Monte Carlo analysis follows individual "light packets" through a dense spray of defined thickness and composition.

The spray is assumed to be monodisperse and homogeneous, and the light packets enter along the same axis with perpendicular incidence. The Monte Carlo algorithm was modified to account for the spatial variation of intensity and the variable angle of incidence at the illuminated side of the spray. An appropriately weighted Monte Carlo decision is used to determine the position of incidence for each light packet. After a large number of attempts, a Gaussian intensity profile is generated.

Inputs to FLSPRY include the volume fraction of liquid, average size of droplets, droplet-size distribution, laser wavelength, laser-pulse energy, laser-pulse

duration, focal length of the lens, diameter of the beam incident on the lens, and the choice of aerosol liquid and surrounding gaseous medium. Other inputs include Monte Carlo analysis indicator, radius (cm) for Monte Carlo analysis, location of Monte Carlo analysis (cm) relative to the lens, number of Monte Carlo attempts, and random-number-generator seed for Monte Carlo analysis. Also necessary for Monte Carlo analysis are the x_{\max} , x_{\min} , y_{\max} , and y_{\min} thicknesses of the spray (cm). The output of the computer program includes, as a function of spatial position along the laser propagation axis within the spray, the laser-pulse intensity and energy, the overall volumetric absorption of laser energy by the aerosol liquid and by the gaseous medium, and the overall average temperature rise of the aerosol liquid and of the gaseous medium.

FLSPRY is written in FORTRAN 77 for both UNIX-based computers and DEC VAX-series computers. FLSPRY requires a compiler that supports NAMELIST input. The VAX version of the program (LEW-16051) has been successfully implemented on DEC VAX-series computers running VMS v5.5. The UNIX version of the program (LEW-16065) has

been successfully implemented on SGI IRIS-series computers running IRIX 5.2, and DEC ALPHA AXP-series computers running OSF/1. The author of the program has also successfully implemented FLSPRY on IBM RS/6000-series computers running AIX v3.2, using the FORTRAN 77 v2.03 compiler. The standard distribution medium for the VAX version of FLSPRY is a 1,600-bit/in. (630-bit/cm), 9-track magnetic tape in DEC VAX BACKUP format. It is also available on a TK50 magnetic-tape cartridge in DEC VAX BACKUP format. The standard distribution medium for the UNIX version of FLSPRY is a 0.25-in. (6.35-mm) streaming-magnetic-tape cartridge (Sun QIC-24) in UNIX tar format. Upon request, the UNIX version of FLSPRY can be provided in UNIX tar format on alternate media. FLSPRY was released in 1994.

This program was written by J. P. Barton of the University of Nebraska in Lincoln for **Lewis Research Center**.

For further information on LEW-16051, write in 32 on the TSP Request Card.

For further information on LEW-16065, write in 33 on the TSP Request Card. LEW-16051/65



Refinement of Hexahedral Cells in Euler Flow Computations

Computational grids are refined where necessary to resolve details more accurately.


Ames Research Center, Moffett Field, California

The Topologically Independent Grid, Euler Refinement (TIGER) computer program solves the Euler equations of three-dimensional, unsteady flow of an inviscid, compressible fluid by numerical integration on an unstructured hexahedral coordinate grid that can be refined where necessary to resolve shocks and other details. (As used here, "unstructured" means arbitrarily and/or complicatedly shaped, usually to fit an irregu-



larly shaped body in the flow field.) The Grid Interactive Refinement and Flow-Field Examination (GIRAFFE) computer program was written in conjunction with the TIGER program to display the computed flow-field data and to assist the researcher in verifying specified boundary conditions and refining the grid.

The TIGER program is based on Jameson's FL057 program, which solves the Euler equations on a structured


grid by use of a finite-volume, four-stage Runge-Kutta numerical-integration algorithm. The development of TIGER involved modifications to incorporate conservative calculations of mass, momentum, and energy fluxes across the faces of multiply connected grid cells. The unstructured-grid nature of TIGER makes it amenable to local refinement of the grid, as specified by the researcher.




SUBDIVISION OF A HEXAHEDRAL CELL



Original Grid at the
50-Percent-of-Span Plane



Grid at the 50-Percent-of-Span
Plane After the Second Step
of Refinement




Part of the Final Refined Grid

ASPECTS OF REFINEMENT OF THE COMPUTATIONAL GRID ABOUT AN AIRPLANE WING

Hexahedral Cells are subdivided, each into eight smaller cells, as needed to refine the computational grid in regions of high flow gradients.

Windows 95 or Windows NT?

Algor is Your Win-Win Solution for FEA




No matter which version of Windows you choose, you only need *one* version of Algor software. Algor's new "WIN" software operates as a 32-bit application in either Windows 95 or Windows NT.

Algor's WIN Software Provides:

- Improved graphics.
- Faster operating system processing, made faster still by Algor's new SS2000 processor!
- Updated Algor "Roadmaps" to guide you through the engineering design and analysis process.
- Graphics in Windows format, enabling copy/paste to other Windows applications such as PowerPoint, PageMaker, QuarkXPRESS, Microsoft Word, Paintbrush and many others.
- Support for the Windows Print Manager, for easy printing and compatibility with other Windows applications.
- The ability to run Algor's 32-bit software as a true Windows application, with multitasking, "plug and play" technology, improved networking and more.
- Use of the Windows pop-up file menu for all file access.
- Enhanced Edit and Help menus.
- The ability to create icons which activate often-used files.

Try it yourself!

Download free Algor "WIN" software from the World Wide Web:



WWW.ALGOR.COM

♦ ALGOR®

When the Engineering
Has to be Right™

Algor, Inc.

150 Beta Drive, Pittsburgh, PA 15238-2932 USA

Phone: +1 (412) 967-2700

Fax: +1 (412) 967-2781

California: (714) 564-0844

Europe (UK): +44 (784) 442 246

E-mail: info@algor.com

COOL IT.

with Master Bond
Thermal Conductive
Epoxy



SUPREME 11A0HT

- Room temperature or heat cure
- Highly electrically insulative
- Excellent vibration & shock resistance
- High peel and shear strength
- Thermal conductivity: 10Btu/hr/ft²/in/°F
- Low shrinkage
- Convenient packaging

For information, call or write:
Master Bond Inc., 154 Hobart St.
Hackensack, NJ 07601 • 201-343-8983


Master Bond Inc.
Adhesives, Sealants & Coatings

For More Information Write In No. 430

HEADHUNTER™

HEAD & EYE SLAVED POINTING SYSTEM

Real-time head & eye movement monitoring systems for advanced man/machine interface. Applications include workstation control, simulation/training, human factors & target designation.



ISCAN

P.O. Box 382076
Cambridge, MA 02238-2076 USA
Tel: 617-273-4455
Fax: 617-273-0076

For More Information Write In No. 431

Each grid cell can be split into eight smaller cells (see figure). If further refinement is needed, the smaller cells can be subdivided similarly. Refinement of the grid appropriate to each flow-field condition and tailored to capture shocks or other specific flow features can be based on a variety of criteria; for example, the ratio between the local and free-stream total pressures, the difference between the maximum and minimum pressures in the vicinity, or the preliminarily calculated location of a shock.

The TIGER program takes about the same amount of time to compute a flow as do conventional flow-simulating programs that solve the Euler and Navier-Stokes equations on structured (that is, regular) grids. The TIGER program involves the use of simple, straightforward programming techniques to take advantage of the vector-processing capabilities of the CRAY Y-MP computer. The TIGER program requires approxi-

mately five times more memory per grid point than a conventional structured-grid program does, but in TIGER, it is not necessary to refine the grid throughout the entire flow domain. When the refinement of the grid is based on flow parameters specified by the researcher, points of the resulting grid are usually distributed more appropriately for the problem, yielding a net decrease in the total memory required.

This work was done by John E. Melton and Gelsomina Cappuccio of **Ames Research Center** and Scott D. Thomas of Sterling Federal Systems. Further information may be found in AIAA paper 91-0637: "Unstructured Euler Flow Solutions Using Hexahedral Cell Refinement."

Copies may be purchased [prepayment required] from AEROPLUS, Burlingame, California 94010, Telephone No. (800) 662-2376, Fax No. (415) 259-5047. ARC-13077


Sensing Position With Approximately Constant Contact Force

LVDTs are held lightly against the surface to be measured.

Marshall Space Flight Center, Alabama

A computer-controlled electromechanical system uses a number of linear variable-differential transformers (LVDTs) to measure the axial positions of selected points on the surface of a lens, mirror, or other precise optical component with a high finish. The system maintains the contact force of each probe at a level between the weights of 9 and 13 grams:

this level of force is just large enough to ensure consistent measurements but not so large as to cause damage to the surface when the probe is compressed or extended during axial positioning of the optic, over an axial range of 7 mm, between measurement positions in contact with the optic surface when the optic is rotated between measurement positions.



The Pressures Applied to Pneumatically Driven LVDTs are adjusted under computer control to maintain small, approximately constant contact forces as the positions of the LVDT tips vary.

Leak-tight Valves & Fittings for Analytical Instrument Applications

The leak-tight technology of the SWAGELOK companies is built into all the products you see here.

They work with each other to give you design flexibility. You can select sizes, shapes, materials and ratings to handle *your* service conditions.

They're all manufactured to the same standards of precision and quality control. You can count on consistent tolerances, compatible end connections, and reliable seals.

They're available locally from Authorized Sales and Service representatives. You can save money through efficient purchasing, controlled inventories, and on-time delivery.



TUBE FITTINGS



BALL & PLUG VALVES



FILTERS



METERING VALVES

CHECK & RELIEF VALVES



QUICK-CONNECTS



WELD FITTINGS



O-RING & METAL GASKET FACE SEAL FITTINGS



FLEXIBLE HOSE



NEEDLE VALVES

These Products are subjects of patent or patents pending



the
SWAGELOK
companies

SWAGELOK Co.
Solon, Ohio 44139
SWAGELOK Canada Ltd., Ontario

The contact tip of each LVDT is a 4-mm ruby ball. Each LVDT is spring-loaded in retraction from the surface to be measured. The probe is driven pneumatically, against the spring loading, into contact with the surface. The pneumatic pressure applied to each probe is sensed and adjusted via an electromechanical pressure transducer. Operating under computer control, the transducers for all the probes maintain the pressures that produce the required contact forces.

The output of each LVDT is a voltage indicative of the position of its tip. During the initial approach to the surface to be measured, the probes are retracted. The

pneumatic pressure driving each probe is increased in steps to extend the probe in steps of 0.006 in. (≈ 0.15 mm). Eventually, the position reading from a probe stops increasing, signifying that the probe has made contact with the surface. Thereafter, the computer maintains the pressure at the level that corresponds to the required contact force. In computing this pressure, the computer accounts for the increase in spring retraction force with increasing extension of the tip or decrease in spring retraction force with compression of the tip.

*This work was done by Jay Sturdevant of Hughes Aircraft Co. for **Marshall***

Space Flight Center. For further information, **write in 49** on the TSP Request Card.

Title to this invention has been waived under the provisions of the National Aeronautics and Space Act {42 U.S.C. 2457(f)} to Hughes Aircraft Co. Inquiries concerning licenses for its commercial development should be addressed to:

Hughes Aircraft Co.

Attn: Jay Sturdevant

7200 Hughes Terrace

P.O. Box 45066

Los Angeles, CA 90045-0066

Refer to MFS-28936, volume and number of this NASA Tech Briefs issue, and the page number.

Multigrid, Fractional-Step Computation of Flow

Computation of incompressible flow to high resolution takes less time.

Ames Research Center, Moffett Field, California

The speed of a computer code that solves the three-dimensional Navier-Stokes equations of flow of an incompressible fluid by the fractional-step method has been increased significantly by use of multigrid procedures. In the specific version of the fractional-step

method, the equations are solved on a general nonorthogonal curvilinear coordinate grid, using volume fluxes (instead of velocities). At each time step, computations are performed in two fractional steps. In the first fractional step, the equations of conservation of momentum

are solved by use of the gradient of pressure from the previous time step via an explicit approximate-factorization method, yielding an approximate flow field that does not satisfy the equation of conservation of mass. In the second fractional step, a discrete Poisson-like

Solid Modeling Simplified

CAD without clutter or complexity. Intergraph's **SOLID EDGE** gives you all of the capability and none of the confusion of traditional CAD systems. High-performance mechanical modeling in the comfortable, familiar Microsoft Windows® environment lets you spend more time designing, and less time operating a CAD system.



Next-generation interactive design tools. **SOLID EDGE** helps you design faster with innovative, intuitive mechanical modeling that is easy to learn and use. If you want to shorten learning curves, improve productivity, and reduce training costs, the clear choice is **SOLID EDGE**.

For the ease-of-use advantage, call **800-546-5550** or reach us on the Internet at <http://www.intergraph.com/mech/solidedge.shtml>.

INTERGRAPH
SOFTWARE SOLUTIONS



INTERGRAPH
SOLID EDGE

Intergraph and the Intergraph logo are registered trademarks and Solid Edge is a trademark of Intergraph Corporation. Microsoft and Windows are registered trademarks of Microsoft Corporation. Copyright 1995 Intergraph Corporation.

equation with Neumann-type boundary conditions, formed by combining the equations of conservation of momentum and mass, is solved iteratively.


The number of arithmetic operations of, and therefore the time consumed by,

the iterative solution of the Poisson-like equation increases with the number of grid points; heretofore, it has usually amounted to more than 80 percent of the total time of a fractional-step computation. The multigrid method is the only one

that provides solution procedures that both are applicable to general curvilinear coordinates and entail numbers of arithmetic operations that increase no more than linearly with the number of grid points. Furthermore, multigrid techniques for the solution of elliptic types of equations similar to the Poisson-like equation are well developed.

To test the ability of the multigrid method to accelerate convergence toward the solution of the Poisson-like equation, several incompressible flows were computed. These included two-dimensional flow about an elliptical airfoil, two-dimensional flow between two eccentric cylinders, and three-dimensional flow in a square duct with a bend. In each case, the computational time needed to solve the Poisson-like equation was reduced by an order of magnitude (see figure), while the overall computation time was reduced by a factor of 3 to 4.

The solution of the Poisson-like equation by use of the multigrid method consumed less than 25 percent of the total central-processing-unit time. The computational work was found to be approximately proportional to N (where N is the number of grid points), while the total central-processing-unit time on a Cray Y-MP vector computer was found to be



This **History of Convergence** toward the solution of the Poisson-like equation was obtained in a computation of flow between eccentric cylinders on a grid of 256×256 points, using four different solution procedures. A work unit (the scale of the abscissa) is a measure of computational effort, essentially proportional to the number of arithmetic operations.

Freedom of Assembly

CAD for assembly.

Intergraph's **SOLID EDGE** goes beyond the part modeling approach of traditional CAD systems to improve assembly design productivity and quality. With specialized assembly design tools, you can model part-to-part relationships, analyze interference, and experiment with assembly configurations.



Design within the assembly.

With **SOLID EDGE**, you build a digital assembly prototype that helps you identify and eliminate design problems. Unique assembly navigation and management aids help you move quickly through large models, select the environment for your design task, and collaborate with assembly project teams. You can even build assemblies using parts from other CAD systems!

For the assembly design advantage, call 800-546-5550

or reach us on the Internet at <http://www.intergraph.com/mech/solidedge.shtml>.

INTERGRAPH
SOFTWARE SOLUTIONS



SOLID EDGE

Intergraph and the Intergraph logo are registered trademarks and Solid Edge is a trademark of Intergraph Corporation. Copyright 1995 Intergraph Corporation.

NOTHING ELIMINATES STATIC ELECTRICITY LIKE STATICIDE!

**JUST SPRAY IT ON
AND WIPE IT OUT.**

Static electricity can wipe out your profits in an instant.

Staticide is a long-term topical anti-stat that prevents costly damage caused by static charge build-up.

Ideal for use in electronic production areas, just spray or wipe Staticide on any surface where static is generated. Completely non-toxic, biodegradable and humidity independent, Staticide is a cleaner as well as an anti-stat.

Don't let static electricity threaten your business. Order Staticide today.


ACL Staticide
Specialists in Static Control



ISO 9002

Reg. to: ACL Inc. Cert. No. A3656

1960 E. Devon Ave., Elk Grove Village, IL 60007 **1-800-782-8420** Fax: (847) 981-9278
e-mail: info@aclstaticide.com Web address: <http://www.aclstaticide.com>



For More Information Write In No. 416

approximately proportional to $N^{0.75}$. Thus, it appears that the combination of multigrid and fractional-step methods provides a viable alternative for the computation of complicated flow fields with very large numbers of grid points.

This work was done by Dochan Kwak of Ames Research Center and Moshe Rosenfeld of Tel Aviv University. Further information may be found in AIAA paper 92-0185, "Multigrid Acceleration of a Fractional-Step Solver in Generalized Curvilinear Coordinate Systems."

Copies may be purchased [prepayment required] from AEROPLUS, Burlingame, California 94010, Telephone No. (800) 662-2376, Fax No. (415) 259-5047.

This is the invention of a NASA employee, and a patent application has been filed. Inquiries concerning license for its commercial development may be addressed to the inventor:

Dochan Kwak
4153 Georgia Ave.
Palo Alto, CA 94306
Refer to ARC-13196.

Bearings Incorporating Deadband Rollers

*Marshall Space Flight Center,
Alabama*

Bearings in a high-pressure turbo-pump have been redesigned to incorporate rollers that allow limited axial motion within a small deadband. The design does not permit radial deadband motion, which is undesired. The axial deadband motion would be used for rotor-thrust-balance control. The axial-deadband rollers would be supported by a multisided bearing carrier. This design would eliminate some nonlinearities in the dynamics of the pump rotor and assist in suppressing vibrations at harmonics of the frequency of rotation.

This work was done by Guy V. Gualtieri of United Technologies for Marshall Space Flight Center. To obtain a copy of the report, "Bearing Deadband Rollers," write in 27 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-28914.



**MADE IN
U.S.A.**

**From 2-Piece Economy
Commercial to MS
Approved Aerospace
Bearings...**

WE'VE GOT IT ALL!

Inch Sizes From 1/8"-2"
Metric Sizes In Stock

**WRITE FOR
FREE CATALOG**



AURORA BEARING COMPANY

970 S. Lake St. • Aurora, IL 60506
Ph. 708-859-2030 • FAX 708-859-0971

For More Information Write In No. 417

Industry Focus: Motion Control/Positioning Equipment

Control of a Serpentine Robot for Inspection Tasks

In keeping with its serpentine character, the robot moves with a slither.

NASA's Jet Propulsion Laboratory, Pasadena, California

An efficient, robust kinematic control scheme has been developed to control a serpentine robot that is designed to inspect a complex structure (see figure). The control scheme takes full advantage of the multiple redundant degrees of freedom of the robot to provide considerable dexterity for maneuvering through a workspace that can be cluttered with stationary obstacles at initially unknown positions. Appropriately to the serpentine configuration of the robot, the control scheme produces a slithering motion.

The robot includes an anthropomorphic robot arm mounted on a platform with one degree of freedom (the platform can translate along a track). The anthropomorphic robot arm includes joint actuators that provide 7 degrees of freedom. Mounted at the tip of the anthropomorphic robot arm is a 6-jointed appendage with 12 degrees of freedom. Thus, there is a total of 20 degrees of freedom.

The control scheme is based partly on a version of the configuration-control concept, which has been discussed in a number of prior articles in *NASA Tech Briefs*. To recapitulate: A robot has n degrees of freedom (in this case, $n = 20$). The basic task is to make the tip of the end effector (the hand at the tip of the manipulator arm) follow a prescribed trajectory in m -dimensional coordinates (where $m < n$). The $r = n - m$ redundant degrees of freedom are used simultaneously to perform an additional task, which can be specified by the user and can include reaching around obstacles, avoiding collisions with objects in the workspace, maintaining one or more links of the manipulator arm in a desired pose, and/or optimizing the overall kinematics. The additional task is represented by a set of kinematic functions that, in effect, define the trajectory in the redundant degrees of freedom.

The end effector of the serpentine robot is instrumented with proximity sensors to detect obstacles and thereby provide for control feedback to pre-


vent collisions between the end effector and the obstacles. It is also necessary to prevent such collisions for all of the interconnected links of the robot arm. The resulting motion-control problem is complex; to cope with the complexity, the problem is decomposed into two subproblems.

The first subproblem is that of the basic task of finding a collision-free path for the end effector, using the readouts from the end-effector sensors and one of the many available mobile-robot-control algorithms. The second subproblem is that of the additional task of making the 6 joints of the appendage follow the same path as that taken by the tip of the end effector so that joints and the links between them also do not collide with obstacles: this amounts to specification of a slithering motion, in which each joint is required to follow the preceding one, the two joints being separated from each other by the length of the intervening link.

This requirement is expressed mathematically as a set of kinematic constraints on the 12 degrees of freedom of the appendage.

The equations for the position of the end effector in terms of the joint angles (equations of forward kinematics) and the equations for the velocity of the end effector in terms of the joint angles and rates of change of these angles (equations of forward differential kinematics) are combined with the corresponding equations for the joints following the end effector to obtain an augmented set of equations, and the augmented set of equations of differential kinematics is solved by use of a damped-least-squares algorithm to obtain the joint-angle rates, which are then integrated in time to obtain the joint angles, as a function of time, that result in the desired trajectories.

It has been proposed to extend this control scheme to cope with an environment in which the obstacles are



The Serpentine Inspection Robot maneuvers to avoid collisions with the struts of a truss.

not necessarily stationary. For this purpose, proximity sensors would be mounted on all of the links. The proximity-sensor information regarding the locations of obstacles would be compressed into a set of kinematic inequality con-

straints. The motion-control algorithm would be modified to ensure that these inequality constraints are satisfied, thereby ensuring avoidance of obstacles.

This work was done by Homayoun Seraji of Caltech and Richard D.

Colbaugh and Kristin L. Glass of New Mexico State University for NASA's Jet Propulsion Laboratory. For further information, write in 59 on the TSP Request Card. NPO-19506

❁ Non-Back-Drivable Gearboxes With Greater Efficiencies

Components are designed so that input torques reduce frictional losses.

NASA's Jet Propulsion Laboratory, Pasadena, California

Non-back-drivable gearboxes with power-transfer efficiencies greater than those of conventional non-back-drivable gearboxes are undergoing development. The greater efficiencies are made possible by a novel design concept that utilizes the input torques in such a way as to reduce frictional losses.

A non-back-drivable gearbox is one that locks itself when input power is not supplied: it transmits torque from a high-speed, low torque input shaft to a low-speed, high torque output shaft, but does not transmit torque from the output shaft back to the input shaft. Typical conventional non-back-drivable mechanisms include worm gears and lead screws. All non-back-drivable gearboxes rely on friction. To make a gearbox non-back-drivable according to the conventional design concept, it is necessary to make the power lost to friction equal to or greater than the output power. Consequently, the theoretical maximum efficiency of a conventional non-back-drivable gearbox is 50 percent. In practice, typical efficiencies are less than 35 percent.

The figure illustrates an example of a non-back-drivable gearbox of the present higher-efficiency type. The input shaft turns a left-handed helical gear that drives a right-handed helical


gear on a main shaft. A quad-lead (that is, quadruple-thread), right-handed worm on the main shaft drives a quad-lead worm gear on the output shaft. Considered by itself, without the braking mechanism described below, this particular worm-gear mechanism is back-drivable, with an efficiency of 80 to 90 percent whether the worm or the worm gear is being driven.

The main shaft turns in ball bearings that allow some small axial movement. Disks with outer conical braking surfaces are mounted near the bearings at both ends of the shaft. At either extreme of the small axial movement, the conical braking surface on one of the disks makes contact with a mating stationary conical braking surface. When a torque is applied to the output shaft in an attempt to back-drive the gearbox, the worm gear exerts a back-driving torque on the worm; it also exerts an axial force on the main shaft, thereby pushing the main shaft axially until one of the conical brakes engages. The dimensions and materials of the various components are chosen so that the braking frictional torque exceeds the back-driving torque on the worm. To state it differently, the back-driving torque on the worm is not sufficient to overcome the braking frictional torque. This makes the main shaft


non-back-drivable, even though the worm-gear mechanism would otherwise be back-drivable.

The reason for using a left-handed driving and a right-handed driven helical gear at the input is that they utilize the input torque in a manner that reduces the braking friction. The engagement of these gears gives rise to an axial thrust on the main shaft; this thrust is proportional to the input torque and in the direction opposite that of the axial thrust exerted by the load or attempted-back-driving torque. The force of engagement of the conical braking surfaces and thus the braking torque are reduced accordingly. With less braking friction to overcome, a greater proportion of the input power is transmitted to the output. Of course, the success of this concept depends in part on choosing the design parameters so that the torque transmitted from the input shaft to the main shaft is great enough to overcome the remaining braking friction but not so great as to drive the shaft to the opposite extreme position in which the other brake engages.

This work was done by Timothy R. Ohm of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 9 on the TSP Request Card. NPO-19322



This **Non-Back-Drivable Gearbox** can be designed to exhibit an efficiency greater than the theoretical maximum of 50 percent for conventional non-back-drivable gearboxes. Typical theoretically achievable efficiencies appear to exceed 70 percent.




Oildyne's EMC Group Experts in Linear Positioning Technology

The Most Complete Position Transducer Family Available

Oildyne's LRT is a uniquely designed, position sensing device that uses a simple resistive element and wiper to provide an analog output signal. The Analog Signal can be used to monitor or control the position of a cylinder or other device.

Only Oildyne's EMC Group can provide these advantages

- Stroke lengths to your exact specifications – you don't have to purchase in 2" or 6" increments.
- System electronics that can be connected at right angles to the cylinder to allow for any cylinder mounting style.
- An LRT that adds only 1" to the length of a standard cylinder.



- Stroke lengths to 130" are available in 1/8" increments.
- Mini-LRT transducers that fit into piston rods as small as 3/8" diameter.
- "Smart" cylinders in bore sizes 1/2" to 14" diameter.

Electronic Motion Control Systems

Oildyne also offers a complete line of Cylcon "open" or "closed loop" Control Systems that can be used for your system positioning requirements.



NAT'L 800-394-1654
NAT'L FAX 800-394-0082

EMC Group 4301 QUEBEC AVE. N., MINNEAPOLIS, MN 55428

Compensating for Friction in a Rotation-Testing Turntable


A motor would apply a torque calculated to cancel the frictional torque.

Lewis Research Center, Cleveland, Ohio

A proposed turntable for testing heavy equipment in rotation would be driven by two motors (see figure). One of the motors would operate under actuator commands from a position-control subsystem; it would rotate the turntable to commanded angular positions according to the specifications for a test. The other motor would operate under actuator commands from a friction-compensating control subsystem; this motor would approximately cancel the effect of frictional torque in and on the turntable, so that the equipment could be tested as though in a nearly frictionless environment.

The turntable was conceived for testing angular-positioning systems for spacecraft solar arrays that weigh several tons; it would be equally useful for effectively frictionless rotational testing of heavy terrestrial equipment. The

turntable and its control system would be used instead of any of a variety of low-friction supporting mechanisms like tethers, air bearings, and floatation devices. Although the electronic control system of the turntable would be



The Turntable Would Bear a Massive Load for rotational testing. The friction-compensating motor would apply a torque calculated to counteract the frictional torque.



Consider ...

SCHNEEBERGER
LINEAR TECHNOLOGY

Frictionless Tables For Your Most Precise Positioning Tasks.

OEM Applications

- Machine Tools
- Robotics
- Aerospace
- Medical
- Electronic Assembly
- Automation
- Semiconductor
- Packaging
- Gauging




SCHNEEBERGER Frictionless Tables are linear guidance systems designed for precise positioning tasks in numerous applications. SCHNEEBERGER tables are renowned not only for their high degree of accuracy, but also their unduplicated level of performance consistency.

SCHNEEBERGER tables come in varying standard sizes from miniature units to multi-axis systems permitting the user to find the most suitable solution for the engineering application.

1-800-854-6333

Schneeberger, Inc.
11 DeAngelo Drive
Bedford, MA 01730

Tel: 617-271-0140
Fax: 617-275-4749




SERVO TUNING
CONTROL PANEL

Are You Performing Tuning Gymnastics?

With Mitsubishi's new MR-H Servo System, you'll never lift a finger again. Using the patented "real-time adaptive tuning control," the MR-H continuously detects disturbances (load fluctuations) and automatically compensates, optimally tuning the system while the machine is in operation. The result? Consistently stable operation—and increased production rates while improving positioning accuracy. Save your workouts for the gym and let our MR-H servo do all the work for you.

TWEAK-O-METER



LOAD COMPENSATOR

ON

OFF



 **MITSUBISHI**
INDUSTRIAL AUTOMATION DIVISION

©1996 Mitsubishi Electronics America, Inc.
800 Biermann Court, Mt. Prospect, IL 60056
Phone: (800) 445-4496 FAX: (847) 298-1834
In Canada call: (905) 475-7935

PLCs • AC DRIVES

• SERVOS

For More Information Write In No. 801

Right On Target!

When you use Xybion products!

Our COTS and custom-designed subsystems or surveillance system designs keep you Right On Target!


Landbased, shipboard or airborne -- reliability that is **WARRANTED** -- The Series 1000/2000 positioners provide everything you need:

**MIL Spec
Stabilized LOS
Digital Real-Time Controls
Lightweight/Modular
Construction**

Xybion systems are ruggedized, lightweight precision pedestals that satisfies your surveillance, detection, or MMW applications.

Call or Fax for Data Sheets:

Xybion Corporation
Sensor Positioning Systems
Tel: (813) 524-1447
Fax: (813) 524-1897



4500 140th Avenue N.
Suite 115
Clearwater, Florida 34622
USA

For More Information Write In No. 807

complex, the turntable would be mechanically simpler than the other mechanisms and it would be more stable. The turntable would also enable testing under more realistic conditions.

The friction-compensating control subsystem would have to be calibrated to make the friction-compensating motor apply the opposite of the frictional torque as a function of the speed of rotation, independent of inertial forces. For this purpose, the positioning motor would be turned off and the frictional torque would be measured at a large number of constant speeds over the range of possible speeds. The resulting data on frictional torque vs. speed would be recorded in an electronic read-only memory (ROM) in the friction-compensating control subsystem. Thereafter, during a test on the turntable, the friction-compensating control subsystem would command the motor to apply a torque opposite the recorded frictional torque as a function of speed.

Static friction, which in general is greater than dynamic friction, would also be measured and stored. With the turntable at rest, the torque applied by the friction-compensating motor would be slowly increased until the turntable would just begin to break free and start rotating; the torque at that instant would be the value recorded. Thereafter, whenever the turntable was stationary during a test and the angular-position-control subsystem called for rotation, the friction-compensating control subsystem would command the friction-compensating motor to apply the break-free torque in the direction of commanded rotation.

In addition to compensating for friction, the turntable control system could command the simulation of a variety of dynamic effects, including those caused by friction in other equipment or longitudinal movement, on the turntable, of the equipment under test. The torque effects to be simulated could be introduced by use of appropriate torque-vs.-speed and/or torque-vs.-angular position algorithms in a computer in the torque-compensating control subsystem.

This work was done by Craig C. Sullender, Kevin R. McCarthy, and Bradley J. Suppanz of Rockwell International Corp. for **Lewis Research Center**. For further information, **write in 83** on the TSP Request Card. LEW-15695


FlexMotion™

The Most Advanced Motion Control Computer Boards

- Up to 10 Axis - Single PC/ISA Slot
- 32 Bit CPU & DSP Dual Processor Design
- 65 μ Sec PID & 16 Mhz Encoder Feedback
- Electronic Gearing, Circular Interpolation
- Multi-Axis Coordinated Vector Control
- Continuous Contouring & Blending
- Windows™ S/W, C Libraries, DLLs
- Visual Basic & LabVIEW®
- Servo & Stepper



New!



nuLogic®

617-444-7680 fax: 617-444-2803
475 Hillside Avenue • Needham, MA 02194

For More Information Write In No. 808



The right ball screw for your application.

Nobody offers more precision ball screws than NSK. Standard or custom. Certified accurate. Various circulation and preload designs, lead accuracies, and accessories are available. Ask for your **FREE** product guides.

NSK Corporation



Fast, flexible, highly accurate indexing.

NSK's compact Mega-Indexer™ rotary positioner operates at speeds to 60 rpm with 60 arc-sec accuracy and features a programmable controller capable of storing up to 64 motion profiles. Ask for your **FREE** product guide.


NSK Corporation



Powerful, precise, high-speed linear positioning.


The Megathrust Motor from NSK is a direct-drive, servo-controlled linear actuator capable of generating forces to 192 lbs. at operating speeds up to 71 in/sec with 1μm resolution. Variety of travel lengths. Ask for your **FREE** product guide.

NSK Corporation



NSK makes precise linear positioning a package deal.

NSK's Mono Carrier™ linear positioner combines a precision ball screw and a specially designed linear guide into a compact, integrated package. You spend less time on motion system design, less time on assembly, and less time on adjustment.



Both basic mechanical and DC servo motor-driven models are available. Stroke lengths vary from 4" to 40". Repeatability is $\pm .00012"$. Speed ranges up to 20 in/sec.

Ask for your **FREE** product guide.



Linear guides with up to 30% more capacity.

NSK's unique Gothic arch design means linear guides with greater static load-bearing capacity and interchangeable components. Wide selection of DF and DB designs—all quality certified. Ask for your **FREE** product guide.

NSK Corporation



Reliable, repeatable rotary positioning.

The Megatorque® motor from NSK is a direct-drive, servo-controlled motor. It provides output torque to 180 ft-lb at speeds to 180 rpm. Gearless design means exceptional repeatability and acceleration. Ask for your **FREE** product guide.

NSK Corporation

NSK Corporation

Precision Products Division

250 Covington Drive • Bloomington, IL 61018-3106 USA

1-800-255-4773 FAX 708-924-8197



FORGET BALL SCREWS

Remember Kerk Anti-Backlash and general purpose Lead Screw Assemblies for unsurpassed quality.

- PRECISION SCREWS
- PATENTED NUT DESIGNS
- NO PRE-LOADING OR LUBRICATING
- LEAD ACCURACY TO .0001 IN./IN.
- LONG LIFE, SMOOTH OPERATION
- LOW DRAG TORQUE / LOW COST



For more information: tel 603-465-7227 • fax 603-465-3598
1 Kerk Drive, Box 539 • Hollis, NH 03049

For More Information Write In No. 809

A great memento for space and movie buffs! The **Apollo 13 Commemorative T-shirt** features a gorgeous full-color rendition of the official Apollo 13 mission emblem (the "Horses of Apollo") superimposed with dramatic effect on a black T-shirt. Adult sizes: S, M, L, XL. \$13.95



Name _____
Company (if applicable) _____
Address _____
City/St/Zip _____
Phone No. _____ Fax No. _____

Mail with payment to: Associated Business Publications,
317 Madison Avenue, Suite 921, New York, NY 10017.
Credit card orders call (212) 490-3999.

Reduced-Weight, Reduced-Backlash Planetary Gearhead Stage

Other features include high torque capacity and an axial hole for cables.


*NASA's Jet Propulsion Laboratory,
Pasadena, California*

An improved planetary gearhead stage weighs less, produces less backlash, and has greater output torque capacity than does a conventional planetary gearhead stage of the same outside diameter. It also includes an axial through-hole that can be used as an open optical path or to accommodate wires, optical fibers, pneumatic or hydraulic tubes, mechanical actuator cables, and/or other connections. This planetary gearhead stage is prototypical of a class of high-torque output stages of compact, lightweight multistage gearheads that can be used in the joints of robot arms.

The figure illustrates some of the differences between this and a conventional planetary gearhead stage. The sun gear has been enlarged into a ring to accommodate the axial through-hole. The enlargement of the sun gear enables an increase in the number of planet gears from three to eight. One result of the increase in the number of planet gears is that each planet gear can share a smaller part of the load. Because there are more planet gears, there are also more pins to transmit the output torque, and the load per pin is reduced. Moreover, the pin-circle diameter is greater, so that the output torque capacity is increased.

Another result of the increase in the number of planet gears is that the outward radial forces of the planet gears on the internal gear are applied more nearly uniformly around the circumference, so that these forces tend to induce less deformation of the internal gear from its nominal circularity than they do when these forces are applied at only three points as in the conventional design. Thus the internal gear can be made thinner because less stiffness is needed to maintain circularity. If the internal gear has a thin wall and oversized planet gears are used, the internal gear can be stretched slightly over the planet gears to reduce or eliminate backlash.

The main disadvantage of the improved design concept is that the torque-increase and speed-reduction ratios are



The **Improved Planetary Gearhead Stage** contains more planet gears and a thinner, slightly conformable internal gear. The internal gear is fixed, the sun gear provides input torque, and torques contributed by the forces on the planet gears are transmitted to an output shaft via the carrier pins.

Compumotor's ZETA Series...

A true revolution in microstepping technology.

Increased efficiency and reduced settling time improves throughput.

Compumotor's ZETA Series combines the benefits of a smaller footprint with advanced features to provide the highest performing and most cost-effective microstepping system available today. Through innovative technology, the ZETA Series improves machine throughput in two ways. Active Damping enables more of the motor's torque to be used for acceleration rather than overcoming the step motor system's typical vibration. Electronic Viscosity decreases settling time by reducing motor oscillation at low speeds.


More power to the load... More usable torque at all speeds.

Compumotor's innovative Active Damping electronically damps motor vibration. By eliminating vibration, the power formerly reserved for the safety margin can now be used to do useful work. This can provide as much as a 50% increase in usable torque. In conventional step motor systems, the speed-torque curves represent the

Comparison of Usable Shaft Power

Traditional Stepper System

ZETA Series




motor's total shaft power, not the usable shaft power. Again, as a result of Active Damping, Compumotor's ZETA system has greater usable shaft power. This higher usable shaft power results in higher torque at all speeds, compared to conventional stepper systems.

A worldwide network of Automated Technology Centers.

The ZETA Series is delivered and supported by an international network of factory-trained organizations specializing in the application of high technology automation equipment. Contact Compumotor for the Automation Technology Center nearest you.

For more detailed information on the ZETA Series, just write Parker Hannifin Corporation, Compumotor Division, 5500 Business Park Drive, Rohnert Park, CA 94928. Or call 800-249-0520. Ask for dept. 3817



The ZETA Drive incorporates patentable techniques known as active damping and electronic viscosity for higher throughput in a smaller package—and all at a reduced cost.

*Worldclass
Quality Products
and Service*

Parker
Motion & Control

LITERATURE SPOTLIGHT

Free catalogs and literature for *NASA Tech Briefs* readers. To order, write in the corresponding number on the Reader Information Request Form (preceding page 81).



HOERBIGER-ORIGA FULL-LINE LINEAR MOTION BROCHURE

A newly updated full-line, four-color brochure presents Hoerbiger-Origa's pneumatic rodless and specialty cylinders, as well as other innovative products used in pneumatic systems. Features, benefits and specifications are highlighted. Hoerbiger-Origa; Tel: 800-695-5984; Fax: 708-941-3424.

Hoerbiger-Origa

For More Information Write In No. 819



COMPACT MOTORIZED POSITIONERS

60mm wide by 32 mm high, Daedal's new M102000 and M402000 Series positioners pair high-performance bearing systems with rolled or precision ground leadscrews into compact, accurate single and multi-axis positioning systems. Tables feature standard protective way covers and optional limit and home switches, Z-axis brackets, stepper and servo drives, and control systems and start at less than \$500 for 50 mm of travel. Daedal Division, Parker Hannifin Corp.; Tel: 800-245-6903; Fax: 412-744-7626.

Daedal Division, Parker Hannifin Corp.
For More Information Write In No. 820



Apollo 11 Commemorative Sweatshirt

Striking full-color illustration on quality white shirt recaptures the spirit and excitement of the Apollo moon landing. Available in adult sizes-S,M,L,XL \$19.95 each plus \$5.00 shipping/handling.

(NY residents add sales tax.)

Mail with payment to: Associated Business Publications, 317 Madison Avenue, Ste 921, New York, NY 10017. For credit card orders call (212) 490-3999.

reduced. The ratio for a typical conventional planetary gearhead stage is about 5:1, whereas that of a stage according to the improved concept is typically about 3:1. Of course, this limitation can be overcome by use of multiple stages. Alternatively, if an axial hole through all stages of a multistage gearhead is not needed, then the improved design can

be reserved for the final high-output-torque stage and the preceding stages can be of conventional design.

This work was done by Timothy R. Ohm of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, **write in 30** on the TSP Request Card. NPO-19321

Tracking Motions of Manually Controlled Welding Torches

Positions, orientations, and velocities would be determined in real time during manual arc welding.

Marshall Space Flight Center, Alabama


Techniques for measuring the motions of manually controlled welding torches in real time are undergoing development. The purpose of this development is to make it possible to treat manual welding processes more systematically so that manual welds can be made more predictable, especially in cases in which the mechanical strengths and other properties of welded parts are highly sensitive to heat inputs and thus to velocities and orientations of welding torches.

As the concept is envisioned at the present early stage of development, the position and/or orientation of a welding torch could be measured by sensors such as accelerometers, gyroscopes, electrolytic tilt sensors, or mechanical linkage devices with encoders. In a proof-of-concept demonstration with no arc operating, an electromagnetic

sensor was used to obtain six-degree-of-freedom data on position and orientation of a welding torch that was moved along various test trajectories. Software to process these data into usable form (see figure) and to compute the velocity of the tip of the torch was developed. Present work is being conducted under full welding conditions using a six-degree-of-freedom jointed arm to track torch motion.

This work was done by Carolyn Russell of **Marshall Space Flight Center** and Ken Gangl of **Advanced Welding Concepts, Inc.** For further information, **write in 91** on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-26330.



This Trajectory Was Computed From Measurements taken by an electromagnetic sensor as the welding torch was moved in a circular path about a fixed tube.

Airstroke[®] actuators • Airmount[®] isolators

Simple Solutions for industrial motion & vibration problems

Firestone invented the Airide[®] spring, which has found wide acceptance on truck, trailer and bus suspensions. This same technology has been proven in thousands of industrial applications just like yours.




Airstroke[®] actuators and Airmount[®] isolators


Outperforms conventional pneumatic & hydraulic cylinders

In applications which require initiation and control of motion—Airstroke actuators give you:

- **Angular capability**—the unique property of stroking through an arc without a clevis. The design advantages are simpler linkages, decreased bushing wear, reduced structural stress, and up to 30 degrees of angular motion.



- **Tolerance to off-center & minor side loading**—Airstroke actuators are virtually unaffected by off-center & side loading, while conventional cylinders end up with bent rods, scoring and excessive seal wear. You save on replacement costs and downtime with Airstroke actuators.



- **Compact starting height**—even the largest, 37" diameter, triple convoluted spring collapses to just 5.5" high. The smallest size collapses to just 1.5". This advantage over cylinders gives you numerous design possibilities and wide application flexibility.



- **Friction-free action**—for immediate response on-the-job. No sliding seals or breakaway friction as with cylinders. You get smoother control and more consistent response.


...plus, Airstroke actuators cost less than cylinders, work with gas (air) or liquid and require no maintenance or lubrication.

Outperforms other vibration isolators


For vibration isolation and shock bumpers or stops, Airmount isolators give you:



- **Unsurpassed isolation capability**—no coil spring isolates vibration like air can. System natural frequencies as low as 60 cycles per minute—1 HERTZ—can be achieved. A coil spring would have to provide a real deflection of 9" to compare.



- **Constant isolation efficiency**—a unique feature that means the spring system frequency does not change with changes in load. The advantage to you is that one size Airmount isolator can be used at each mounting point of an unevenly loaded machine.




- **Effective noise reduction**—no "chatter" like metal coil springs. Rubber and air Airmount isolators are quiet in themselves. The result is a quieter work environment, along with better structural member protection.



- **Versatility**—Airmount isolators handle loads from 100 lbs. to 100,000 lbs. per mounting point. Installed height can be as low as 2.5", with accurate height control through internal air pressure regulation. Airmount

isolators are as applicable on heavy vibrating machinery as they are on delicate, sensitive types of equipment.



Both Airstroke actuators and Airmount isolators come in a wide range of sizes to give you precise application fit. Firestone can make your motion and vibration problems disappear into thin air. Call your local distributor today for design assistance.

Firestone
World's Number 1
Air Spring.

FIRESTONE INDUSTRIAL PRODUCTS COMPANY

701 Congressional Blvd., Carmel, IN 46032 317/580-2300

For More Information Write in No. 804

Solving Positioning Problems

Is Our Business

New England Affiliated Technologies understands that you need to work faster, at a lower cost, and produce a higher quality product.

NEAT provides more than just *precision positioning and motion control components and systems*. NEAT provides **SOLUTIONS**.



Five Axis Air Bearing System

We take the time to listen to your application requirements and work hard to provide the *best* solution at the *lowest possible cost*, whether that means off-the-shelf, modified, or completely custom designed products.

NEAT has over two decades of experience serving a wide variety of industries including semiconductor, flat panel, digital imaging, optical, test and inspection, medical, automotive, and fiber optics. We have the ability to conceptualize, design and manufacture positioning systems using the latest technologies.



Call us today to discuss your application requirements with our


Sales staff... or to request a copy of our FREE 160-page catalog.



Phone: 1-800-227-1066 Fax: 1-800-523-8201

1-508-685-4900 1-508-688-8027

E-mail: sales@neat.com #85



new england affiliated technologies

620 Essex Street, Lawrence, Massachusetts 01841 USA

For More Information Write In No. 805

Motion Control Industry Leaders

FIRESTONE INDUSTRIAL PRODUCTS COMPANY

Firestone is the manufacturer of the world's #1 air spring for both vehicular and industrial applications. Division headquarters and main sales offices are located in Carmel, IN, with manufactur-

ing facilities in Noblesville, IN; Williamsburg, KY; Dyersburg, TN; and Sao Paulo, Brazil. Additional sales offices are located in Southfield, MI; Staines, Middlesex, England; and Sao Paulo, Brazil.

Firestone developed the air spring in the late 1930s as a more efficient spring (vibration isolator) for use in vehicle suspensions. Airide® springs, as they were named, provided the means for a suspension to reduce the amount of road shock and vibration transmitted into the vehicle. Millions of miles of actual use have proven the dependability and effectiveness of the air suspension concept using Airide® springs by Firestone.

In addition to their use on heavy-duty trucks, Firestone air springs are also used on passenger-rail cars, buses, light- and medium-duty trucks and buses, and automobiles.

In industrial applications, Airstroke® actuators are capable of generating a force of 100,000 lbs., and Airmount® isolators can

isolate up to 80,000 lbs. They are available in a wide variety of sizes ranging from as small as 2.8" in diameter to 37".

Some of the industries that utilize air springs include: manufacturing, forest products, pulp and paper, aerospace, steel, packaging, material handling, amusement and entertainment, food processing, agriculture, transportation—or anywhere something needs to be moved, pushed, lifted, or isolated.

For more information, call 1-800-888-0650 or E-mail Firestone via the Internet: firestone@industry.net; England: 44-1784-462-326; Brazil: 55-11-411-1166.

For More Information Write In No. 811



NEW ENGLAND AFFILIATED TECHNOLOGIES

Motion Control and Positioning Systems and Components

New England Affiliated Technologies (NEAT) is a leading manufacturer of precision positioning and motion control components and systems. Located in

Lawrence, Massachusetts, NEAT was established as a division of Instrument Industries, Inc. and has been solving positioning problems for over 20 years.

NEAT operates two, uniquely integrated facilities: a 33,000 square foot building houses the engineering, product design and development, assembly, machining, and administrative teams, while a 13,000 square foot building serves as a Large Systems Facility for the design and production of sizable posi-

tioning systems. These tightly integrated teams and facilities allow NEAT to minimize the design and build cycle and respond promptly to customer requirements.

NEAT employs engineers with experience in electronics, mechanics, optics, and physics. In many cases, positioning requirements, whether simple or complex, cannot be met with standard, off-the-shelf components. NEAT's special strength lies in their willingness and ability to provide solutions, not just components.


NEAT prides itself on supplying optimal solutions to challenging customer requirements in

fields such as semiconductor inspection and probing, digital imaging, optical bonding, and general automation.

NEAT regularly designs and builds high vacuum positioning systems, such as the spectrometer positioners aboard ESA's SOHO satellite.

Contact: Krista Fabian, NEAT, 620 Essex Street, Lawrence, MA 01841; Tel: 1-800-227-1066; Fax: 1-800-523-8201.

For More Information Write In No. 812



INTELLIGENT MOTION SYSTEMS, INC.

Excellence in Motion™

Intelligent Motion Systems, Inc. is a leader in stepping motor drive technology. Patented technology, which is a hallmark of leadership, includes their unique "Auto Slow/Fast Decay" circuitry. This is an advanced technology, that when used in a PWM driver, reduces current ripple and permits the use of low inductance motors in high-speed applications. Stepping motor drivers, from IMS, provide the performance required for today's and tomorrow's most demanding applications.

Focused solely on the design and manufacturing of compact, efficient, low-cost stepping motor drivers and controls, IMS provides



the user with a broad product range of full step/half step and microstepping drivers. Drivers that offer the OEM and the single unit user the highest performance-to-cost ratios available. Features found on IMS drivers include optically isolated inputs, chopping rates at 20 kHz for inaudible operation, and single supply operation. These features are typically found only in larger, more expensive drivers.

Dedicated to satisfying customers' needs means up-front technical application assistance and the technical support needed for easy integration into a user's application. Technological leadership and dedication to supplying quality stepping motor drivers at low cost helps customers of IMS retain a competitive edge in today's marketplace. As IMS drivers are also designed for ease of manufacturing, JIT delivery in OEM quantities is easily achieved. Intelligent

Motion Systems, Inc. truly represents "Excellence in Motion."

Miniature High Power Microstepping Driver

High power-to-size ratio is a feature of this new, economical, high-performance microstepping driver from Intelligent Motion Systems. The IM804 driver combines advanced surface-mount and application-specific integrated circuit (ASIC) technologies to provide 600 watts of bipolar power from a package only 3 in. x 2.75 in. x 1.3 in. (76.2 mm x 69.9 mm x 33.0 mm). The IM804 FET bridge drivers accept high voltage, up to 75 Volts, and provide 4.0 Amps RMS and 6.0 Amps peak current to each phase. The inaudible 20 kHz chopper driver includes circuitry to minimize ripple current, reducing wasteful motor heating and encouraging the use of low inductance motors that will improve high speed performance and system efficiency.

The proprietary technology in the ASIC gives designers high performance microstepping control by providing them with the capability to switch microstep resolution on the fly. This technology provides full motion-profile control, high position resolution, silent and resonance-free when operating at slow speeds near the target position, and expanded (lower) resolution for substantially higher speed capability for slewing between target positions. Additional features include programmable motor run and hold currents, all way short circuit over/under voltage and over temperature protection, power and fault LEDs, and all operated from a single supply voltage.

For more information, contact Intelligent Motion Systems, Inc., 370 North Main St., Marlborough, CT 06447; Tel: 860-295-6102; Fax: 860-295-6107.

For More Information Write In No. 813

MITSUBISHI ELECTRONICS AMERICA, INC.

MR-C High-Performance, Low-Cost Micro-Servo Drive

Mitsubishi Electronics' new MR-C brushless servo system is a high-function, economical alternative to 5-phase or microstepping drives. The compact size and low cost of this new series of servo motors and amplifiers virtually eliminate the need for stepping drives.

To improve the performance and meet the increasing demands of positioning applications, stepper manufacturers have added encoders and features such as damping and viscosity control—essentially pseudo-like "servo" capabilities, but without all the benefits of precise servo control. Conversely, Mitsubishi was able to develop a servo package that is easy to use, low cost, and extremely compact, yet still offers advanced servo functions that traditional stepper drives will never be able to offer.

Smallest Amplifier Yet

By incorporating a new miniaturized intelligent power module with a single micro-chip process-

ing unit (CPU), Mitsubishi has produced its smallest sized servo amplifier yet. The two amplifiers, 100 and 200 Watts, are available in single-phase, 110 and 230 VAC versions. They are only 1.57 inches wide, 5.12 inches high, and 3.94 inches deep, allowing customers to mount more units in smaller spaces.

The new MR-C servo motors include advantages of innovative technologies in all three areas of motor design. The encoder is reduced in size by eliminating one of two printed circuit boards. Rotors produce more power in smaller packages by using neodymium-iron-boron magnets. Stators are specially constructed to produce even more power than before. The smallest motor, 30 Watts and 300 RPMs, is only 1.57 inches in diameter and 3.56 inches long.

The MR-C has 100% torque from zero to almost 4,500 RPM, and 400% torque available from 0 to almost 4,500 RPMs. This superior torque capability allows



the MR-C to far surpass the ability of steppers to accelerate and especially decelerate from any speed.

The hardware platform is the same powerful 32-bit reduced instruction set microprocessor (RISC) used in Mitsubishi's higher function MR-H servo drive, and provides high performance with a frequency response range of 200 Hz.

The patented real-time adaptive control scheme is the heart of

the system's operation, eliminating the need for any retuning following a load change. Using a 32-bit RISC processor, the algorithm provides an advanced servo that responds to the diverse and demanding needs of the motion control market. Compared to traditional systems, which required constant adjustment by hand, the MR-C servo amplifier offers a unique and efficient alternative.

As a bonus, an optional RS-232C interface kit allows use of an optional Windows-based software package that allows you to diagnose the drive and display waveforms from your PC.

For more information, contact Mitsubishi Electronics America, Inc., 800 Biermann Ct., Mt. Prospect, IL 60056-2173; Tel: 708-298-9223; Fax: 708-298-0567.

For More Information Write In No. 814

NSK CORPORATION, PRECISION PRODUCTS DIVISION

NSK Corporation is a world-class manufacturer of precision motion control components and systems. Product offerings include high-precision direct drive rotary and linear motors, X-Y stages, high-speed indexers, ball screws and linear ball bearing guides. The Precision Products Division is a leading U.S. supplier of high-quality and high-accuracy mechanical and mechatronic components to many industries.

Precise positioning is achieved with both the direct drive YS Series MegaTorque® Motor System and linear Y Series MegaThrust Motor System. The MegaTorque rotary positioner is a direct drive DC brushless servo that provides high speed and extremely accurate positioning capabilities. Gearless design means zero-backlash, micron level positioning and maintenance-free operation. Permanently lubricated bearings can handle axial loads up to 4000 lbs. The system provides high



reliability and comes in a variety of sizes and models including waterproof styles. Up to 360 ft./lb. of torque, speeds as high as 180 rpm and resolution of 2.1 arc/sec. It provides ideal motion control for robots, indexers, automatic assembly and machining applications.

The YS Series comes com-

plete with interchangeable motor, programmable driver and cables. It is equipped with an RS-232C interface to make programming simple and convenient. A hand pendant is used to input parameters and programs for the first time or if the motor is not connected to a personal computer.


The MegaThrust Motor is a linear positioner that incorporates the same principles of the MegaTorque motor. Direct drive eliminates backlash and loss of accuracy common in mechanical designs. Standard, multi-function digital servo driver can be interfaced with a variety of remote components and controllers for sophisticated sequencing. Motor generates up to 132 lbs. of force with speeds up to 71 in./sec. with ± 1 micron repeatability. Effective stroke lengths up to 100 ft.

For more information, contact NSK Corporation, Precision Products Division, 250 Covington Dr., Bloomington, IL 60108; Tel: 800-255-4773; Fax: 708-924-8197.

For More Information Write In No. 815

OILDYNE EMC GROUP

Introduces Two New Innovative Products



1/2" Bore Smart Cylinder

1/2" Bore Hydraulic Smart Cylinder

Oildyne EMC Group has designed one of the smallest Smart Cylinders ever available. The cylinder is a remarkably small 1/2" bore, complete with an internal position feedback transducer that provides for infinite positioning capability. This is a perfect package for those applications where space is a premium but positioning and hydraulic forces are required.

The cylinder features a maximum 9" stroke length and pressures up to 2500 psi. There is a miniature 3-pin quick disconnect electrical connector for connection to a PLC or other electronic motion controller.

Miniature Valve Pad Smart Cylinder

Oildyne has also developed a miniature Smart Cylinder featuring an integral hydraulic proportional valve pad and valve. Now, for the first time, it is possible to have a 1" bore hydraulic smart cylinder and mini hydraulic proportional valve as one complete integrated package. This provides a totally unique product for those applications

where space is at a premium but hydraulic forces and positioning are a requirement.

These products are part of a uniquely designed linear resistor position transducer family that allows for internal installation in cylinders as small as 1/2" bore. They feature a right angle exit for an electrical connection that provides an advantage not found in most position transducers. The design also

has the advantage of being manufactured in any length desired rather than only in 1", 2", or 6" increments. For hydraulic or pneumatic applications the LRT/MLRT family provides the designer the opportunity for the smallest profile, infinite resolution, and linearity from .1% to 1% of stroke, depending on the model.

For More Information Write In No. 816



1" Bore with Mini NG3 Valve

PARKER HANNIFIN CORP., COMPUMOTOR DIVISION

Compumotor: A Pioneer in Microstepping and Servo Motor Technologies

Incorporated in 1979, Compumotor earned its reputation for innovation by pioneering microstepping drive techniques to improve the smoothness and resolution of step motor control systems. Compumotor's innovative leadership has continued to produce a complete line of stepper motor and servo drive systems, computer bus-based and stand-

alone controllers, and extensive applications software. Parker Hannifin's acquisition of Compumotor in 1986 fostered breakthroughs in servo technology, followed by AC brushless drives, DSP servo controller techniques, and smart drive controller combinations. Today, after a decade of innovation, Compumotor is among the largest service-orient-

ed and most technologically advanced suppliers of electronic motion controls in the world.

The Complete Solution

We provide more than just the products necessary for today's demanding automation requirements. An accessible network of knowledgeable worldwide support resources accompanies every product. To maintain our leadership position in the electronic motion control industry as a complete supplier of electromechanical solutions, it is mandatory that we continue to identify, invest in, and develop those technologies, products, services, and processes that will always keep our products ahead of the competition.

Custom Service and Custom Products

It is impossible to anticipate every need of every individual (and unique) customer. After evaluating our extensive line of


products, you may decide that a customized version of a standard product is required. A custom product can be anything from a software modification to integrating our products into larger systems. Compumotor is prepared to quickly respond and adapt to your specific requirements.

The Right Choice

Compumotor's distinguished product excellence and experience in the electronic motion control industry is as far-reaching as our global support network. Selecting a Compumotor product is much more than a decision for today—it is an investment in your future.

For more information, write to: Parker Hannifin Corp., Compumotor Division, 5500 Business Park Drive, Rohnert Park, CA 94928.

For More Information Write In No. 817



WARNER ELECTRIC

Offers Programmable Linear Actuators

Warner Electric, long a leading supplier of linear and rotary motion control devices, now offers an extensive line of programmable linear actuators that features greater service life and expanded load-carrying capabilities, operating speeds, duty cycles, and accuracies. Named the *Electrak 2000*, this industry-leading line of linear actuators is available in both high-efficiency ball screw and economical Acme screw models.

All *Electrak 2000* actuators are engineered to operate for up to 50 million cycles. Operating speeds range from 20 inches/second for 40-lb. loads to 2 inches/second for 500-lb. loads, with repeatability of 0.0005 inches. Standard stroke lengths are 2, 4, 6, 8, 12, 18, and 24 inches. The maximum load capacity for parallel models with ball screw drive is 2000 lbs.

Ball screw models feature excellent speed, load, and duty-cycle capabilities with low power



consumption. An electrically-released, spring-set brake mounted on the step motor controls back-driving of the ball screw actuator if power is interrupted.

Acme screw units offer an economical alternative for applications with lower load, speed, and duty-cycle requirements. The Acme screw models can hold ver-

tical loads without back-driving in either a power-off or a stall mode.

Designed to be impervious to washdowns, *Electrak 2000* sealed step motors carry an IP-56 rating and are featured as standard equipment. Controls are supplied complete with I/O boards, input power cables, indexer, and drive.

All *Electrak 2000* Series actuators are available with a menu-driven software package that is specifically designed for linear motion/position applications. With terms expressed in linear units rather than in motor steps, the new software ensures simplified programming.

Mounting options include front flanges, trunnions, side-tapped holes, and mounting feet. Encoders, sensors, and brakes are offered as options. Both parallel and in-line actuator configurations are available.

For additional technical information on any Warner Electric product, contact: Warner Electric Advertising Department, 449 Gardner Street, South Beloit, IL 61080; Tel: 815-389-3771; Fax: 815-389-2582.

For More Information Write In No. 818



Helium-Recycling Plant


Helium would be conserved with little contamination or back pressure on the source.

Lyndon B. Johnson Space Center, Houston, Texas

A proposed system would recover and store helium gas for reuse. The system would maintain the helium at

99.99-percent purity, preventing water vapor from the atmosphere or lubricating oil from pumps from contami-

nating the gas. The system would take in the gas at a nearly constant low back pressure near atmospheric pres-



Helium From a Test Stand would enter a variable-volume capture vessel for temporary storage before being transferred to tanks for longer-term storage. The capture vessel would be a buffer that would prevent the application of excessive back pressure to the test stand.

sure [14.7 psi (0.101 MPa)]; that is, it would introduce little or no back pressure into the source of helium.

The helium-recycling system was conceived for test facilities of NASA and its contractors, which together use almost 10 million standard cubic feet (about 283,000 standard cubic meters) of helium per year. Recycling would save an estimated \$650,000 (in 1992 prices) annually. The concept could also be extended to recycling of other gases. The helium to be recycled would enter the system through inlet pipes

that would route the helium from a test stand or other source to a semicylindrical capture vessel (see figure). The pipes, typically 3 in. (7.6 cm) in diameter, would be designed to offer low resistance to flow and, consequently, low pressure drop. The inlet plumbing would include a butterfly-type isolation valve and a filtering relief valve, which would keep out particulate contamination while preventing excessive buildup of pressure in the vessel.

The capture vessel would be a lined variable-volume enclosure that would

be made to expand to accommodate the incoming helium. The growth of the capture vessel during intake of helium would prevent the buildup of back pressure that would interfere with the operation of the source of helium. The maximum expansion of the vessel would accommodate 60,000 ft³ (about 1,700 m³) of helium — the amount emitted by a full day's operation of the test stand for which the system was conceived.



The walls of the capture vessel would be made of a low-outgassing material that would have a low permeability by helium, so as to minimize contamination and leakage of helium. A liner of metallic foil or metalized plastic would reduce contamination and leakage further. The bottom of the vessel would be tied down to prevent wind from blowing it away.

A volume-control system would monitor the pressure in the capture vessel and adjust the volume of the vessel accordingly by regulating the stiffness of an integral rib structure. The controller could be an electronic computer or a pneumatic logic circuit. It would use some of the recycled helium to pressurize the ribs through a metering valve or pressure regulator and a rib manifold. Increasing the pressure in the ribs would stiffen them, raising the enclosure and thereby increasing the volume. Decreasing the pressure would soften the ribs, lowering the enclosure, and thereby reducing the volume.

A compressor would pump the helium out of the capture vessel overnight into storage in tanks at a pressure above 2,000 psi (14 MPa). The compressor would be of a diaphragm type that minimizes contamination. On its way to the tanks, the helium would be purified further in a liquid-nitrogen cold trap, which would remove water vapor and other impurities. The helium could also be filtered through porous metal to remove particles larger than 100 micrometers.

This work was done by Joseph Cook of Johnson Space Center. For further information, write in 81 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, Johnson Space Center; (713) 483-4871. Refer to MSC-22091.



**Power.
When you
need it.
Whenever
you need it.**

EVANS

P.O. Box 4158, East Providence RI 02914
(401) 434-5600. Fax (401) 434-6908.

The Evans Capattery. Very small, very powerful, very reliable.

This incredible double-layer capacitor is a unique carbon-based device that is housed in a welded tantalum package.

Its patented Permselective valve allows it to release CO₂ generated during normal operation while inhibiting the escape of electrolyte vapors and preventing contaminants from entering the container.

A 5.5-volt, 1F Capattery has a volume of 0.5 in.³, an 11-volt, 0.5 F Capattery has a volume of less than 1 in.³.

The Capattery has a temperature range of -55°C to 85°C. It withstands unlimited charge/discharge cycles.

ONLY ONE COMPANY'S FEEDBACK ENGINEERS DISGUISE THEMSELVES AS SALESMEN.



It's HEIDENHAIN. As an original equipment manufacturer, you deserve the right to partner with salesmen who can hold up their end of the partnership. ■ That's why all **HEIDENHAIN** OEM salesmen have degrees in either mechanical or electrical engineering. More importantly, they have an average of 15 years experience in our industry. They have encountered design problems similar to yours and can help your design staff avoid many common pitfalls, saving you time and money. ■ In fact, **HEIDENHAIN** OEM salesmen are so experienced, they usually function as part of our customers' design teams. A service we're happy to provide free because linear and rotary encoders are most effective when "designed in" at the earliest possible conceptual stages. ■ If you're in the conceptual stage on one or more projects, please call one of our feedback engineers today. Just be sure to ask for a salesman.



HEIDENHAIN

HEIDENHAIN CORPORATION ■ 115 Commerce Drive ■ Schaumburg, IL 60173 ■ Phone: 708.490.1191 ■ FAX: 708.490.3931

North American Sales & Service Offices

Salem, New Hampshire • Aquascaliente, Mexico • Los Alamitos, California • Mississauga, Ontario, Canada

Noncavitating Pump for Liquid Helium

An immersion pump features high efficiency in cryogenic service.


Ames Research Center, Moffett Field, California

A simple and reliable centrifugal pump transfers liquid helium with a mass-transfer efficiency of 99 percent — no more than 1 percent of the cryogenic liquid is lost by boiling off due to energy input from the pump. The pump operates without cavitation even with negative values of net positive suction head. (Net positive suction head is the difference in static head between the liquid at the inlet of the pump and the static head in saturated vapor.)

The purpose of the pump is to transfer liquid helium from a supply to a receiver vessel, or to provide liquid helium flow for testing and experimentation. The pump includes an induction motor, a centrifugal impeller, a helical inducer, solid-lubricated ball bearings, and a housing (see figure). It is located in a supply vessel submerged in liquid helium, which also serves to cool the motor. With a net positive suction head of ~ 12 cm or more, the pump delivers 800 L/h at a head of 128 J/kg and an impeller speed of 12,000 r/min.

Liquid helium first flows into the inducer, then flows into the centrifugal impeller. The inducer resists blockage of flow from cavitation and imparts a small head to the inlet stream to reduce the tendency to cavitation in the impeller. The centrifugal force in the impeller provides most of the pressure rise through the pump. The liquid helium flows radially away from the impeller through the diffuser region between front and back covers, then enters a plenum that surrounds the inlet. As the helium decelerates in the diffuser and plenum, its kinetic energy is partially converted into increased pressure. From the plenum, the liquid leaves the pump through the outlet port.

There are two ball bearings, that carry axial and radial shaft loads. The bearings



Liquid Helium Is Drawn into the pump by the helical inducer, the primary function of which is to pressurize the helium slightly to prevent cavitation when the liquid enters the impeller. The impeller then pressurizes the liquid.

consist of stainless-steel balls and raceways with fiberglass/polytetrafluoroethylene/nylon composite retainers, selected for a combination of durability and lubricating properties in a severe cryogenic environment. After 24 h of continuous operation, the bearings showed light wear but no sign of imminent failure.

The motor is of a three-phase ac, squirrel-cage type. An induction motor was chosen for its simplicity and absence of commutating electrical connections (graphite brushes in commuta-

tors are short-lived in a dry environment with no moisture for lubrication).

This work was done by Robert Hasenbein, Michael Izenson, Walter Swift, and Herbert Sixsmith of Creare, Inc., for Ames Research Center. For further information, write in 56 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Ames Research Center; (415) 604-5104. Refer to ARC-13229.

Magnetostrictive Actuators for Cryogenic Applications

These actuators would work at both room and cryogenic temperatures.

NASA's Jet Propulsion Laboratory, Pasadena, California

Linear-translation motors containing magnetostrictive actuator elements have been proposed for use in making fine position adjustments on scientific instruments at temperatures from near absolute zero to room temperature. Like

piezoelectric actuators of a similar type described previously in *NASA Tech Briefs*, these actuators would produce small increments of linear motion and would operate in a "set-and-forget" mode in the sense that they would auto-

matically lock themselves against motion when power was not applied. Conversely, they would not consume or dissipate power when stationary.

The reason for using magnetostrictive (as distinguished from piezoelectric)

Heating a medical device? We have the perfect prescription!

Heaterstat™
Sensorless Controller

Stick-on simplicity...
Sophisticated thermal control

Flexible Thermofoil™ heaters are the sure cure for chronic heating ailments: Easy to apply as a flexible bandage, yet capable of uniform, efficient heat • Proven performance in diagnostic devices, catheters, fluid warming, respirators

Etched-foil element with chemical-resistant polyimide insulation • Drop-in-place subassemblies with integral sensors, connectors, metalwork, flex-circuitry • Optional factory mounting • Full range of temperature controllers

MINCO

 PRODUCTS, INC.

7300 Commerce Lane • Minneapolis, MN 55432-3177 U.S.A.
Telephone: (612) 571-3121 • FAX: (612) 571-0927

For More Information Write In No. 670

Thermal-Clear™ Heaters The clear choice for transparent heating

Optical grade mylar with fine wire element for shine-through heating • 82% minimum light transmission
• Rectangular, round, and irregular shapes to 11" x 22"
• Optional temperature sensors & controllers

Extend the operating range of LCD's & fluorescent tubes
• Portable computers & scanners • Incubator covers
• Microscope stages • Aircraft displays • Medical devices • Outdoor security equipment • Faceplates

MINCO

 PRODUCTS, INC.

7300 Commerce Lane • Minneapolis, MN 55432-3177 U.S.A.
Telephone: (612) 571-3121 • FAX: (612) 571-0927

For More Information Write In No. 671

Heaterstat™ Sensorless Temperature Controller

Low cost, compact DC controller operates on feedback from heating element — no sensor required! • Regulates up to 3 A at 4.5 to 60 VDC • Adjustable setpoint
• Solid state design • Wire leads or circuit board mount

Accurate temperature control with minimal space requirements & power consumption • LCD's • Vehicular electronics • Medical devices • Miniature components: Crystals, inkjet printheads, lasers • Scientific apparatus

MINCO

 PRODUCTS, INC.

7300 Commerce Lane • Minneapolis, MN 55432-3177 U.S.A.
Telephone: (612) 571-3121 • FAX: (612) 571-0927

For More Information Write In No. 672

Thermal-Ribbon RTD's fast response surface sensing

S17422
0.1 second response

S17624 Thin film RTD

S651 Miniature platinum RTD

Thin, flexible resistance temperature detectors • Wire wound or thin-film • Pt, Cu, Ni, Ni-Fe curves • 0.1 second time response • Rugged laminated construction
• -200 to 220°C range • Many sizes & styles in stock

Stable, accurate, dependable measurement • Install with self-stick backing, tapes, or cements • Avionics
• Process lines • Medical devices • Aircraft windows
• Stator windings • Thermal processing equipment

MINCO

 PRODUCTS, INC.

7300 Commerce Lane • Minneapolis, MN 55432-3177 U.S.A.
Telephone: (612) 571-3121 • FAX: (612) 571-0927

For More Information Write In No. 673

actuators is that magnetostrictive actuators function throughout the desired temperature range, whereas piezoelectric actuators tend to become inoperable in

cryogenic environments. Although voice-coil actuators have been demonstrated at low temperatures, they cause waste of cryogen (because of continued con-


sumption and dissipation of power when stationary at nonequilibrium positions), offer limited maximum displacements, and require complicated controllers. Because of the "set-and-forget" mode, the proposed actuators would thus offer advantages over voice-coil actuators; namely, less power dissipation (and consequently less consumption of cryogen). The proposed linear-translation motors could also be made to produce large maximum displacements.

Moreover, the controller of a motor of the proposed type could be relatively simple because it would be required to generate only simple sequences of on/off commands for three magnetostrictive actuator elements. As shown in the figure, these elements would be (1) a magnetostrictive element that, when energized, would pry clamp 1 to slide on the guide rod; (2) a similar element in clamp 2; and (3) a linear-motion element.

One cycle of operation (during which the motor would effect one increment of linear motion) would consist of the following events:


1. Friction in the clamps would maintain the initial position as long as power was not applied.
2. Power would be applied to the magnetostrictive element in clamp 1, causing this clamp to release the guide rod while clamp 2 continued to grip.
3. The linear-motion element would be energized, causing clamp 1 to translate one increment of position, relative to clamp 2, along the guide rod.
4. Power would be removed from the magnetostrictive element in clamp 1, causing clamp 1 to grip the rod. Thus, at this point, both clamps would grip the rod.
5. Power would be applied to the magnetostrictive element in clamp 2, causing this clamp to release the guide rod while clamp 1 continued to grip.
6. Power would be removed from the linear-motion element, causing clamp 2 to move along the guide rod by the same amount and in the same direction as clamp 1 moved previously.
7. Power would be removed from clamp 2, so that both clamps would grip the rod.
8. At this point, the motor would be unpowered at the incremented position, and friction between the clamps and the guide rod would maintain the position as long as power was not applied.

This work was done by Benjamin P. Dolgin of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, **write in 67** on the TSP Request Card. NPO-19218



When this **Linear-Translation Motor** was not powered, friction created between the clamps and the guide rod would maintain the position of the motor along the guide rod. The motor would move in steps; during each step, a motor controller would systematically turn the power on and off in the magnetostrictive elements.

Watts are Watts*



The new **PECOS®** (Porcelain Enamel Coating on Steel) resistors allows the same watt dissipation as old fashioned power resistors in less space and features direct mounting on PC boards. They are non-inductive and lower cost than comparable wire wound resistors. Available in 10 watts to 100 watts and .25 ohms to 250K ohms.

For more information on how to reduce your cost and space requirements, contact **Ohmite Manufacturing Company** Tel. 708-675-2600, Fax 708-675-1505 and ask for Catalog #50008 or contact one of our authorized distributors.

Fax order form

Fill out below, photocopy this AD then Fax to Ohmite: 708-675-1505. You'll promptly receive your catalog and the name of your Ohmite distributor.

Name _____ Company _____

Address _____ State _____ Zip _____

Your Phone _____ Your Fax _____

OHMITE®
THE POWER BEHIND RESISTORS


Ohmite Manufacturing Company
3601 Howard St. Skokie, Illinois 60076

70th
ANNIVERSARY

Data Acquisition Direct To Tape At 15 MBS.

**51 GB uncompressed
tape capacity**

**15 MBS sustained
throughput,
uncompressed**



**Fast/Wide SCSI, ESCON,
IBM Channel, and Parallel
Data Channel Interfaces**

**Rack mount configuration
available**

Built to match the speed of the fastest computer systems while providing the high capacity needed to handle massive amounts of data, the CY-9000 half-inch digital DTF drive is a performance breakthrough.

Store 51 GB on a single tape, *uncompressed*.

Save time and resources by writing directly to tape at a record-breaking speed of 15 MB per second — 54 gigabytes per hour — over a *terabyte* every day.

Choose from Fast/Wide SCSI, ESCON, IBM Channel, and Parallel Data Channel interfaces for plug

compatibility with the widest range of systems.

Available in a desktop or rack mount configuration, the drive features a 32 MB data buffer. An optional Digital Data Recorder interface provides up to 128 MB of variable rate buffer to ensure a smooth flow of data from host to drive, regardless of fluctuations in the data source.

Whatever configuration you choose, the drive will be up and running when you need it with a MTBF of 200,000 hours — the best reliability in the industry.

You'll also like the fact that the compact cartridges are widely available and easy to organize, ship, and store.

If you need it, 100% lossless data compression is available to boost tape capacity to up to 153 GB and speed to 20 MBS.

If you're serious about data acquisition, get the tape drive that's serious about performance.

Call today for more information.

(804) 833-9000

CYBERNETICS

Tera One • Yorktown, VA 23693 • Fax (804) 833-9300



Manufacturing Superconducting Cables

For protection, superconducting ceramic would be encapsulated before activation.

NASA's Jet Propulsion Laboratory, Pasadena, California

A process has been proposed for the manufacture of cables that contain the ceramic high-temperature-superconductor $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$. The cables would carry electrical current with little or no loss of power when cooled to or below temperatures of about -200°C . The process would accommodate the brittle nature of $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$ and would be economical and readily controllable. It would also be flexible in the sense that it could be modified to accommodate a variety of precursor materials to be processed into $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$.


The process (see figure) would begin with mixing of oxides of yttrium, barium, and copper with water to form a slurry, followed by drying of the slurry, followed by calcining in a rotating kiln to obtain a stoichiometric precursor powder oxide,

$\text{YBa}_2\text{Cu}_3\text{O}_7$. The precursor powder would then be cooled, stored, and inspected for quality. A dry oxygen atmosphere would be provided during calcining, cooling, storage, and inspection to protect the precursor powder from water and other atmospheric contaminants.

In the next few steps, a thin metal foil would be unspooled and formed into a V-channel, into which the precursor powder would be metered. The foil is required to be permeable by oxygen at the high temperature (850 to 950°C) to which the cable would subsequently be exposed (to activate the superconductivity as explained below), but to be impervious to oxygen and other environmental contaminants at lower temperatures at which the cable would be used. Vanadium has been tentatively selected

as the foil material because it exhibits the desired permeability-versus-temperature characteristic, plus a favorable thermal-expansion characteristic. Niobium and tantalum may be suitable alternatives as foil materials. The foil would be continuously folded over and welded to seal the powder inside. The filling, folding, sealing, and most of the following operations would be performed in a vacuum to prevent trapping of gaseous oxygen in the cable. The cable would then undergo several steps of consolidation by rolling and heating, and the heating in these steps would also constitute preheating for the following activation step.

Activation of superconductivity would involve a controlled combination of (1) heating the precursor stoichiometric



A Cable Containing Superconducting Ceramic sheathed in metal would be drawn in a continuous process. The ceramic would be converted to a high-temperature superconductor after it had been encapsulated in metal foil.



COMPLEX HEATING

SPECIFICATIONS

WELCOME.

(ACCEPTING NEW APPLICATIONS ON A DAILY BASIS.)

When you're in need of a heat solution, select the supplier who can help make your product more competitive or your manufacturing process easier. Call Watlow.

Whatever the complexity of your application, Watlow can be your single source supplier for both development and integration of heaters, sensors, and controllers. We've increased heater reliability in a military satellite, reduced component size for a soldering iron used in fiber optic cable splicing and added multi-loop

intelligence in circuit board manufacturing. We'll work to meet your design considerations, too.



Get Our New Guide to Selecting the Best Source for Your Heat Solution.

Want proof? We've detailed our solutions to some of our most complex and demanding customer requirements. Call 314-878-7820, ext. 2326, or fax us at 314-878-2369 for your free copy.

 **WATLOW**

YBa₂Cu₃O₇ powder to the activation temperature and (2) removing a small amount of oxygen to obtain the desired superconducting ceramic that is slightly substoichiometric in oxygen; namely, YBa₂Cu₃O_{7- α} (where α represents the deviation from stoichiometry). For this purpose, the cable would be pulled through a bath of molten lithium at the upper activation temperature of 950 °C. The affinity of lithium for oxygen would create a thermodynamic gradient of oxygen activity across the encapsulating foil, causing

oxygen to diffuse out of the cable. Liquid sodium or liquid potassium might be used instead of liquid lithium, but their vapor pressures are higher — a disadvantage in the vacuum environment. The speed of the cable through the activation bath could be adjusted to adjust the immersion time and thus the amount of oxygen removed.

After emerging from the activation bath, the activated cable would be slowly cooled to room temperature, then brought out of the vacuum, then optional-

ly clad with copper, which would provide additional support and protection and would serve, along with the foil, as an alternative path for current if the superconductor should fail. Finally, the cable would be wound on a spool for shipment.

This work was done by Christopher England of Caltech for NASA's Jet Propulsion Laboratory. For further information, write in 43 on the TSP Request Card. NPO-19196

Compressor Case Made With Filaments Wound With V-CAP Resin

Weights and costs could be reduced.

Lewis Research Center, Cleveland, Ohio


A laminated cylindrical composite-material compressor case has been fabricated in a process that includes winding of filaments wetted with matrix resins. This case is a prototype of lightweight composite compressor cases that are required to withstand internal temperatures as high as 700 °F (371 °C). These composite cases are candidates for replacing titanium compressor cases in high-temperature turbines: it has been estimated that in comparison with titanium compressor cases, the composite compressor cases could weigh about 30 percent less and cost about 10 percent less.

The figure shows the prototype case as a workpiece at various stages of fabrication. The case includes a two-layer inner skin, which was formed by winding filaments wetted with VCAP-75 polyimide resin onto a cylindrical mandrel. The filaments in the innermost layer were made of glass and were wound in a hoop configuration; the filaments in the adjacent layer were made of graphite and were wound in three sublayers in hoop, helical, and hoop configurations, respectively. The layers and sublayers were cured by heating, along with a combination of externally applied pressure and internal vacuum to remove bubbles.

The cured inner skin was trimmed to length and removed from the mandrel, at which point it was in the form of a thin-walled, self-supporting cylinder. Its outer surface was grit-blasted to roughen it to enhance adhesion of the following layers. Premolded closure rings made of phenolic resin, chopped glass, and microballoon filler were installed on the ends of the cylindrical inner skin and bonded in place by use

of a high-temperature adhesive in bonding grooves. Next, a film adhesive was installed on all bonding surfaces and a premachined aromatic polyamide honeycomb layer was laid up onto the cylindrical inner skin. The honeycomb core was wrapped with shrink tape and the film adhesive was then cured.

The workpiece was reinstalled on the mandrel, more film adhesive was applied, and an outer layer of graphite filaments wetted with a high-temperature epoxy was wound onto the outer surface of the honeycomb core in sublayers with hoop and helical configurations. The epoxy was then cured, then the work-



The **Composite Compressor Case** is fabricated in stages that include winding of filaments wetted with matrix resins, adhesive bonding, layup, and several intermediate curing steps.

piece was trimmed to length and removed from the mandrel in its final form.

This work was done by Raymond Vannucci and James Sutter of **Lewis Research Center**; W. Donald Humphrey, A. John Ayorinde, and Jeremy Eaton of Brunswick Composites, Inc. (Lincoln Composites); Ted Westerman of Allied Signal Engines; and Ron Allred of Adherent Technologies. No further documentation is available. LEW-15990

Brazing Dissimilar Metals

Metals with widely different coefficients of thermal expansion can be joined.

Marshall Space Flight Center, Alabama

Brazing has been found to be an effective technique for joining ordinary structural metals to brittle, low-thermal-expansion refractory metals. Specifically, a brazing process has been established for (a) joining copper or nickel flanges to the ends of vacuum-plasma-sprayed tungsten tubes and for (b) joining stainless-steel flanges to the ends of tubes made of an alloy of molybdenum with 40 percent of rhenium.

In the original application, the tubes were furnace-cartridge tubes 23.5 in. (59.7 cm) long and 1 in. (25.4 mm) in diameter, with wall thickness of 0.030 in. (0.76 mm). The tubes were of test-tube configuration and the flanges were joined to the open ends.

In preparation for brazing, the tubes were cleaned of surface contaminants by placing them in a hydrogen furnace in the temperature range of 2,000 to 2,100 °F (approximately 1,100 to 1,150 °C) for 15 minutes. That area on each tube that was to be joined to a flange was then pre- "tinned" by wrapping the area with a thin brazing foil and heating it to the melting temperature.

After pretinning, each flange was machined to provide a braze-joint gap of 0.003 to 0.004 in. (0.076 to 0.10 mm). Each tube was then put together with its flange, and a small amount of brazing alloy was placed at the opening of the braze joint to provide sufficient material to fill the gap. A braze-stop-off solution was applied to the surfaces surrounding the joint to prevent the brazing alloy from flowing onto these surfaces and thereby make it unnecessary to perform a post-braze cleanup. The tubes were then brazed, variously, in an inert or vacuum

Engineered for Your Environment

E^E Engineering Environments™ – An innovative furniture system designed to optimize your technical work environment.

- Increases productivity by organizing equipment for instant access
- Unmatched strength and stability support the heaviest instrumentation
- Superior cable management • Countless configuration choices
- Integrated ESD controls for sensitive environments • Lifetime Warranty

For **NEW Color Brochure**: Call 800-225-7348 or 508-852-4300. FAX 508-853-8904.



W R I G H T • L I N E technical furniture solutions

For More Information Write In No. 434

Interface MINIBEAM LOAD CELLS

The Choice in Low Capacity Force Measurement



- Capacities from 5 lbs.
- Very Low Creep
- High Performance

PRECISION MEDICAL & INDUSTRIAL
LOW CAPACITY WEIGHING

Interface
ADVANCED FORCE MEASUREMENT

7401 E. Butherus Dr. • Scottsdale, Arizona 85260 USA • (602) 948-5555 • FAX (602) 948-1924

The world's broadest line of thermal sensing and control products.



Solid-state temperature sensors.

Precision thermostats.

Commercial thermostats.

Thermal cutoffs.

Flexible heaters.

When it comes to temperature sensing and temperature influencing, absolutely no one can offer you as complete a system as Elmwood Sensors. Worldwide capabilities. Local service. Custom engineering solutions.

No matter what you need, or when you need it, we can help you. Please call 1-800-ELMWOOD for more information.

ISO 9001 CERTIFIED



Thermal Sensing and Control Technology...Worldwide

500 Narragansett Park Drive • Pawtucket, RI 02861-4325, U.S.A. • Tel: 401-727-1300 • Fax: 401-728-5390

For More Information Write In No. 425

environment in the vertical orientation with the flanges at the lower ends.

This work was done by Phillip D. Krotz, William M. Davis, and Daniel L. Wisner of Rockwell International Corp. for **Marshall Space Flight Center**. For further information, **write in 12** on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-30105.

Mathematical Model of Variable-Polarity Plasma Arc Welding

Marshall Space Flight Center, Alabama

A mathematical model of the variable-polarity plasma arc (VPPA) welding process has been developed for use in predicting the characteristics of welds and thus serving as a guide for the selection of process parameters. These parameters include the welding electric currents in, and the durations of, straight and reverse polarities; the rates of flow of plasma and shielding gases; and the sizes and relative positions of the welding electrode, the welding orifice, and the workpiece. The model includes sub-models that approximate the time-dependent major electrical, thermal, radiative, and mechanical phenomena involved in the transfer of energy through the electrode and gases to the workpiece and environment. The model predicts (1) electric potentials (in both straight and reversed polarities) at key locations; (2) electric power input at the electrode, within the orifice, in the free plasma jet column, and in the weld key-hole in the workpiece; (3) power loss at the electrode, within the orifice but outside the electrode, in the standoff column, and in the workpiece; (4) enthalpy of the plasma arc; and (5) widths and heights of the crown and root of the weld bead. In a study, predictions by this model were found to agree fairly well with data on both normal and abnormal experimental welds.

This work was done by R. J. Hung of the University of Alabama in Huntsville for **Marshall Space Flight Center**. For further information, **write in 57** on the TSP Request Card. MFS-26311

1st North American Aluminum Extruder to Achieve ISO 9002 Certification.



Since 1950, General Extrusions, Inc. has directed its efforts toward the design and production of quality fabricated and finished aluminum extrusions. Our complete in-house services include:

EXTRUSION

Custom designs to meet your quality and precision tolerance requirements.

FABRICATION

Fabrication, forming and machining processes performed on CNC machining centers and/or with dedicated tooling.

FINISHING

- Buffing
- Brushing
- Sanding
- Silk Screening
- Powder Coating
- Anodizing (Clear & Colors)

ASSEMBLY

Subassembly manufacturing including welding, bonding and fastening component parts.

Call today for your Free design guide.

General Extrusions, Inc. • P.O. Box 2669 • Youngstown, OH 44507 • Ph: (216)783-0270 • Fax: (216)788-1250

For More Information Write In No. 439

Connector Cleaner Plus

It's a Miller-Stephenson and Monsanto perfect match!

brings you state of the art total Connector treatment

Cleans, Protects and Extends Connector Life!

By combining the superior lubricating qualities of Monsanto's Polyphenyl Ether (PPE) with the dynamic cleaning power of our solvents, Miller-Stephenson has created Connector Cleaner Plus; a product line that provides the most advanced total treatment for connectors. Advantages:

- Cleans, lubricates and protects multi-pin connectors.
- Reduces insertion forces.
- Greatly increases mating cycles, (especially important where high pin counts are involved).
- Extends connector life by preventing corrosion and galling.
- Removes contaminants and oxides.
- Forms no residue, even at high temperatures.
- Is non-migrating - contains no silicones.
- Nonflammable.
- Available with a UV indicator.
- No interference in electrical continuity.
- NSN 6810-01-367-8095 (Aerosol)

TECHNICAL SUPPORT: 1-800-992-2424 (8-4 Eastern Time).
IN CANADA 1-800-323-4621 (8-4 Eastern Time).



millier-stephenson chemical company, inc.

CALIFORNIA
12261 Foothill Boulevard
Sylmar, California 91342
818 896-4714

CONNECTICUT
George Washington Highway
Danbury, Connecticut 06810
203 743-4447

ILLINOIS
6348 Oakton Street
Morton Grove, Illinois 60053
708 966-2022

CANADA
514 Carlingview Drive
Rexdale, Ontario M9W 5R3
416 675-3204

COMPLETE COUPON BELOW

PLEASE
SEND



AEROSOL
☐ SAMPLE
16oz.



BULK
☐ SAMPLE
8oz. 183N

Enclose \$10.00 for each sample. Mail to:

millier-stephenson chemical co., inc.
George Washington Highway
Danbury, Connecticut 06810 U.S.A.

INTENDED USE _____

NAME _____

DEPT/TITLE _____

COMPANY _____

ADDRESS _____

NTB/3Q

For More Information Write In No. 429

Electrical-Discharge Machining of Perpendicular Passages

A perpendicular telescoping electrode reaches into previously inaccessible places.


Marshall Space Flight Center, Alabama

A perpendicular telescoping electrode is used to perform electrical-discharge machining (EDM) of an internal passage through the previously inaccessible depth of a metal workpiece. More specifically, it is used to make an internal passage perpendicular to a passage that enters from the outer surface. Heretofore, the only way to make such a perpendicular internal passage was to make an access hole, then machine through the depth of material to form the passage, then restore the overlying material by welding a plug or other appropriately dimensioned piece of metal over the access hole.

The telescoping electrode is mounted on the lower end of an EDM electrode holder that is lowered into the passage from the surface (see figure). The telescoping electrode consists of an electrode disk supported on the narrowest one of a series of progressively narrower thin-walled copper sleeves. Attached to the smallest sleeve is an electrode disk

the same diameter as the largest sleeve. The disk is the actual burning area. The sleeves are assembled concentrically

and are compressed axially before lowering the electrode into the passage from the surface.



The **Telescoping Electrode** is extended into the perpendicular passage by the pressure exerted by the flowing dielectric oil.

The telescoping electrode is positioned at the depth of the perpendicular passage to be machined and its axis is aligned with the axis of the perpendicular passage. The electrode holder is hollow and is used as a manifold to supply dielectric oil to the electrode. The pressure exerted by the oil flowing through the electrode pushes the sleeves out-

ward, thus extending the electrode so that the burning surface of the electrode disk follows the retreating end face of the passage. After the EDM is complete, the electrode can be retracted by use of a vacuum or compressed air.

This work was done by R. Michael Malinzak and Gary N. Booth of Rockwell International Corp. for **Marshall Space**

Flight Center. For further information, write in 55 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-30027.

Verifying Removal of Red Penetrant Dye From Inspected Welds

A clean surface is assured for more sensitive inspection with fluorescent penetrant dye.

Marshall Space Flight Center, Alabama

A simple procedure has been devised to ensure that visible (red) penetrant dye that has been used to identify flaws in a welded surface has been completely removed from the surface. It is necessary to ensure complete removal because any residual red dye could interfere with a subsequent inspection in which ultraviolet illumination and a fluorescent penetrant dye are used to identify smaller defects.

The procedure consists in applying a reversible penetrant developer to the surface to be inspected. The developer contains a fluorescent dye that reacts with, and thus is eliminated by, the red penetrant dye. Therefore, when the surface is viewed under ultraviolet illumination, the residual spots of red penetrant dye stand out as dark spots against a fluorescent background. Once the removal of red penetrant dye has been

completed and verified by this procedure, the developer is removed from the surface by rinsing with water.

This work was done by Jan R. Torkelson of Rockwell International Corp. for **Marshall Space Flight Center.** For further information, write in 76 on the TSP Request Card. MFS-30001

Some prices must eventually obey the Law of Gravity.

VME + PC TIMING SOLUTIONS NOW UNDER \$1,000

VME Time & Frequency Processor bc336VME + PC Real Time Clock bc630AT — These modules decode time code at real-time rates and offer excellent performance characteristics for many demanding time code processing requirements.

PC Time Code Reader PC03XT — Always a strong performer, this PC module is ideal for reading time code from tape recorders at non-real-time rates, in forward & reverse directions.

Treat your budget to some down-to-earth prices from Datum!

Call us toll-free today!

800 348 0648



datum inc
BANCOMM DIVISION

THE M A S T E R S O F T I M E

6541 Via del Oro, San Jose, CA 95119 USA • Tel 408 578 4161 • Fax 408 578 4165

OUR LASER IS WELL KNOWN AROUND THESE PARTS.




Gasket Manufacturing



*Color Marking on
Anodized Aluminum*



Engraving Wood




Marking Microprocessors




Cutting Plexiglas



Cutting Paper




Wire Stripping



Textile Cutting



Cutting Wood



Marking Plastic



Cutting and Welding Plastic



Rubber Stamps

And the list doesn't stop here. The more manufacturers get to know our RF-excited, sealed CO₂ lasers, the more uses they keep finding for them.

This growing popularity makes sense when you consider how versatile and cost-efficient our lasers can be. All the parts shown here were marked or cut in seconds or less – in some cases while moving on high speed production lines.

No tooling is required. The laser's power and motion are controlled using a simple PC. Images, graphics, and text can be created in standard CAD or graphics software – delivering

greater process flexibility. Changing the pattern is as simple and quick as loading a new computer file.

Plus, the laser's small focused spot and non-contact approach eliminate the use of dies, blades, scribes or ink. So you can expect increased accuracy, resolution and process savings.

We offer models from 10 to 250 watts of power, allowing you to select the laser that matches your application and budget. And, as they all take advantage of our patented all-metal construction, you get over




20,000 hours continuous operation.

With no gas bottles or other consumables. That's why Synrad lasers cost less to buy and run than any other models.

If you don't recognize your application on this page, don't worry. Our biggest customers had never used a laser before talking to us.

To find out how lasers can take part in your application, call (800) SYNRAD1.



11816 North Creek Parkway N., Bothell, WA 98011-8205 (206) 483-6100 FAX (206) 485-4882 E-mail: synrad@aol.com

International Representatives

Australia 61 (376) 15200. Belgium 32 (71) 488-44-8. China 86 143-658-91. Denmark 45 (354) 30133. England 44 (1295) 267755. France 33 1-60.79.59.00. Germany 49 898-90-1350. Greece 30 312-045-50. Hungary 36 1-269-0105. Israel 972 9574111. Japan 81 (33) 758-1111. Netherlands 31 172-43-1234. Poland 48 224-318-02. Singapore 65 382-2633. Spain 34 1-35.88.61.1. Sweden 46 87-569-190. Turkey 90 2-122-63-2670.

For More Information Write In No. 520



Mathematics and Information Sciences

Modified Mean-Pyramid Coding Scheme

The data-expansion factor can be reduced from 1/3 to 1/12.

NASA's Jet Propulsion Laboratory, Pasadena, California


A modified mean-pyramid coding scheme requires the transmission of slightly fewer data than does the unmodified mean-pyramid coding scheme. These are schemes for the progressive transmission of image data. In progressive transmission (which should not be confused with "progressive scanning"), data on the entire image area are transmitted in a sequence of frames in such a way that a coarse version of the image can be reconstructed after the receipt of the first frame and an increasingly refined version of the image can be reconstructed after the receipt of each subsequent frame.

Progressive transmission offers an advantage when the time and/or the bandwidth available for transmission of image data is limited. When using a traditional line-by-line or raster scan, it is usually necessary to transmit the entire image before the user at the receiving end can recognize it. In progressive transmission, the user can view the increasingly refined approximate received images and make a decision as to whether it is worthwhile to continue refining the image or to devote the limited communication channel to another purpose — possibly the transmission of another image. In the mean-pyramid coding schemes, progressive transmission is combined with data-compression coding to decrease the bandwidth of the data signal, thereby further increasing the efficiency of utilization of the communication channel.

In the unmodified mean-pyramid coding scheme, the image data are represented by a hierarchical structure, which, in its simplest form, involves the construction of each succeeding higher and coarser layer by averaging over blocks of pixels (typically 2×2) in the layer immediately below it. The highest layer (which represents the average pixel intensity of the entire image) is transmitted first, followed by the differences between the highest and second highest layers, followed in turn by the differences between the third and second layers, and so forth. The differences between adjacent layers tend to be

smaller more often than they are larger and can, therefore, be encoded with fewer bits (that is, compressed). The receiver decodes the transmitted data and partly mimics the operation of the transmitter in reconstructing approximate images of successively finer resolution.

block from (a) the three other pixels in the block and (b) the mean pixel in the next higher layer. In the absence of any further correction, this technique of reconstruction could introduce a truncation error into the fourth pixel, inasmuch as the mean pixel is the trun-



A **Recognizable Image** is formed after fewer than 5 percent of the image data have been transmitted, and an image of fairly high quality can be reconstructed with fewer than 20 percent of the data.


The unmodified mean-pyramid scheme partly counteracts the effort to compress data in that it increases the number of data to be transmitted for each layer. In the case of an 8-bit gray-scale image of 512×512 pixels, the increase is by a factor of 1/3. The modification is directed toward reducing this expansion, and it involves the reconstruction of the fourth pixel in each

cated average of the 2×2 block.

The truncation error is either 0, 1, 2, or 3 levels and is quite evenly distributed. The needed correction is supplied by transmitting the error term, which can be coded with 2 bits instead of the full 8 bits. This correction and representation guarantees lossless transmission and reduces the data-expansion factor from 1/3 to 1/12. The modified mean-pyra-

MATRIX_X

The Leading Real-Time Simulation and Test Environment





RealSim AC-100 Model C40

- Fully integrated hardware/software environment
- Seamless support for up to four TI C40 DSPs
- Extensive I/O support (A/D, D/A, CAN,...)
- Open and expandable I/O
- Data acquisition capabilities
- Single vendor turn-key solution

The MATRIX_X Product Family from Integrated Systems has enhanced the **RealSim AC-100** product line with the **Model C40**. This newly designed, easy-to-use,

portable system has been ruggedized and tested for reliability in extreme temperature and vibration environments. Combining the power of this high-performance real-time processing system with the simplicity of the MATRIX_X icon-based graphical modeling/programming tools, the Model C40 provides the ideal solution for your real-time simulation and testing needs.



To dramatically shorten your development time, please call:


Integrated Systems, Inc.

800.770.3338 (U.S. and Canada only) or 408.980.1500

World Wide Web: <http://www.isi.com>



World's smallest position sensor



For the tightest installations, Kaman's 0.080-inch diameter sensor lets you resolve microscopic displacements down to 4 microinches at 50 kHz, without contact. Ideal for both magnetic and non-magnetic materials, this sensor is only one of Kaman's 24 standard sensors that let you see small changes in position. Call us today for information.

Kaman Instrumentation, 1500 Garden of the Gods Road
Colorado Springs, Colorado 80907
Voice 719-599-1132, Fax 719-599-1823
Internet: <http://www.kamansensors.com/kaman>

800-552-6267

KAMAN

For More Information Write In No. 428

Rotating Torque Sensors



The **01224** is a slip ring based, shaft to shaft rotating torque sensor. This family of sensors has full scale capacities ranging from 1 to 2000 in-lbs. A morse/jacob tapered shaft model is also available for direct installation in standard drill presses.

The **01225** is similar to the **01224**, but is equipped with male and female square socket ends for measurement of fastener torques. Square socket sizes from 1/4" to 1/2" as well as a 1/4" hex socket size are available.

Both models can include optional foot mounts, magnetic speed pickups, and/or pulse angle encoders.



For dynamometer and other torque measurement applications, SDI produces FM telemetry coupled sensors such as the model **01243** and infrared coupled sensors such as the model **01251**.

**Sensor
Developments Inc.**
800-997-3676

P.O. Box 290
Lake Orion, MI 48361-0290
WWW: <http://sendev.com>

mid coding scheme also incorporates a context-based arithmetic code that compresses the difference and error terms. The figure illustrates the sequence of reconstructed images obtained by applying the modified mean-pyramid coding scheme to an image of an oilfield.

This work was done by Kar-Ming Cheung and Richard Romer of Caltech for **NASA's Jet Propulsion Laboratory**. For further information, write in **21** on the TSP Request Card.
NPO-18890

Algorithm for a Self- Growing Neural Network


Either a crisp or a fuzzy measure on entropy can be used.

Lewis Research Center, Cleveland, Ohio

The CID3 algorithm simulates a self-growing neural network. It constructs decision trees equivalent to the hidden layers of the neural network (see figure). The algorithm is so named ("CID3" is short for Continuous ID3) because it is based on the ID3 algorithm, which dynamically generates a decision tree while minimizing the entropy of information. [The entropy of a piece of information, x , is given by $-p(x)\log_2 p(x)$, where $p(x)$ denotes the probability or frequency of occurrence of x .] The CID3 algorithm generates a feedforward neural network by use of either a crisp or a fuzzy measure of entropy.

A description of ID3 is prerequisite to a description of CID3. ID3 generates decision rules from a set of training examples. Each example is represented by a list of features. In the training process, classes to which the input data belong must be known. The idea is to find the minimum number of original features that suffice to determine these class memberships. ID3 uses information theory to select features that maximize the information gain in the sense that they maximize the decrease in entropy.

Inasmuch as the number of new nodes added to a decision tree depends on the number of values that a selected feature can take on, the ID3 algorithm requires features to have discrete values. The decision tree thus generated is then described in terms of hierarchical decision rules that must be



A **Three-Node Hidden Layer** of a neural network is generated from a decision tree, in the CID3 algorithm, by use of mathematical constructs called "adaptive linear neurons."

used in the order specified by the tree structure. The condition part of a decision rule consists of a number of feature tests linked by AND/OR logical operators. The disadvantage of a feature test is that correlations between features are ignored. ID3 considers only the degree to which each individual feature is significant for classification of training examples.

In the formulation of CID3, ID3 was modified to operate on continuous data and to search for weight vectors that minimize an entropy measure. This measure can be based on either the crisp entropy (the conventional information entropy defined above) or a fuzzy entropy. The fuzzy entropy measure is a modified entropy, derived from fuzzy-logic theory, that accounts for degrees or probabilities of membership in various classes.

The CID3 algorithm comprises the following major steps:

1. For a given problem with N training examples, start with a random initial weight vector, W_0 .
2. Using a learning-rule equation, a description of which would greatly exceed the space available for this article, search for a hyperplane in weight-vector space that minimizes the applicable crisp or fuzzy entropy function at a given level of the decision tree or layer of the neural network.
3. If the minimized entropy is not zero, but is smaller than the previous value, add a node to the current layer of the neural network and return to step 2. Otherwise, go to step 4.
4. If the hidden layer consists of more than one node, generate a new layer that utilizes inputs from both the original training data and the outputs from all previously generalized layers, and go to step 2. If the hidden layer consists of only one node, then the problem is reduced to a linearly separable one; stop.

This work was done by Krzysztof J. Cios of the University of Toledo for **Lewis Research Center**. For further information, write in 78 on the TSP Request Card. LEW-15931

Software for Multivariate Bayesian Classification

This program can be embedded in another program or run by itself.

*Ames Research Center,
Moffett Field, California*

PHD is a general-purpose classifier computer program. Originally part of another program, PHD has been extracted and made available for wider use.

"Classifier" in this context denotes a program that accepts data in the form of vectors and assigns a class label to each vector. Typically, a classifier is trained to recognize a set of classes by (a) presenting it with training data in the form of a set of vectors to which the correct labels have been attached, then (b) running a "learning" procedure to characterize the classes. Thereafter, when presented with new, unlabeled vectors, the classifier is required to determine the class to which each vector most likely belongs, along with a measure of confidence in the correctness of the classification of each vector.

PHD was constructed according to the concept of Bayesian inference, a mathematically optimal family of algorithms for classification that has long been a fundamental technique for classification of patterns. PHD uses Bayesian methods to classify vectors of real numbers, based on a combination of statistical techniques that include multivariate den-

Hard-to-find Positioning Slide Assemblies

Over 945 different Models
to choose from

Linear Slides
Rotary Tables
X—Y Tables

Widths: 1½" to 9"
Lengths: 2" to 90"

Single or
OEM Quantities

Compact
Durable
Economical

Get to your
Point!

Get your **FREE**
36 page
Catalog **G**
today!




UNISLIDE ASSEMBLIES

VELMEX INC.

800 642-6446
FAX: 716 657-6153
In NYS: 716 657-6151
POB 38, Bloomfield, N.Y. 14443

For More Information Write In No. 401



**AMERICAN
VARISEAL**

High Pressure Seals

*True reliability makes
all the difference...*

- Low friction, chemically inert Turcon®
- Temperatures to 575°F
- Pressures to 30,000 psi

When high pressure, high temperature, harsh chemicals and other severe conditions combine, the high-performance Variseal™ M is the best solution. Made from Turcon® polymers and energized by a corrosion-resistant metal spring, Variseal M provides the extra measure of performance and reliability needed for high-pressure valves and other applications. Call for product literature and technical support. Fax: 303-469-4874
1-800-466-1727

A Member of **Busak + Shamban**

See us at IFPE, Busak + Shamban
Booth #622

For More Information Write In No. 418

Digital Quartz Crystal Pressure Instrumentation



0.01% Accuracy

Digiquartz®

Transducers	Barometers
Transmitters	Manometers
Lab Standards	Depth Sensors

Multiple pressure ranges with one part-per-million resolution to meet your needs in

Hydrology
Aerospace
Meteorology
Oceanography
Process Control
Energy Exploration
Laboratory Instrumentation
ISO 9001



For application / engineering support-call:

Paroscientific, Inc.

4500 148th Avenue N.E. Tel: (206) 883-8700
Redmond, WA 98052 Fax: (206) 867-5407

sity estimation, Parzen density kernels, and the EM (Expectation Maximization) algorithm. By means of a simple graphical interface, the user can train the classifier to recognize two or more classes of data and then use it to identify new data.

The classifier is trained to create a statistical model, known as a "mixture density," for each of several classes of training data. During training, in order to model the training data for a given class, the program searches for a maximum-likelihood (best-fitting) density estimate constructed of one or more multivariate Gaussian kernels. Overfitting (failing to distinguish low-probability noise from higher probability data) is avoided by applying a minimum-description-length criterion to determine how many Gaussian kernels are justifiable in representing the training data. Whereas traditional pattern classification applies a discriminant function to distinguish each class from the others, PHD models each class separately. Thus, outliers that do not belong to any of the known classes can usually be spotted and labeled as "unidentified."

After finding densities for each of the training classes, PHD is ready to assign a class to an unlabeled vector by finding the highest likelihood for that vector from among the known class distributions. If the vector does not belong to any of the training classes, that fact will be reflected in the low confidence measure of its classification; thus, PHD is useful in a task that requires recognition of data that do not fit in any of the known classes.

PHD is written in ANSI C for Unix systems and is optimized for online classification applications. It can be embedded in another program, or it can run by itself using the simple graphical-user-interface. Online help files make the program easy to use.

This work was done by Ronald Saul and Philip Laird of Ames Research Center and Robert Shelton of Johnson Space Center. For further information, write in 60 on the TSP Request Card.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Ames Research Center; (415) 604-5104. Refer to ARC-13383.

Fast Parallel Computation of Multibody Dynamics

Processors and computation time are utilized efficiently.

NASA's Jet Propulsion Laboratory,
Pasadena, California

The constraint-force algorithm is a fast, efficient, parallel-computation algorithm for solving the forward dynamics problem (given the control forces, compute the motions) of a multibody system like a robot arm or a vehicle. This is the first known algorithm to solve the problem in a minimum time proportional to $\log(N)$ by use of an optimal number of processors proportional to N , where N is the number of dynamical degrees of freedom: in this sense, the constraint-force algorithm is both a time-optimal and a processor-optimal parallel-processing algorithm.

Fast algorithms and computers have been sought for use in telerobotic and other control systems. In many of these systems, there is a need for faster-than-real-time simulation of multibody

dynamics. Fast serial algorithms with processing times proportional to N have been developed, but even the fastest serial algorithm does not exhibit the requisite computational efficiency, and further improvements in the efficiencies of serial algorithms seem unlikely.

Heretofore, in the development of a typical parallel-processing algorithm, it has been customary to first develop an algorithm for fast serial computation, then attempt to increase the computational efficiency through parallelization. A different approach was followed in the case of the constraint-force algorithm: From the outset, it was developed for efficient parallel computation.

The complexity of the underlying mathematics precludes a detailed description of the algorithm in this article. From the perspective of physics, a given algorithm for multibody dynamics can be classified on the basis of, and can be considered to originate from, its force-decomposition strategy. From the perspective of mathematics, the algorithm can be classified on the basis of that factorization of the mass matrix of the dynamical system that corresponds to the specific force-decomposition strategy. The constraint-force algorithm is accordingly so named because it is

putation. In addition to its theoretical significance, this algorithm is highly practical and can be efficiently implemented on a variety of commercially available computers that feature multiple-instruction/multiple-data parallel architectures. In a test, the constraint-force algorithm was successfully implemented on a 32-node hypercube computer in which each node contains an 80386 microprocessor, an 80387 arithmetic coprocessor, and 4 MB of random-access memory. The performances of several different versions of the algorithm (a serial version and parallel versions with three different levels of

parallelism) were compared with respect to an $N = 8$ test case (see table). The results of the test confirmed expectations that the constraint-force algorithm exhibits a high degree of parallelism in computation with minimum communication and synchronization requirements.

This work was done by Amir Fijany of Caltech and Gregory L. Kwan and Nader Bagherzadeh of the University of California at Irvine for NASA's Jet Propulsion Laboratory. For further information, write in 31 on the TSP Request Card. NPO-19340

Version	Time (in ms)	Speed	
		Absolute	Relative
Serial	481	1.00	-
N-Parallel	87	5.53	5.53
2N-Parallel	69	6.97	1.26
3N-Parallel	55	8.75	1.25

Significant Speedups Were Achieved in a test computation by use of three different parallel versions of the constraint-force algorithm.

based on a novel decomposition of interbody forces that leads to an explicit computation of constraint forces.

Researchers had previously often argued that because constraint forces are nonworking forces, one should avoid calculating them for the sake of computational efficiency. Although this argument is valid for serial computation, it does not necessarily apply to parallel computation. In this case, the force-decomposition strategy leads to a new factorization of the mass matrix and this factorization, in turn, results in the efficient constraint-force algorithm.

A salient feature of the constraint-force algorithm is that while it is less efficient than other algorithms for serial computation, it is strictly efficient for parallel com-

Imagine the possibilities.



See us at NDES
Booth #1437

How can you tell if an elephant's been sitting on your chaise lounge? If it was made with 3M™ Continuous Ceramic Fiber Aluminum Matrix Composites (CF-AMCs), you probably couldn't.

That's because 3M CF-AMCs are not your average AMC. They consist of a high-strength ceramic fiber in an aluminum matrix—providing the strength of better steels at nearly half the weight, with stiffness and fatigue properties that particulate-reinforced AMCs just can't reach.



When you include pure aluminum or aluminum with a small amount of copper, 3M CF-AMCs can match or even outperform PMCs in many applications.

Just think of the weight critical, high-performance applications you could use them in. Of course, the possibilities are endless. All you have to do is let your imagination run wild. For more information, call 1-800-440-2966, ext. 10 or write to 3M MMC, Building 60-1N-01, St. Paul, MN 55144.



Books & Reports

These reports, studies, and handbooks are available from NASA as Technical Support Packages (TSPs) when a Request Card number is cited; otherwise they are available from the NASA Center for Aerospace Information.



Physical Sciences

Thermal Conductance of Gold Contacts at Liquid-Helium Temperatures

A report describes a study of the thermal conductance of gold-plated copper, aluminum, brass, and stainless-steel contacts at temperatures from 1.6 to 4.2 K under applied forces of 22 to 670 N. It was found that the thermal conductance improved greatly as the result of gold-plating, except for the stainless-steel samples.

This work was done by Peter Kittel and Louis J. Salerno of **Ames Research Center** and Alan L. Spivak of **Trans-Bay Electronics**. To obtain a copy of the report, "Thermal Conductance

of Gold-Plated Metallic Contacts At Liquid Helium Temperatures," **write in 23 on the TSP Request Card**.

Inquiries concerning rights for the commercial use of this invention should be addressed to the Patent Counsel, Ames Research Center; (415) 604-5104. Refer to ARC-13178.

Basis and Application of the CARES/LIFE Computer Program

A report discusses the physical and mathematical basis of the Ceramics Analysis and Reliability Evaluation of Structures LIFE prediction (CARES/LIFE) computer program, which was described in "Program for Evaluation of Reliability of Ceramic Parts" (LEW-16018) elsewhere in this issue. As explained in more detail in that article and

in the report, this software calculates the time-dependent reliability (probability of failure as a function of time in service) of a monolithic ceramic component subjected to thermomechanical and/or proof-test loading. The report explains the basic equations implemented in CARES/LIFE to mathematically model the various phenomena involved in the failures of ceramic components: CARES/LIFE accounts for subcritical crack growth by use of a power law, the Paris law, or the Walker equation.

This work was done by Noel N. Nemeth, Lesley A. Janosik, and John P. Gyekenyesi of **Lewis Research Center** and Lynn M. Powers of **Cleveland State University**. To obtain a copy of the report, "Durability Evaluation of Ceramic Components Using CARES/LIFE," **write in 48 on the TSP Request Card**. LEW-16207

ELGILOY®

EXPANDING NEW HORIZONS

In addition to Elgiloy, we also process

- Over 60 nickel-based alloys
- Wire: Gauges from 1.250 inch to .005 inch annealed
Gauges from .800 inch to .005 inch tempered
- Strip: Gauges from .135 inch to .0015 inch
Widths up to 13 inches



Elgiloy® • Haynes® • Hastelloy® • Inconel® • Monel® • MP35N

*Haynes and Hastelloy are registered trademarks of Haynes International. Inconel and Monel are registered trademarks of Inco Alloys International. MP35N is a trademark of SPS Technologies.

Our state of the art facility is ISO 9002 registered and operates under Pratt & Whitney LCS, G.E., and NADCAP certifications.

- Resists Stress & Cracking
- High Strength
- Performs Consistently in Temperatures Ranging From -300° F to 850° F
- Non-Magnetic
- Corrosion Resistant
- Excellent Fatigue Life

Elgiloy® is extremely resistant to:

- Hydrogen Sulfide • Chlorides
- Marine Environments



Elgiloy® Limited Partnership

1565 Fleetwood Dr., Elgin, IL 60123
Ph. 708/695-1900 Fax: 708/695-0169



Mechanics

Non-Newtonian Effects in Viscous Flows

A report presents a theoretical study that addresses the persistent problem of explaining the random aspects of the flows of real fluids in terms of the classical governing equations. A review of the classical mathematical formalism of fluid dynamics leads to the conclusion that some of the physically unrealistic aspects of classically computed flows (for example, infinite times of approaching equilibria, and fully deterministic solutions of the Navier-Stokes equations) can be removed by relaxing the Lipschitz condition, which is a requirement that the derivatives of the solutions of the differential equations of flow be bounded. (The Lipschitz condition guarantees the uniqueness of the solution under fixed initial conditions, whereas what is sought here is the non-uniqueness characteristic of real, partly random flows.)

This work was done by Michail Zak of Caltech and Ronald E. Meyers of the U. S. Army Research Laboratory for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "Non-Newtonian Effects in Viscous Flows," write in 22 on the TSP Request Card. NPO-19728

Theory of Controlling Spacecraft Motion With Pulsed Thrusters

A report presents a new class of flight-control laws for making a spacecraft follow a desired trajectory by use of pulsed thrusters during such maneuvers as automated rendezvous on orbit and soft landing on a planet. The guidance problem is solved with an extension of robust nonlinear control theory, resulting in algorithms that determine the duration and frequency of thruster firings from estimates of spacecraft position and velocity. These algorithms incorporate a complete nonlinear dynamical model of the spacecraft motion, and enable analytical characterization of transient-error behavior, limit-cycle dead-band region, and the domain of possible terminal states. Although the emphasis in the report is on guidance, it is ultimately shown that the same techniques are also useful for attitude control and station keeping. A realistic application is illustrated via computer simulation of a soft landing, on Mars, of a

robotic spacecraft equipped with an inertial-guidance system.

This work was done by Sam W. Thurman of Caltech and Henryk Flashner of the University of Southern California for NASA's Jet Propulsion Laboratory. To obtain a copy of the report, "A New Pulse-Modulation Technique for Guidance and Control of Automated Spacecraft," write in 20 on the TSP Request Card. NPO-19695



Machinery/Automation

Experimental Study of Rotating Unbalanced-Mass Actuators


A report discusses the theory of rotating unbalanced-mass (RUM) actuators and describes experiments to test the concept of using RUM actuators for mechanical scanning of scientific instruments in linear, circular, or raster patterns. This concept and some aspects of the design and operation of RUM actuators have been described in several previous articles in NASA Tech Briefs.

Previous calculations had shown that scanning by use of RUM actuators should consume significantly less power than does scanning by use of gimbal actuators in both gravitational and nongravitational environments. The results of these experiments were found to be in fair agreement with data from simplified computer simulations of the experiments. The results verify expectation of reduced power consumption; depending on the particular test configuration, the power needed to scan with gimbal actuators ranged from 17 to 494 times that needed to scan with RUM actuators.

This work was done by Dean C. Alhorn and Michael E. Polites of Marshall Space Flight Center. To obtain a copy of the report, "Results of a Laboratory Experiment That Tests Rotating Unbalanced-Mass Devices for Scanning Gimballed Payloads and Free-Flying Spacecraft," write in 61 on the TSP Request Card.

This invention is owned by NASA, and a patent application has been filed. Inquiries concerning nonexclusive or exclusive license for its commercial development should be addressed to the Patent Counsel, Marshall Space Flight Center; (205) 544-0021. Refer to MFS-28994.

Your Best Guide To Engineering Tools Online



The Internet For Scientists And Engineers will show you how to navigate the net and find important online resources in aerospace, electronics, energy, computing, bio/medicine, physics, and many other fields. A great time- and cost-saver for both beginners and seasoned surfers. 450 pages.

Only \$34.95

Rush me ___ copies of *The Internet For Scientists And Engineers* at \$34.95 each plus \$5.00 postage.

(NY residents add sales tax to total.)

☐ Check enclosed (payable to Associated Business Publications)

Bill me:

☐ VISA

☐ MasterCard

☐ AmEx

Account No. _____

Expire Date _____

Signature _____

Name _____

Company _____


Address _____

City/St/Zip _____

Phone No. _____

Mail (in envelope) to: Assoc. Business Publications, Dept. F,
317 Madison Ave., Suite 921, New York, NY 10017.

Or fax to: (212) 986-7864.




You are connecting at a HIGHER level with AMP Incorporated, a global leader in connectors, connector intensive assemblies, and complete interconnection systems.

Examine our product line in detail at <http://www.amp.com>

Visit **NASA Tech Briefs** on-line at <http://www.keds.com/ntb>

- search 20+ years of tech briefs for new product ideas and engineering solutions
- renew your subscription electronically in seconds
- find NASA resources nationwide that can help with your specific needs; links to all NASA field centers and headquarters
- discover new products and services from *NASA Tech Briefs* advertisers

Hosted by Knowledge Express Data Systems.



FOR EXTRUDED SEALS, GASKETS AND WEATHER STRIPPING

Visit Lauren Manufacturing at IndustryNet. You'll find information on:

- A complete company profile
- Our sponge and solid polymer extrusion and molding capabilities
- Seals and gaskets with Pressure Sensitive Adhesives
- And, much more...



Ask for our new brochure and capabilities video.

Lauren Manufacturing:
www.industry.net/lauren

E-mail: htyp17a@prodigy.com
800-683-0676 • Fax 330-339-7166







For Information on Finite Element Design and Analysis



Stop by Our Place

WWW.ALGOR.COM

Algor's Internet place is the fastest way to find out about:

-  Houdini: CAD/FEA Integration with 8-node "Bricks"
-  Finite Element Design and Analysis Software
-  Plant and Piping System Design and Analysis Software
-  Multimedia Products for Engineers (books, videos, etc.)
-  Speed-Mesh: CAD to 8-node "Brick" Modeling Service
-  Algor Education Seminars

E-mail: info@algor.com

New Literature

Fittings • Tubing & Valves

**COLE-PARMER
INSTRUMENT
COMPANY**

CALL TOLL FREE
(800)
323-4740

A 70-page handbook of **fittings, tubing, and valves** is available from Cole-Parmer Instrument, Vernon Hills, IL. New products include polycarbonate and polysulfone quick-disconnect fittings and platinum-cured silicone tubing.

For More Information Write In No. 740

Materials for **noise, vibration, shock, and motion control** are described in a product guide from E-A-R Specialty Composites, Indianapolis, IN. Featured are absorbing foams, barrier composites, isolation materials, grommets, and mounts.

For More Information Write In No. 741



National Instruments, Austin, TX, has released its 1996 catalog of **computer-based instrumentation products**, including software and hardware for test, measurement, and industrial communication. The 624-page catalog features sections on data acquisition and industrial automation.

For More Information Write In No. 742

A 12-page brochure of **miniature and sub-miniature position transducers** is available from SpaceAge Control, Palmdale, CA. The transducers are used in the automotive, aerospace, and automation fields for test and development, industrial control, and OEM applications.

For More Information Write In No. 743

Axon Instruments, Foster City, CA, has released a 180-page 1996 product catalog of **scientific instruments**, including data acquisition and analysis hardware and software, microelectrode amplifiers, cellular imaging products, and simulation software.


For More Information Write In No. 744

Molded and stamped rubber products are described in a 20-page brochure from Syntex Rubber Corp., Bridgeport, CT. Included are grommets, O-rings, rubber tips, shock mounts, stoppers, suction cups, bumpers, and capacitor boots.

For More Information Write In No. 745


Hamilton Precision Metals, Lancaster, PA, offers a 24-page technical brochure describing precision tolerance **metal alloy strip and foil**, which is available in thicknesses from 0.050" to 0.00060", and widths to 15". Applications include medical instrumentation, computers, electronics, and automotive.

For More Information Write In No. 746



A six-page brochure from Emerson Electronic Motion Controls, Chanhassen, MN, describes **motion control devices**, including brushless positioning servo drives, digital and analog servo drives, and multi-axis controllers. Related system software also is featured.

For More Information Write In No. 747



Interpoint Corp., Redmond, WA, has released a product guide describing 35 new **DC/DC power conversion products** for industrial, commercial, and military applications. The new VP Series features output power ranges from 6 to 45 watts in single, dual, and triple output configurations.

For More Information Write In No. 748

FEMAP

Features

Modeling:


- True Windows or Motif Point and Click Graphical User Interface
- 2-D, Surface, and 3-D Automatic Meshing
- Create, Import and Edit 3-D CAD Geometry
- Direct Meshing Interface to ACIS Solid Models (AutoCAD, MicroStation, Solid Edge, TriSpectives)
- Support for Static, Modal, Buckling, Steady State and Transient Heat Transfer, Nonlinear, Frequency and Transient Response

PostProcessing:

- Animations, Color Contours, Vector Plots, Slices, Cuts, Isosurfaces and Transient Animations
- Cut and Paste Text and Graphics to other programs
- Standard and User-Defined Sorted and Culled Printed Reports
- Error Estimates

Bringing Efficiency to Finite Element Analysis

Finite Element Analysis promises a faster product design cycle, but only if you can effectively model your components and clearly visualize your results. If you want to increase the efficiency of FEA, look no further than FEMAP. Intuitive, powerful and affordable, FEMAP can help you realize the full potential of FEA. Contact us for a free 300-Node Demo Version and see why more FEA companies have chosen FEMAP as their built-in Pre- and Post-Processor.



FEMAP works with ABAQUS, ALGOR, ANSYS, COSMOS, MTAB, NASTRAN, PAL2, SAP IV, STAAD-III, STARDYNE, WECAN and many more on Windows, Windows 95, Windows NT and UNIX.

Enterprise Software Products, Inc.

P.O. Box 1172 • Exton, PA • 19341

Phone: 610-594-2454 FAX: 610-594-7579

E-Mail: femap@entsoft.com Web: <http://www.entsoft.com>

FEMAP ADVANCED MESHING MODULE utilizes ACIS software by SPATIAL TECHNOLOGY INC. All product names are trademarks or registered trademarks of their respective owners.

For More Information Write In No. 437

Control

Loss of it can be disastrous. In a high-efficiency, cost-competitive market there's no room for error. CUI Stack's line of optical and magnetic encoders gives you the quality and reliability you need to



MEL Series

maintain your competitive edge. Our innovative development has produced the new MEL series, an optical encoder with a magnetic drive. No shaft to couple, no alignment concerns, no vibration, no stress on the bearings.

If you need an optical, magnetic, mechanical, shaft, shaftless or contactless encoder, CUI Stack has the value you are looking for in:

ENCODERS



**Cui
STACK**

CUI Stack, Inc.
9640 SW Sunshine Ct.
Beaverton, OR 97005
(503)643-4899 Fax: (503)643-6129

For More Information Write In No. 438

105

Bellows Assemblies... A Performance Classic



Servometer's craftsmanship and design capabilities can provide precision Bellows Assemblies for applications where weight, strength or flexibility are a priority. The exceptional life, extreme sensitivity and high flexibility of our bellows has greatly influenced their usage within the Instrumentation, Laser, Medical and Aerospace Industries.

- Can be soldered or welded to a leak tightness of less than 1×10^{-9} cc/sec.
- Pressures of 5000 PSI or higher
- Variable Wall Thicknesses
- Extremely low spring rates



Call for a
free sample
and Brochure

SERVOMETER®

501 Little Falls Road
Cedar Grove, NJ 07009

Fax (USA): (800) 785-0756
Fax: (201) 785-0756
Tel: (201) 785-4630

For More Information Write In No. 426

Shock & Vibration Damping.

Sorbothane® patented visco-elastic material absorbs and dissipates unwanted energy and outperforms rubber and other materials by providing:

- Impact Absorption
Vibration Isolation
- Sound Damping
- Excellent Memory
- Quick & Cost-Effective Custom Molding

The Solution to all your energy dissipation needs.

For a free brochure and
prototype sample.
330.678.9444

Sorbothane Inc.

2144 State Route 59, PO Box 178, Kent, Ohio 44240
330.678.9444 Fax: 330.678.1303



For More Information Write In No. 440


New on the Market

Product of the Month



FieldWorks, Eden Prairie, MN, has introduced the FW7600 Field WorkStation™ rugged lap-top computer, which features 100 MHz 486 or Pentium processors. The computer operates on AC, battery, or 12V DC input power and includes multiple slots: one PCMCIA slot and three ISA slots for the standard model; one PCMCIA plus three ISA or three PCI slots (or any combination of the two) for the Pentium model. It weighs 14.7 pounds, and features a sealed Field MousePad pointing/drawing device, integral CD-ROM drive, and a one-piece chassis that meets military standards for shock and vibration.

For More Information Write In No. 700



The Model 276 pressure transducer from Setra Systems, Acton, MA, features a variable-capacitance sensor, which provides high thermal expansion coefficient and low mechanical hysteresis. The device is available with 0.1 or 0.2% accuracy and a 1/8" NPT pressure connection for use in industrial and aerospace applications.

For More Information Write In No. 701



Meritec, Painesville, OH, has introduced MSJ™ terminated connectors for cable routing requirements in LCDs and printed circuit boards. The cable assembly is designed for critical mechanical applications and is available with 31 or 41 connectors, with or without pull-tabs.

For More Information Write In No. 702

The K4 Series of sealed toggle switches from Otto Controls, Carpentersville, IL, feature front panel snap-in mounting and illuminated function indication. The single- and double-pole switches are available in two- and three-position circuit combinations for use in severe conditions in equipment, industrial control, and marine applications.

For More Information Write In No. 705


Parity Systems, Los Gatos, CA, offers the EtherStor™ intelligent storage controller, which increases network storage capacity without adding a workstation or server. It provides direct attachment of SCSI storage devices to any Ethernet network that uses UNIX or Netware protocols and supports up to 56 Gb of disk space or seven CD-ROM drives.

For More Information Write In No. 704



The HLE80 linear positioning drive from Parker Hannifin Corp., Daedalus Division, Harrison City, PA, is a low-mass cartridge positioned within an extruded aluminum profile. The modular component is available with a range of stepper and servo motors and allows configuration of multi-axis systems for automation applications.

For More Information Write In No. 703




Omega Engineering, Stamford, CT, offers the DAS-1800 Series plug-in boards for high-speed data acquisition in Windows or DOS on IBM-compatible computers. They feature 64 single-ended inputs of 32 differential inputs at up to 333 ksamples/second or 100 ksamples/second. The boards plug into a 16-bit AT-style slot.

For More Information Write In No. 706

New on the Market

Methode Electronics Interconnect Products Division, Rolling Meadows, IL, has introduced a 1.0 mm **surface mount header and connector system**, which provides maximum space utilization for high-density circuits. It is available with 4 to 60 circuits and features industry-standard platings.

For More Information Write In No. 707



ICEBrite™ VGA electroluminescent **flat panel displays** from Planar Systems, Beaverton, OR, are available in 10.4", 8.1", and 6.4" diagonal sizes. They feature 640 x 480-pixel formats and produce a high-contrast visual image tolerant to ambient light. The displays feature response time of less than 1 millisecond, a viewing angle of more than 160°, and a display life of more than 120,000 hours.

For More Information Write In No. 708

Monarch Instrument, Amherst, NH, has introduced Data-Chart® 3000, a one- to six-analog input series of **paperless recorders/data acquisition systems** for process monitoring, instrumentation, and recording. The systems feature up to 12 channels of information and touchscreen control. Data is stored simultaneously in an internal buffer and either a PCMCIA card or 3.5-inch floppy disk.

For More Information Write In No. 709




Exergen Corp., Watertown, MA, has introduced the IRT/c.3X **non-contact temperature sensor** with a sensing range of -40 to 650° C and a 17° field of view. The sensor fits most temperature control systems and includes a built-in air purge for operation in rugged environments.

For More Information Write In No. 711

A line of ultraviolet, x-ray, and particle **diamond radiation detectors** is available from Alameda Applied Sciences Corp., San Leandro, CA. They use bulk photoconductivity to provide <1 ns rise-time measurements of photons, electrons, ions, and neutrons. They are available in SMA, ultraminiature, and Type N mounts.

For More Information Write In No. 710



The GSAF-10 Gold Series **analog low-pass filter** from Alligator Technologies, Costa Mesa, CA, is installed between sensors and an A/D converter board in data acquisition systems. The fixed-frequency board provides one differential-input channel and can be mounted on the benchtop or plugged into a 21-channel back-panel.

For More Information Write In No. 712

Life Sciences, St. Petersburg, FL, offers the EnviroScreen, a computer-linked **optoelectronic analyzer**, which is a portable, spectrograph-based instrument for detection and measurement of metals, volatile organic compounds, and other organic and inorganic substances. It measures absorbance, reflectance, and fluorescence over the 200-2000 nm range.

For More Information Write In No. 713




Hewlett-Packard, Palo Alto, CA, has introduced a two-channel **digital-storage oscilloscope** that features a 1-gigasample/second sample rate and 500 MHz bandwidth. It supplies automatic measurements of frequency, voltage, pulse width, and rise time for engineers and technicians working with mixed-signal circuits.

For More Information Write In No. 714

The Model APP-100APR **computer-controlled automated pressure regulator** from Advanced Pressure Products, Ithaca, NY, controls gas pressure remotely without operator assistance. For use in laboratories and process control applications, the regulator controls system pressure automatically from a computer or other controller.

For More Information Write In No. 715

ELECTROID Aerospace Components



Electroid's Hi-Rel aerospace brakes, failsafe brakes, clutches and solenoids are included on every major aircraft from the Blackhawk Helicopter to the Space Shuttle, the Airbus A300 to the Boeing 777.



ELECTROID COMPANY

A DIVISION OF VALCOR ENGINEERING CORP.
45 Fadem Road, Springfield, NJ 07081
201/467-8100 Fax: 201/467-5656

For More Information Write In No. 441

SMOOTH MOVES!! WITH BS&A CO. LINEAR MOTION PRODUCTS




FREE CATALOG-DESIGN GUIDES

BALL SCREWS & ACTUATORS CO.
3616 SNELL AVE. SAN JOSE, CA. 95136
BS&A FAX (408) 629 2620

1-800-882-8857 OR (408) 629-1132

MAGNE

Magneclutches®, Magnebrakes® and Electronic Controllers



Precision Motion Control Systems

CALL MAGNE TODAY
314/968-9500


9380 Watson Industrial Dr. • St. Louis, MO 63126
314/968-9500 • Fax 314/968-3030

- **TORQUE**
Independent of speed—Linear torque vs. current
- **TENSIONING**
Precisely controllable continuous slip
- **STEPPING**
Ultra fast response
- **LIFE**
Virtually unlimited—No friction pads to wear or adjust

For More Information Write In No. 443

FAST ELECTROMAGNETICS

Gemini



Fast 2D magnetostatics simulation at a budget price from Infolytica. New Gemini for Windows™ incorporates neural network-based solutions, LDCG solvers, the Open Boundary Technique, and "tunable Maxwell stress" calculations. Call 1-800-492-6464 for full details and our promotional price.

INFOLYTICA: THE E-M SPECIALISTS

FROM INFOLYTICA


SAVE PROTOTYPING TIME AND COSTS with Infolytica's Gemini and MagNet 2D and 3D products on PCs & UNIX platforms.



USA/Intl - Infolytica Corporation
tel: (514) 849-8752 fax: (514) 849-4239
EUROPE - Infolytica Limited
tel: 44 123-583-3288 fax: 44 123-583-3141
JAPAN - ADITECH Corporation
tel: (03) 5276-5291 fax: (03) 5276-5293


For More Information Write In No. 444

New on Disk




Ricoh Corp., Software Research Center, San Jose, CA, has introduced Windows version 5.0 of DesignBase™ solid and surface modeling software, which provides program development, on-line documentation, a graphical developer's interface, and 2000 different functions. Designs can be created and modified directly or through dimensional parameters.

For More Information Write In No. 720



ICEMatrix parametric AutoCAD editing software from ICEM Technologies, Division of Control Data Systems, Arden Hills, MN, provides dimension-driven geometric editing of any 2D AutoCAD drawing. It automatically recreates a drawing whenever dimensions are changed and runs entirely in AutoCAD, requiring no special drawing preparation. The software costs \$487 and runs with AutoCAD R12 and 13 in DOS, Windows, or Windows NT.

For More Information Write In No. 721



Intergraph, Huntsville, AL, has introduced Imagineer Technical™, a 2D drawing and concept design tool for Windows that allows engineers, designers, scientists, and inventors to perform 2D sketching, concept design, and project review. It features 32-bit drawing power, compatibility with AutoCAD and MicroStation, and allows linking/embedding of drawings in word processing, spreadsheet, and presentation files. The program requires no formal training and is available at an introductory price of \$279.

For More Information Write In No. 729


Cadra® version 10 CAD/CAM/CAE tools from Adra Systems, Chelmsford, MA, integrates separate modules for design drafting, numerical control, solids modeling, electrical control, and power systems design. It is compatible with Windows, DOS, and UNIX platforms, and can take data created in any form from a translator and manipulate it as native data.

For More Information Write In No. 723



Cyco International, Atlanta, GA, offers AutoManager WorkFlow document management software for drawings, spreadsheets, memos, engineering change orders, and scanned images. Documents and related data can be tracked, retrieved, marked-up, and verified within a workgroup or across an enterprise. It is available for DOS or Windows, works with various CAD programs, and costs \$799 per license.

For More Information Write In No. 722




Computational Engineering International, Research Triangle Park, NC, has released EnSight™ 5.5 engineering postprocessing software, which postprocesses and animates up to eight datasets simultaneously. In addition to standard planar clipping, the program provides clipping against quadric surfaces such as cylinders and cones. Designed for computational engineers, it can postprocess data from most commercial analysis packages. A perpetual license starts at \$8000.

For More Information Write In No. 731

Compunex, Southfield, MI, has released IGES/STL rapid prototyping enabling translation software, which provides bidirectional translation between IGES and STL data formats. The program improves data translation quality by repairing gaps between adjoining surfaces, warped surfaces, and incorrect surface normals, allowing STL files to be used with rapid prototyping machines. It is available in Windows or DOS formats.

For More Information Write In No. 724

New on Disk



AnalyzIR+ Windows-compatible **image analysis and report generation software** from FLIR Systems, Portland, OR, allows users to read popular file formats and legacy files captured from infrared cameras. The program can track images and temperatures over time and uses spatial calibration to determine the length and area of objects. The cost is \$3000.


For More Information Write In No. 725

Industrial Systems, Bothell, WA, has released UNIX version 3.2 of **CIM/21® process information management software**, which features display and analysis capabilities. Users can graphically monitor system performance, perform backups, and manage scanning and history subsystems and system security. Time series data such as temperatures, flows, and pressures can be viewed in batch context.

For More Information Write In No. 726

Eagle virtual systems integration software from Eagle Design Automation, Beaverton, OR, was designed for PC-based Windows NT embedded system development and consists of two components: the Virtual Product Console (VPC) and the Virtual Software Processor (VSP). VSPs are software models of popular microprocessors for use with the VPC, which links the microprocessor descriptions with application software code. Prices start at \$40,000.

For More Information Write In No. 728




The MathWorks, Natick, MA, has introduced **MATLAB Compiler and MATLAB C Math Library technical computing modules**. MATLAB Compiler allows users to automate the conversion of MATLAB code to portable ANSI standard C or MATLAB-callable executable functions; MATLAB C Math Library makes MATLAB math functions accessible as a cross-platform foundation for standalone applications. Both programs are available for Windows and UNIX platforms. Compiler prices start at \$895; Library prices start at \$595.

For More Information Write In No. 727

ENVI™ image processing software from Research Systems, Boulder, CO, was designed for scientists who analyze and visualize remote sensing data. Featuring array-based image math and an annotation package, it allows users to read, display, analyze, and output any spaceborne or aircraft digital imagery. Ground-based and laboratory spectral measurements also can be imported, manipulated, and analyzed. It operates on UNIX and Windows platforms on a Macintosh or PC.

For More Information Write In No. 730



Algor, Pittsburgh, PA, has introduced **Integrated Plant Package (IPP) software** for designing, engineering, and analyzing **piping systems, pressure vessels, and heat exchangers**. The package consists of three tools: Pipepak piping system structural analysis program; FE/Pipe finite-element analysis program; and BOS/Fluids, which simulates how fluid phenomena affect piping systems.

For More Information Write In No. 732



MANTA 4.0 visual product data management software from B.A. Intelligence Networks, Southfield, MI, is an upgrade that supports design and engineering through a product life cycle via visual presentation of product-related data. Users can track, control, and manage tasks and data involved in product design.

For More Information Write In No. 733

ESM Software, Hamilton, OH, has released **MAPP engineering materials property database software** that interfaces with the ASM International® Mat.DB® engineering materials properties databases. The program allows access to mechanical, physical, and chemical properties of more than 6000 commercial alloys and polymers from a Windows or Macintosh platform. The cost is \$495.

For More Information Write In No. 734

CLOSE THE GAP!

SEAL MASTER INFLATABLE SEALS



OVERCOME TROUBLESOME DESIGN PROBLEMS



Inflatable seals in a wide range of sizes and configurations are used anywhere a positive seal is needed between opposing surfaces. It's the innovative solution for many difficult applications. Design assistance available.

SEAL MASTER CORPORATION
INFLATABLE SEALS AND OTHER CUSTOM RUBBER PRODUCTS
368 MARTINEL DRIVE • KENT, OH 44240-4368 USA
(216) 673-8410 • FAX (216) 673-8242

For More Information Write In No. 445

Full Featured Expansion Tray for Notebook Computers



ONSITE INSTRUMENTS
230 E. Caribbean Dr., Sunnyvale, CA 94089

Tel (408) 752-1640 Fax (408) 752-1625

USE WITH SELECTED NOTEBOOK COMPUTERS FROM
IBM Thinkpad, PANASONIC, AST, & GRID

- From two to eight full-size AT-bus expansion slots
- Operate from 10 to 30 volt DC or 110 to 240 volt AC
- Rugged metal case • Power for internal peripherals
- Video, Parallel, RS-232, Mouse, and Keyboard ports

IDEAL FOR MOBILE, PORTABLE, AND MARINE APPLICATIONS

For More Information Write In No. 446

SoftwareWedge™

Automatically inputs any serial data directly into any PC application.



Serial I/O

Communicate With:
Industrial & Lab.
Instruments ...
Gages ...
Balances ...
PLCs ... etc. ...
Any Serial Device!

- Real-Time Serial Data into Any Application — Excel, VB, Quattro, Lotus, Access, Stat. software, etc.
- Full data acquisition and instrument control.
- Risk free 90 day, money-back guarantee.

Now Windows, DOS, NT & Windows 95 applications

For Free Literature, Call
800-722-6004

TAL TECHNOLOGIES, INC.
2027 Wallace St., Philadelphia, PA 19130
Tel: 215/763-7900 Fax: 215/763-9711
E-mail: tal@taltech.com
Home page: <http://www.taltech.com>

TAL
InstrumentAL Software™

For More Information Write In No. 580




FREE!
130
Page
Catalog

"Optics
for
Industry"

Free 130 page product catalog from Rolyn, world's largest supplier of "Off-the-Shelf" optics. 24-hour delivery of simple or compound lenses, filters, prisms, mirrors, beamsplitters, reticles, objectives, eyepieces plus thousands of other stock items. Rolyn also supplies custom products and coatings in prototype or production quantities. **ROLYN OPTICS Co.**, 706 Arrowgrand Circle, Covina, CA 91722-2199, (818)915-5707, FAX (818)915-1379

For More Information Write In No. 581

NURBS Geometry Software



Nlib 2.0 is a library of ANSI C functions for creating and processing NURBS curves and surfaces. The functions are easy to call and no knowledge of NURBS mathematics is required. Nlib 2.0 is the ideal kernel upon which to build geometry-based applications. Source code, multi-users, no royalties. Maintenance, consulting and training.

GeomWare, Inc. PH/FAX 903 839-5042

For More Information Write In No. 582

256 MBYTE Image Memory
Dual TMS320C40 Coprocessors

4MEG VIDEO™ Model 12
Flexible Image Capture, Processing, & Display Board for the PC

- 4-31,000 Pixels per Line
- 1-16,000 Lines/Image
- 2-50MHz Sampling & Display Rate
- Configurable 4-256 MB Image Memory
- On-Board DSP
- Programmable Non-Standard, RS-170, & CCIR Video Formats
- Area or Line Scan Input
- Extensive Software

EPIX
381 Lexington Drive
Buffalo Grove, IL 60089
Tel 847 465 1818
Fax 847 465 1919
epix@epixinc.com
©1999 - EPIX, Inc. USA

For More Information Write In No. 583

Windows 95
Motion Control Software

Linear Motion StepUp 95 Rotational Motion

- Move To **Intuitive, User Friendly**
- Pause **Complete Unit Auto Conversion**
- Special **Graphical Position Display**
- Label **Controls Multiple Stepmotors**
- Pause **Limitless Smooth Distance and Rotational Capabilities**
- Cycle to **Enter Complete Motion Profiles in ANY Units of Distance and Time, and Walk**

The Mellen Company
800-633-6115
R.F.D. #5 Penacook, N.H. 03303 mellen@kear.tdsnet.com

For More Information Write In No. 584

FREE CATALOG

Over 500 PAGES of Tooling Components!

- Jig & Fixture Bases
- Chuck Jaws
- Modular Fixturing
- Toggle Clamps
- Drill Jig Bushings
- SWIFTSURE Power Workholding

ORDER TODAY!

Carr Lane MANUFACTURING CO.
4200 Carr Lane Ct., P.O. Box 191970
St. Louis, Missouri 63119-2196
Phone: 314-647-6200, FAX: 314-647-6736

For More Information Write In No. 585

Control Practically Anything. from \$79.

LCD
RELAYS
ADC/DAC
RS232
RS485
SRAM
FLASH
EPROM
RTC
TIMERS
BATTERY
WATCHDOG
DMA
PIO

Our miniature controllers are ideal for machine control and data acquisition. Easy to program with our Dynamic C. Save time and money. Call for your free demo disk today!

30 I/Os
Little Star \$185

ZWORLD ENGINEERING
1724 Picasso Ave.
Davis, CA 95616
916.757.3737
916.753.5141 FAX
<http://www.zworld.com>

For immediate information, call our 24-Hr AutoFAX 916.753.0618 from your FAX. Request catalog #18.

For More Information Write In No. 586

Data acq and signal conditioning IN ONE PACKAGE!

- ◆ Replaces chart recorders & scopes
- ◆ Accepts plug-in amplifiers
- ◆ Connects to your PC's printer port
- ◆ Fast 250,000 Hz sample rates
- ◆ Ready-to-run recording software

Forget multiple boxes. Set aside your old, traditional instruments. Our products take you from sensor to final results with computer-precision. Our DI-500 portable, rack mounted, or desktop hardware measures TCs, rtds, vac, vdc, rpm, and strain—virtually any sensor used in industry—with safe, 1000 V isolation per channel. Our ready-to-run WinDaq software allows you to acquire, display, record, playback, and analyze your toughest waveforms with more speed and flexibility than you've ever seen on a PC.



CALL FOR FREE INFORMATION




DATAQ INSTRUMENTS

800-553-9006

For More Information Write In No. 587

Copyright © 1995 by Dataq Instruments, Inc.

100 MFLOP OEM-DSP \$889 QTY 100



BLACKTIP

- Analog Devices ADSP-2106x SHARC floating-point DSP
- Up to 512Kx48 external SRAM
- Flexible high-speed I/O site
- Two external link ports
- Half-length ISA card
- Free evaluation packages from Hyperception, Ixthos, and Wideband Computers with purchase of development SW

BITWARE RESEARCH SYSTEMS
The SHARC tamers.


800-848-0436

33 North Main Street • Concord, NH 03301
FAX: 603-226-6667 • E-Mail: bitware@bitware.com

For More Information Write In No. 588

POSITION ACCURACY to ±0.5 arc second!

Inductosyn® transducers provide absolute or incremental position data to ±0.5 arc second (Rotary) or ±40 microinches (Linear). Resolution to 26 bits.




For brochure, call 914/761-2600 or fax 914/761-0405.

FARRAND CONTROLS
DIVISION OF RUHLE COMPANIES, INC.
99 Wall Street, Valhalla, NY 10595

For More Information Write In No. 589

ARE YOU STILL TRYING TO MEASURE VERY THIN GAPS THE HARD WAY?



Capacitec HPS Series of thin (back to back) sensors can measure gaps as small as 0.0085" (.22mm) inboard 84" (2133.6mm) with accuracies of 0.0003" (7.6µm), without scratching delicate surfaces.

Capacitec

P.O. Box 819, 87 Fitchburg Rd., Ayer, MA 01432 U.S.A.
Tel. (508) 772-6033 • Fax (508) 772-6036

For More Information Write In No. 590

ACCEL Technologies, Inc.	(RAC 462)	COV Ila	(RAC 323)	67	
ACL Inc.	(RAC 416)	80	Lauren	(RAC 405)	36, 104
ACR Systems	(RAC 407)	40	Light Machines Corp.	(RAC 336)	68
Adaptive Research	(RAC 524)	29	LPKF CAD/CAM Systems Inc.	(RAC 480)	20a
Algor, Inc.	(RAC 525, 613, 319)	9, 75, 104, 66	Lumitex, Inc.	(RAC 459)	1a
AlliedSignal Instrument Systems	(RAC 461)	21a	Macintosh Tech Center	(RAC 675-692)	72-73
Aluminum Shapes Inc.	(RAC 553)	25	MacNeal-Schwendler Corporation	(RAC 561)	71
American Varisair	(RAC 418)	99	Magne	(RAC 443)	106
Ametek, U.S. Gauge Division	(RAC 313)	66	Master Bond Inc.	(RAC 430)	76
AMP		104	MathWorks, Inc.	(RAC 606)	follows 16, 17
Amphenol Canada Corp.	(RAC 330, 332)	67	The Mellen Company	(RAC 584)	110
AMTEC	(RAC 474)	18a	Meridian Laboratory	(RAC 448)	112
Analog Devices	(RAC 537)	4	Metrum, Inc.	(RAC 599)	69
Ansoft Corporation	(RAC 463)	3a	MicroSim	(RAC 468)	13a
APD	(RAC 320, 321)	66	Microsoft	(RAC 502)	53
Applied Microsystems Corporation	(RAC 324)	67	Miller-Stephenson	(RAC 411, 429)	55, 93
Armco Products, Inc.	(RAC 327)	67	Minco Products, Inc.	(RAC 670-673)	85
Astro-Med, Inc.	(RAC 527)	57	Mitsubishi Electronics America, Inc.	(RAC 801, 814)	56, 14b
Aurora Bearing Company	(RAC 417)	80	National Instruments Corporation	(RAC 550)	COV II
Autodesk, Inc.	(RAC 409)	30-32, 46-47	National Technology Transfer Center	(RAC 410)	50
Ball Screws & Actuators	(RAC 442)	107	New England Affiliated Technologies	(RAC 805, 812, 341)	12b, 13b, 68
Bell Technologies, Inc.	(RAC 326)	67	Norder, Inc.	(RAC 339)	68
Bitware Research Systems	(RAC 588)	111	Novamet Specialty Products Corporation	(RAC 652)	45
Capacitec	(RAC 590)	111	NSK Corporation	(RAC 802, 815)	7b, 15b
Carr Lane Manufacturing Co.	(RAC 585)	110	NuLogic	(RAC 808)	6b
Circuit Specialists, Inc.	(RAC 329)	67	Numerix Software Corporation	(RAC 660)	2
CLEO '96	(RAC 612)	64	Ohmite Manufacturing Company	(RAC 427)	86
Cole-Palmer Instrument Company	(RAC 325)	67	Oldlyne	(RAC 800, 816)	3b, 15b
CUI Stack, Inc.	(RAC 438)	105	Omega Engineering, Inc.	(RAC 625-629, 300-308)	1, 65
Cybernetics	(RAC 504, 603)	7, 87	Onsite Instruments	(RAC 445)	109
Daedal Division, Parker Hannifin Corp.	(RAC 820)	10b	Paroscientific, Inc.	(RAC 449)	100
Data Translation	(RAC 530)	15	Parker Hannifin, Compumotor Div.	(RAC 803, 817)	9b, 16b
Dataq Instruments, Inc.	(RAC 587)	110	Penn Engineering & Manufacturing Corp.	(RAC 414)	62
Datum Inc., Bancrom Division	(RAC 435)	94	PIC Design	(RAC 317)	66
De-Sta-Co	(RAC 311)	66	Pittman	(RAC 403)	21
Dewent North America	(RAC 334)	68	Poly-Optical Products, Inc.	(RAC 451)	2a
Digi-Key Corporation	(RAC 604)	3	PSC Lamps	(RAC 340)	68
DSM Desotech Inc.	(RAC 415)	63	Quantum Composers, Inc.	(RAC 331)	67
DuPont	(RAC 413)	61	Quatech	(RAC 406)	38
Edmund Scientific Co.	(RAC 458)	1a	RAG Electronics	(RAC 508)	5
Electroid Company	(RAC 441)	107	Research Systems	(RAC 577)	13
Elgiloy Limited Partnership	(RAC 436)	102	RGB Spectrum	(RAC 400)	12
Elmwood Sensors	(RAC 425)	92	Rolyn Optics Co.	(RAC 581, 310)	110, 66
Endevco	(RAC 464)	5a	Sanyo	(RAC 469)	COV Ila
Enterprise Software Products, Inc.	(RAC 437)	105	Schneeberger, Inc.	(RAC 806)	4b
Envoy Data	(RAC 333)	67	Science Accessories	(RAC 408)	42
Epix, Inc.	(RAC 583)	110	Seal Master Corporation	(RAC 445)	109
Equipito Electronics Corporation	(RAC 328)	67	Sensor Developments Inc.	(RAC 444)	22
Evans	(RAC 444)	62	Sensory	(RAC 460)	21a
Farrand Controls	(RAC 589)	111	Servomotor Corporation	(RAC 426)	106
Fieldworks Inc.	(RAC 470)	16	Sigma Systems	(RAC 338)	68
Firestone Industrial Products Co.	(RAC 804, 811)	11b, 13b	SL Corporation	(RAC 420)	68
Fluke Corporation	(RAC 465)	7a	SoftWorld International	(RAC 322)	67
Gage Applied Sciences Inc.	(RAC 610)	43	Sony Magnetics America, Inc.	(RAC 466)	9a
General Extrusions, Inc.	(RAC 439)	92	Sorbothane Inc.	(RAC 440)	106
GeomWare Inc.	(RAC 582)	110	Specialized Products Co.	(RAC 380)	19a
Gould Instrument Systems, Inc.	(RAC 539)	COV IV	StarcoSwitch	(RAC 314, 315)	66
Grayhill Inc.	(RAC 455, 456)	15a, 17a	Stevens Products	(RAC 318)	66
Heidenhain Corporation	(RAC 614)	83	Sun Microsystems, Inc.	(RAC 567)	23
Hewlett-Packard Company	(RAC 534)	follows 48, 49	The Swagelok Companies	(RAC 540)	77
Hoerbig-Origa	(RAC 819)	10b	Synrad	(RAC 520)	95
Igus, Inc.	(RAC 591)	111	3M MMC	(RAC 419)	101
Illbruck	(RAC 447)	112	T.A.L. Technologies, Inc.	(RAC 580, 381)	110, 19a
Illinois Capacitor, Inc.	(RAC 382)	19a	TEC Products and Lab Services	(RAC 471)	20a
Infolytica Corporation	(RAC 444)	108	TekSoft	(RAC 404, 335)	34, 68
Inframetrix	(RAC 611)	51	Tescor Corporation	(RAC 412)	59
Integrated Engineering Software	(RAC 607)	27	Toshiba	(RAC 452)	8a
Integrated Systems, Inc.	(RAC 609)	97	Trim-Lok	(RAC 337)	68
Intel Corporation		10-11	Vector Fields	(RAC 316)	66
Intelligent Motion Systems, Inc.	(RAC 813)	14b	Velmax, Inc.	(RAC 401)	99
Interface	(RAC 432)	91	Visual Numerics, Inc.	(RAC 572)	COV III
Intergraph Corporation	(RAC 421-422)	7b-79	Warner Electric	(RAC 635-641, 818)	39, 16b
IOtech, Inc.	(RAC 615-618)	41	Wattlow	(RAC 505)	89
Iscan	(RAC 431)	76	Wright Line	(RAC 434)	91
Janco Corporation	(RAC 312)	66	Xytron Corporation	(RAC 807)	6b
Kaman Instrumentation	(RAC 428)	98	Z World Engineering	(RAC 585)	110
Kelley	(RAC 467)	11a	Zircar Products, Inc.	(RAC 402)	19
Kerk Motion Products, Inc.	(RAC 809)	8b			

FREE CABLE CARRIER CATALOG



CHAINFLEX cables for flexing power cable applications such as in cable carriers or cable reels. Chainflex cables offer long life and small bend radii due to special design features. Numerous sizes are available from stock in standard, shielded and twisted pair versions. Catalog offers technical and engineering data.

Igus, Inc.,
POB 14349, E. Providence,
RI 02914 • 800-521-2747

For More Information Write In No. 591

Official NASA Tech Briefs Cap




Sporty poplin cap perfect for golf or any outdoor activity. Red and black NASA Tech Briefs logo on white cap. Size adjustable. \$9.95

Name _____
Address _____
City _____
State _____ Zip _____

Mail with payment to: Associated Business Publications, 317 Madison Avenue, Ste 921, New York, NY 10017. For credit card orders call (212) 490-3999.

It doesn't take a rocket scientist to control noise. No offense.



SONEX
The new standard.

illbruck's family of SONEX products is setting new standards, with completely **FIBER-FREE** acoustical solutions in exclusively **CLASS 1** materials. Our new and improved SONEX combines exceptional absorption properties with Class 1 fire-resistant materials for the safest environment. You'll get peace of mind, as well as peace and quiet. Send today for a free brochure.

illbruck
Minneapolis, Minnesota
1-800-662-0032
(612) 520-3620

For More Information Write In No. 447

ROTOCON HIGH PERFORMANCE ROTARY CONTACTS

**THERMOCOUPLES,
RTD's, LVDT's
STRAIN GAUGES,
1 to 100 contacts!**



Unlike conventional slipping designs, the unique ROTOCON Sealed Mercury Rotary Contacts are low noise, low resistance, zero maintenance links between stationary and rotating components.

- Zero Electrical Noise
- Low And Stable Resistance
- Compact Size
- Zero Maintenance
- Environmentally Sealed
- Rugged And Reliable
- Unaffected By Vibration
- Mount In Any Orientation

A variety of standard and custom ROTOCON models are available to fit your mounting configuration, rotation speed, and current requirements (up to 2000 Amps!).

"Try Before You Buy"

Call:
800-837-6010
or 608-836-7571 (FAX 608-831-0300 TELEX 754381)



meridian laboratory

P.O. Box 620156, 2415 Evergreen Road, Middleton, WI 53562-0156

For More Information Write In No. 448

The Technology Connection

To Advertise Call (800) 944-NASA

Opportunities for Partnership & Commercialization

Shaped Elongate Crystals:
Sapphire, YAG, Substrates for High
Tc Superconductors - Fibers, Tubes,
Sheets, Custom-Made Materials

Contact: Richard Ventura,
Technologist
Advanced Crystal Products
617-933-4626 FAX 617-932-9239

**Efficient Electrical Impedance
Tomography Using Boundary
Element Techniques**

Contact: Dr. Ramani Duraiswami,
Manager
Dynaflo, Inc.
301-604-3688 FAX 301-604-3689
E-mail: info@dynaflo-inc.com

Inventors Marketplace

"How To Offer Your Invention For Sale."

We have helped hundreds of inventors and showed them how to offer their inventions for sale to business all over the world. No cost.

Call 1-800-537-1133. Kessler Sales Corp.,
C-47-6, Fremont, Ohio 43420.

Davison & Associates offers customized development, patenting and licensing with proven results. Free information package: 1-800-677-6382

Apollo 13 Commemorative T-Shirt

The **Apollo 13 Commemorative T-shirt** features a gorgeous full-color rendition of the official Apollo 13 mission emblem (the "Horses of Apollo") superimposed with dramatic effect on a black T-shirt. Adult sizes: M, L, XL, XXL. \$13.95 + \$5 s&h. Mail with payment to: Associated Business Publications, 317 Madison Avenue, Suite 921, New York, NY 10017. Credit card orders call (212) 490-3999.

Engineering Catalog

80/20 Inc. FAST
Manufacturers of The Industrial Erector Set®
T-SLOT ALUM. EXTRUSIONS
for Machine Frames, Work
Stations, Shop Projects,
Guarding, Enclosures, Etc.
Free catalog
with over 1400 building components!
Internet - <http://www.fwi.com/8020>
(219) 248-8030 • FAX 248-8029
1701 South 400 East • Columbia City, IN 46785

Tech Transfer Meetings

"Partnering For A Better Tomorrow"

Federal Laboratory Consortium
Spring National Meeting

May 6-9, 1996
Red Lion Hotel
Seattle-Tacoma International Airport

The FLC's 600+ member labs and agencies offer a wealth of technology transfer and partnership opportunities. Discover how you can take advantage of the nation's greatest R&D resource!

- Meet technology transfer experts and award-winning scientists and engineers
- Listen to leaders from world-class organizations such as Microsoft, Boeing, and Weyerhaeuser describe the future of technology development in their sectors
- Learn from successful technology partnerships like the one that built the Boeing 777

For a complete registration package contact: Federal Laboratory Consortium, PO Box 545, Sequim, WA 98382-0545; phone: (360) 683-1005; fax: (360) 683-6654. Space is limited, so act today.

NASA Tech Briefs, ISSN 0145-319X, USPS 750-070, copyright© 1996 by Associated Business Publications Co., Ltd. Copyright is not claimed for the individual "tech briefs" contained in this publication. The U.S. Government has a paid-up license to exercise all rights under the copyright claimed herein for government purposes. NASA Tech Briefs is published monthly by Associated Business Publications Co., Ltd., 317 Madison Ave., Ste. 921, New York, NY 10017-5391. Editorial, sales, production and circulation offices at 317 Madison Ave., New York, NY 10017-5391. Subscription for non-qualified subscribers in the U.S., Panama Canal Zone, and Puerto Rico, \$75.00 for 1 year \$125.00 for 2 years; \$200.00 for 3 years. Single copies \$10.00. Foreign subscriptions one-year U.S. Funds \$195.00. Permit by check, draft, postal, express orders or VISA, MasterCard, or American Express. Other remittances at sender's risk. Address all communications for subscriptions or circulation to NASA Tech Briefs, 317 Madison Ave., New York, NY 10017-5391. Second Class postage paid at New York, NY and additional mailing offices.

POSTMASTER: please send changes to NASA Tech Briefs, P. O. Box 10523, Riverton, NJ 08076-0523.

Serious about simplifying your data analysis?







IMAGE TOOL
Display your data as
8-bit or 24-bit images




PLOT TOOL
Plot data arrays as
lines, markers or a
combination of the two




CONTOUR TOOL
Contour 2D data with
straight or splined lines



3D SURFACE TOOL
Visualize, rotate and
shade your data as a
3D surface plot



HISTOGRAM TOOL
Visualize quantitative
trends in large data
sets



PREVIEWER TOOL
Read ASCII data files
and interactively select
headers, records, and
fields for the data

PV-WAVE:NAVIGATOR™

*Rapid application development for
data analysis just got easier!*

The PV-WAVE:NAVIGATOR Graphical User Interface (GUI) offers a foundation of pre-engineered tools for easy data analysis. And with PV-WAVE's reusable objects, every tool can be easily customized and extended to meet your ever-changing design and analysis requirements.

Start your analysis with the Navigator, then add your own specific tools with the smart, 4GL programming environment of PV-WAVE®.

Now supporting multi-vendor architecture: UNIX®, OpenVMS™, Windows NT™ and Windows® 95

*Call us today for more information on other available tools.
Free technically supported evaluation upon request.*

Visual Numerics®

YOUR PARTNER IN DATA EXPLORATION

800-364-8880

WORLD WIDE WEB: <http://www.vni.com>

Telephone (713) 784-3131 ■ Fax (713) 781-9260
9990 Richmond Ave., Suite 400
Houston, TX 77042

e-mail: marketing@houston.vni.com
CompuServe: go pwwave (at any! prompt)

London + 44(0) 1753-790600 ■ Paris + 33 1 46 93 94 20


Stuttgart + 49 711-13287-0

Taiwan 886 (0) 2-727-2255 ■ Tokyo 81-3-5689-7550

PV-WAVE is a registered U.S. trademark of Visual Numerics, Inc. Rapid Application Development Environment is a trademark of Visual Numerics, Inc. AD 9631NASA

For More Information Write In No. 572

New Gould COBRA16 Real-Time Analysis System



Gould's new COBRA16 combines a real-time recording system with the power of real-time mathematical calculations to provide real-time results. Its Windows 95® control system allows real-time color monitoring of raw or computed data. With its extensive post-acquisition analysis program, the COBRA16 delivers unparalleled performance in a portable package.

Real-Time Results

If every test problem were the same, the answers would be simple.

Now, Gould's new Real-Time Math Module lets you create a unique mathematical solution to your special test problem. This new module converts real-time raw data to useful information at the time and place of acquisition. Instantaneous answers make the most effective use of your valuable test cell resources, providing savings which go directly to your bottom line.

Add Gould's powerful Real-Time Math Module, the heart of our new COBRA16 System, to any existing TA11 or TA6000 product to provide powerful, enhanced functionality. Perform real-time calculations at 50,000 samples per second. Use resultant math outputs as inputs to additional math functions, providing for complex equations. Trigger acquisition using derived results, raw data or combinations. To ensure easily interpreted results, define your input units to provide real-world values; such as PSIG or Watts.

If you have uncommon problems, call your Gould representative for some surprisingly uncommon solutions.

$$\sqrt{\left(\int \sin\left(\frac{\text{input1}}{\pi}\right) dt\right) \times e^{\text{input2}} \times \left(\frac{8.214 \times \text{input3}}{\tan^{-1}(\text{input4})}\right) \times \log(\text{input5} + 6.1)}$$

TA6000 Recording System



- Up to 64 channels • Continuously record to Hard Disk at 1 MS/sec • External high resolution color monitor • Compatible with Real-Time Math Module

TA11 Portable Recording System



- Up to 16 channels • Record transient signals to 8 Msample memory • Compatible with Real-Time Math Module

6600 Series Signal Conditioning



- Wide selection allows instrumentation to be used with strain gage, temperature, and frequency conversion transducers • The perfect complement to Gould's Real-Time Math Module

Fast Action FAX: (216) 328-7404
attention Inquires Manager,
or CALL: (800) 468-5365

☐ Have a Gould Sales Representative call me to arrange a demonstration

☐ Rush me free information on Gould's new Real-Time Math

NTB 3/96

(Please print)

Name: _____

Title: _____

Company: _____

Street: _____

City: _____ State: _____ Zip: _____

Telephone: () _____

FAX or mail coupon/photocopy (you may affix business card) to: Gould Instrument Systems, Inc. 8333 Rockside Road, Valley View, OH 44125

For More Information Write In No. 539